

[Advertisement for Bellingham Herald]

**LAKE WHATCOM WATER AND SEWER DISTRICT  
GENEVA RESERVOIR AND SVWTP PUMP HOUSE SEISMIC UPGRADES  
REQUEST FOR QUALIFICATIONS**

Lake Whatcom Water and Sewer District is requesting qualifications from qualified engineering firms for the GENEVA RESERVOIR AND SVWTP PUMP HOUSE SEISMIC UPGRADES located in Sudden Valley and Geneva in Whatcom County, Washington. Professional services include surveying, easement acquisition, pre-design, permitting, design, bidding, inspection, and construction contract administration. The District intends to select the most qualified firm for the project. Submittal requirements and project information are available at <https://lwvsd.org/2402-C>

Submittals shall be delivered by 11 am, March 12, 2024 to Attn: Greg Nicoll, Lake Whatcom Water and Sewer District, 1220 Lakeway Drive, Bellingham, WA 98229. Questions should be directed to Greg Nicoll, at 360-734-9224.

Any firm failing to submit information in accordance with the procedures set forth in the Request for Qualifications may not be considered responsive and may therefore be subject to disqualification by the District.

**LAKE WHATCOM WATER AND SEWER DISTRICT  
GENEVA RESERVOIR AND SVWTP PUMP HOUSE SEISMIC UPGRADES  
REQUEST FOR QUALIFICATIONS**

**I. INTRODUCTION**

A. This Request for Qualifications ("RFQ") outlines the information necessary to understand the consultant selection process and the required documentation a Consultant must submit. After reviewing this RFQ, any firm that determines it has the necessary expertise and experience and could successfully perform the required services may submit its Submittal, addressing the items set forth herein. A general overview of the selection process is as follows:

1. Consultants shall deliver the Submittal to the District no later than **2:00 p.m. on March 28, 2024**, after which time they will be reviewed and evaluated. The Submittal shall be delivered to:

**Lake Whatcom Water and Sewer District  
1220 Lakeway Drive  
Bellingham, WA 98229  
Attn: Greg Nicoll, District Engineer**

2. The District may, at its option, contact a Consultant and ask clarifying questions concerning the Consultant's Submittal.
3. At the District's option, the District may conduct interviews with Consultants qualifying as finalists.

B. The purpose of this RFQ is to obtain a qualified consultant team to provide professional services to design replacement and/or improvements for the Geneva Reservoir and SVWTP Pump House Seismic Upgrades project. The scope of work includes professional services for topographic surveying, pre-design, permitting, design, bidding, inspection, and construction contract administration. The District intends to select the most qualified firm for the project.

C. It is anticipated that Consultant services will be separated into three phases of work. The initial contract and first phase of work will cover topographic surveying, pre-design, and permitting. Phase two includes detailed design, specifications, cost estimates, and bidding. Phase three includes services during construction.

**II. DISTRICT SUMMARY**

A. The Lake Whatcom Water and Sewer District is a special purpose district operating under Title 57 Revised Code of Washington. Originally formed in 1968 as Whatcom County Water District No. 10, the District provides water service to approximately 4,100 equivalent residential units (ERUs) and sewer service to approximately 4,400 ERUs in an 18-square mile area encompassing Lake Whatcom. The District is operated by 18 full-time professionals, governed by a five-

member board of commissioners elected from within the District, and has an annual budget of approximately \$8 million.

1. Water System Summary. The District owns and operates three Group A water systems and one Group B water system. In total, the District operates two water treatment plants, six pump stations, seven reservoirs, and approximately 70 miles of transmission and distribution mains. Additional information specific to the District's water system may be found in the 2018 Water System Comprehensive Plan, available on the District's website at <https://lwwsd.org/resources/water-system-comprehensive-plan/>.
2. Sewer System Summary. The District owns and operates 28 sewer lift stations and over 75 miles of sewage collection and conveyance lines. The District does not treat the sewage it collects, instead delivering its wastewater to the city of Bellingham's treatment plant for treatment and disposal under terms of an interlocal agreement that expires in 2034. Additional information specific to the District's sewer system may be found in the 2020 Comprehensive Sewer Plan, available on the District's website at <https://lwwsd.org/resources/comprehensive-sewer-plan/>.

### III. PROJECT BACKGROUND

The Lake Whatcom Water and Sewer District provides potable water to its South Shore water system, which is comprised of the Sudden Valley and Geneva communities (population approximately 10,000), wholly by water treated at its Sudden Valley Water Treatment Plant. The water treatment plant is a rapid-rate, direct filtration plant with a rated capacity of 2.0 million gallons per day (mgd).

The treatment plant, whose water source is Lake Whatcom, is located at 22 Morning Beach Drive, adjacent to Lake Whatcom and the Sudden Valley Community Association's Morning Beach Park. An essential component of the Sudden Valley Water Treatment Plant system is SVWTP Pump Building. The pump building has the highest consequences of failure since it serves the entire population in the South Shore System. The pump building houses four (4) transmission pumps that convey potable water to the entire South Shore system. As a result, the pump building will not be stable under the earthquake loads assumed and could fail catastrophically.

In April 2022 Gray & Osborne Inc. consulting engineers completed the Sudden Valley Water Treatment Plant Facility Improvement master plan. One aspect of the plan was to evaluate the seismic integrity of components of the treatment plant and pump building. For the Pump Building, structural and nonstructural retrofits to address seismic deficiencies were identified.

A structural analysis was performed in 2016 on five Lake Whatcom Water and Sewer District water storage reservoirs to determine their ability to withstand seismic events based on existing earthquake code requirements. The analysis determined that the foundations and/or anchorage systems were inadequate in all five reservoirs, which included the Geneva Reservoir.

#### IV. PROCUREMENT PROCESS

##### A. General Information

###### 1. Compliance with Legal Requirements.

- a. The procurement of these consultant services will be in accordance with applicable District, federal, state and local laws, regulations and procedures. The District reserves the right to reject any and all Submittals received. Any Consultant failing to submit information in accordance with the procedures set forth herein may not be considered responsive and may therefore be subject to disqualification by the District.
  - b. In accordance with the provisions of this RFQ, the District will evaluate the Submittals. The final selection, if any, will be that Consultant which, in the opinion of the District, best meets the requirements set forth in the RFQ and is determined to be the most highly qualified for the services requested.
2. Costs borne by Consultants. All costs incurred in the preparation of a Submittal and participation in this RFQ and negotiation process shall be borne by the proposing firms.
3. Public Disclosure. Once in the District's possession, Submittals shall become property of the District and considered public documents under applicable Washington State laws. All documentation that is provided to the District may be subject to disclosure in accordance with Washington State public disclosure laws.

##### B. Protests

###### 1. Time to File a Protest.

- a. Any prospective Consultant may file a protest challenging the requirements identified in the RFQ provided such protest is received no later than ten (10) calendar days prior to the date established for responding to this solicitation.
  - b. A financially interested Consultant may file a protest based on evaluation of Submittals provided such protest is received no later than five (5) calendar days after the protesting party knows or should have known of the facts and circumstances upon which the protest is based.
  - c. In no event shall a protest be considered if all Submittals are rejected or after execution of this contract.
2. Form of Protest. A protest shall be in writing and addressed to: Lake Whatcom Water & Sewer District, 1220 Lakeway Drive, Bellingham, WA 98229, Attention: General Manager. The protest shall include the following:
- a. The name, address and telephone number of the party protesting or their representative;



- b. The RFQ number and contract title under which the protest is submitted;
  - c. A detailed description of the specific grounds for protest and any supporting documentation; and
  - d. The specific ruling or relief requested.
3. Determination of Protest. Upon receipt of a timely written protest, the District General Manager shall investigate the protest and shall prior to execution of the contract respond in writing to the protest. The District General Manager's decision shall be considered the final action by the District.
  4. Compliance with Protest Process. Failure to comply with these protest procedures will render a protest untimely and inadequate and may result in rejection thereof by the District.
  5. Exhaustion of Administrative Remedies: As a mandatory condition precedent to initiating a lawsuit against the District, a prospective Consultant or a Consultant shall comply with the Protest Procedures defined herein.
  6. Venue: By responding to this RFQ and for the convenience of the parties, the prospective Consultant or a Consultant acknowledges and agrees that a lawsuit or action related to or arising out of this procurement shall be brought in the Superior Court of Whatcom County, Washington.

C. Schedule

1. Anticipated Schedule. The selection process is anticipated to proceed as outlined below and is subject to change:

<u>Date</u>	<u>Selection Process</u>
<b>February 14, 2024</b>	<b>Public Announcement of the RFQ</b>
<b>March 12, 2024</b>	<b>Submittals Due</b>
<b>March 27, 2024</b>	<b>Recommendation to Board</b>
<b>Mid-April 2024</b>	<b>Contract Execution</b>

2. Notification. The District will notify appropriate firms of changes in the RFQ and Notice of Selection.
3. Addenda. In the event it becomes necessary to revise any part of the RFQ, addenda will be provided to all firms still under consideration at the time the addendum is issued. If any firm has reason to doubt whether the District is aware of the firm's interest, it is the responsibility of the firm to notify the District to be sure that addenda are received. Mail or call such notice to Greg Nicoll, 360-734-9224, Lake Whatcom Water and Sewer District, 1220 Lakeway Drive, Bellingham, WA 98229.

#### D. Negotiations

1. At the completion of the selection process, the selected Consultant will enter into contract negotiations with the District. Negotiation of a contract will be in conformance with applicable federal, state and local laws, regulations and procedures. The negotiated cost and pricing data, once agreed to by the District and the Consultant, shall form the basis for a billing/payment provision.
2. At the beginning of negotiations, the selected Consultant and District shall establish a Negotiation Schedule. Negotiations shall begin with the Work Plan identified in the Qualifications Statement submitted by the selected Consultant.
3. If the District and selected Consultant cannot come to terms on level of effort (LOE) and a scope of work (SOW) after three (3) revisions to the SOW and LOE, the District may discontinue negotiations and go to next highest ranked Consultant. Failure to reach agreement after three (3) revisions demonstrates an inability to reach agreement within a reasonable timeframe.
4. If the District and selected Consultant cannot come to terms on cost and pricing data after three (3) revisions, the District may discontinue negotiations and go to the next highest ranked Consultant. Failure to reach an agreement after three (3) revisions demonstrates an inability to reach agreement within a reasonable timeframe.

#### E. Contract Terms and Conditions

1. A copy of the draft agreement(s) for A/E professional services is included as an Attachment.
2. By submitting qualifications, the Consultant represents that it has carefully read the terms and conditions of the Request for Qualifications and agrees to be bound by them. Agreement to be negotiated.

#### F. Cost and Pricing Data

1. The selected consultant shall provide the following information within five (5) business days after Notice of Selection has been received. Failure to provide such information in a timely manner may result in the District discontinuing negotiations with the selected Consultant and starting negotiations with the next highest ranked Consultant.
  - a. Direct Salaries. Selected consultant and its subconsultants shall submit the following information:
    - (1) List of employees, in alphabetical order (last name first), with job classification, rate of pay, and salary review date.
  - b. Overhead Rates. Selected consultant and its subconsultants shall provide the following information:
    - (1) Provide current audited overhead schedule, audit report, and cost detail by

general ledger account.

- (2) Provide a listing of all personnel who will perform work on this Project whose salaries, in full or in part, are included in overhead for the current and previous year. For each person identify his or her title, classification, position in company and salary rate.
- c. Billing Rates. Submit only for certain qualifying small firms.
- (1) Small firms that do not have an accounting system in place, that identifies direct and indirect costs separately, generally use billing rates. Fully burdened billing rates, which include labor, overhead costs and profit are allowed on a case-by-case basis for those firms that typically use this method for billing purposes.
- d. Other Direct Cost(s).
- (1) Identify all Other Direct Cost(s) (ODC) for this project and the rationale used as a basis for this cost.
  - (2) For each ODC, provide the unit prices and/or rates with supporting rationale, historical data and estimating methodology used to validate these rates.
  - (3) Failure to identify ODC results in a presumption that there are no ODC.
- e. Profit. Selected consultant and its subconsultants shall provide the following:
- (1) Proposed profit;
  - (2) Rationale and justification for the proposed profit rate.
- f. Markup on Subconsultant Costs and ODC. Selected consultant and its subconsultants shall provide the following:
- (1) Proposed markup on subconsultant costs and ODC;
  - (2) Rationale and justification for the proposed markups.

## V. INSURANCE REQUIREMENTS

- A. Prior to execution of the Agreement, the Selected Consultant shall file with the District certificates of insurance and endorsements from the insurer(s) certifying to the coverage of all insurance required in accordance with the District's standard agreement. All evidences of insurance must be certified by a properly authorized officer, agent, general agent or qualified representative of the insurer(s) and shall certify the name of the insured, the type and amount of insurance, the location and operations to which the insurance applies, the expiration date, and provides that the District receives notice at least thirty (30) calendar days prior to the

effective date of any policy limit or cancellation of required coverages. The Consultant shall notify the District at least thirty (30) calendar days prior to the effective date of any cancellation or reduction in coverage in the policy. The Consultant shall maintain during the entire Contract period, insurance coverage at least as broad as the limits and coverage outlined in the District's standard agreement. The Consultant shall, upon demand of the District, make available to the District at Consultant's local office in all such policies of insurance and the receipts of payment of premiums thereon. Failure to provide such policies of insurance within a time acceptable to the District shall entitle the District to suspend or terminate the Consultant's work hereunder. Suspension or termination of the Consultant Agreement shall not relieve the Consultant from its insurance obligation hereunder.

- B. The Consultant shall obtain and maintain at a minimum the limits of insurance set forth in the Consultant Agreement. By requiring such minimum insurance, the District shall not be deemed or construed to have assessed the risks that may be applicable to the Consultant under the Agreement. The Consultant shall assess its own risks and, if it deems appropriate and/or prudent, maintain greater limits and/or broader coverage.
- C. Each insurance policy shall be written on an "occurrence" form; excepting that insurance for professional liability, errors and omissions when required, is acceptable on a "claims made" form.
- D. If coverage is approved and purchased on a "claims made" basis, the Consultant shall continue coverage either through (1) policy renewals for not less than three years from the date of completion of the work which is the subject of this Agreement or (2) the purchase of an extended discovery period for not less than three years from the date of completion of the work which is the subject of this Agreement, if such extended coverage is available.
- E. If, in order to meet the insurance requirements the Consultant must rely on the insurance to be provided by one or more subconsultant, then such subconsultant(s) shall be required to meet all of the requirements herein applicable to the insurance they are providing, and shall include District and Consultant as additional insureds on all liability policies except Professional Liability/Errors & Omissions and Workers Compensation. The District will not make any payments on work performed by subconsultants until all insurance documentation from such subconsultants have been received and accepted by the District.
- F. Provided the affected insurance policies permit the following waiver, without voiding coverage, Consultant and District waive all rights against each other to subrogation for damages covered by property insurance.

## **VI. EVALUATION AND SELECTION CRITERIA**

- A. All Submittals will be evaluated by a Consultant Selection Panel ("Panel"), which will be responsible for ranking of the Submittals. The criteria outlined below will be used in evaluating the Submittals and determining the most qualified Consultant. A total of 100 points (excluding a potential interview) has been assigned to the Evaluation Criteria. The maximum points possible will follow each criterion listed. The points indicate relative weight or importance given to each criterion.

- B. The District may determine that the ranking is close and an interview with the top ranked firms is necessary. Interviews will have a maximum of 50 points. The number of Consultants to participate in interviews, if any, will be determined by the District based on the recommendation of the evaluation. The District may choose to use different criteria for the interview, in which case the finalists will be so notified in writing. The interview process may or may not include a Consultant presentation and the Consultants will not be given questions to prepare for in advance of the interview.
- C. Following the review of the submittals and the interviews (if conducted) the evaluators will use the points to score each Submittal. Each evaluator will put the scores in rank order, with the highest scored Consultant 1st, the second-highest scored Consultant 2nd, etc. This ranking will then be totaled. From the ranking, the District intends to recommend the most qualified Consultant to the Board of Commissioners for approval to begin negotiations.

## VII. DOCUMENTATION

- A. The prime Consultant shall submit two (2) bound copies and a USB with the electronic PDF file of the Submittal.
- B. Consultants are discouraged from submitting lengthy Submittals. The District requests that Submittals be concise and clearly written containing only essential information. Submittals should be 25 pages or less, including any resumes and cover letter.
- Submittals should be minimum of 11 font.
  - Sheets with double sided printing will be counted as 2 pages.
  - Sketches, maps and charts printed on 11x17 count as 1 page.

The Submittal shall consist of the following parts:

1. Letter of Interest: The Letter of Interest shall contain the following information:
  - RFQ Title: **GENEVA RESERVOIR AND SVWTP PUMP HOUSE SEISMIC UPGRADES;**
  - Consultant's name, mailing address, contact person, telephone and fax numbers;
  - UBI and federal tax ID numbers; and
  - Stipulation that Consultant accepts all terms of the RFQ, especially the terms and conditions of the attached sample contract(s).
2. Qualifications Statement. The submittal shall include Key Personnel's:
  - General statement of the understanding of the scope of services.
  - Project Team including proposed subconsultants.
  - The Project Team's experience with water conveyance and treatment infrastructure, maintenance, design, construction management and inspection services.
  - Experience with District's water infrastructure.
  - Permitting experience with Whatcom County, including experience in the County's shoreline permitting process and requirements.
  - Approach to managing and completing projects.
  - Approach to communicating with the District.
  - Approach to ensure cost efficient execution and quality control.

- Experience with FEMA Hazard Mitigation Grant projects and associated federal and state funding requirements.

The submittal shall be presented in a clear, comprehensive and concise manner and shall be submitted in a complete package by the prime Consultant.

## **VIII. EVALUATION CRITERIA AND SUBMITTAL INFORMATION**

### **A. Experience and Technical Competence - 40 Points.**

The District will evaluate the experience and technical competence of the Consultant's Key Personnel to complete the project. Emphasis will be placed on recent experience and expertise in performing the required services on projects with a scope of work similar in size and complexity to this Project.

### **B. Work Plan - 30 points.**

The District will evaluate the proposed Work Plan to determine the Consultant's understanding of the scope of work, allocation of skilled personnel to specified tasks, appropriate utilization of subconsultants, and overall project approach.

1. The Work Plan is an opportunity for the Consultant to demonstrate its understanding of scope and propose ideas for the Project.

### **C. Record of Past Performance & References - 30 Points.**

1. The District will evaluate the project team's record of performance and references on previous and/or ongoing projects with consideration given to quality of work, ability to meet schedules and budgets, cooperation, responsiveness, performance on other District projects and other managerial considerations.
2. The District will evaluate the project examples provided with respect to Key Personnel's experience with similar projects and the amount of involvement they had with the project examples. The project examples provided should demonstrate Key Personnel's experience in providing services similar in scope to this Project.

### **D. Interviews - 50 Points (if conducted)**

1. The District may or may not conduct interviews. If the District determines that interviews are necessary, the District will conduct interviews with the short-listed Consultants (finalists).
2. Consultants will be notified in writing of the request and provided the date, place, and time of the interview. The interview process may or may not include a Consultant presentation and the Consultants will not be given questions to prepare for in advance of the interview. The District may choose to use different criteria for the interview, in which case the Finalists will be so notified in writing.

3. Failure to participate in the interview process shall result in a Consultant's disqualification from further consideration.

**AGREEMENT FOR A/E PROFESSIONAL SERVICES  
FOR  
GENEVA RESERVOIR AND SVWTP PUMP HOUSE SEISMIC UPGRADES**

**THIS AGREEMENT**, made and entered into by and between Lake Whatcom Water and Sewer District, Whatcom County, Washington, hereinafter referred to as "District", and **[[[ FIRM NAME ]]]** ("Consultant"), a corporation with a place of business at **[[[ FIRM ADDRESS ]]]**, collectively referred to as "Parties", shall be effective upon the authorized signatures of both Parties to this Agreement ("Effective Date").

**WHEREAS**, the District, a special purpose municipal corporation, provides water and sewer service to its constituents; and

**WHEREAS**, the District desires to retain the Consultant to perform certain professional services, including engineering services necessary to perform **GENEVA RESERVOIR AND SVWTP PUMP HOUSE SEISMIC UPGRADES** ("Project"); and

**WHEREAS**, the District solicited for professional services as required by RCW 39.80; and

**WHEREAS**, the Consultant represents it has available and offers to provide qualified personnel and facilities necessary to accomplish such services required for the Project within the required time.

The Parties enter into this Agreement. The term Agreement and Contract shall be used interchangeably and refer to this Agreement.

**SECTION 1: PERIOD OF PERFORMANCE**

- 1.1. All required work and services specified in the terms and conditions of this Agreement for **Phase 1, Design and Permitting Services per Exhibit A – SCOPE OF WORK**, shall be completed by **[[[ December 31, 2023 ]]]** unless extended or terminated earlier by the District pursuant to the terms and conditions of this Agreement. The District reserves the right to amend this Agreement to add **Phase 2, Services During Construction per Exhibit A – SCOPE OF WORK**. The District also reserves the right to let the Agreement expire at the completion of Phase 1 and to select another consultant to perform the additional study and/or phases.
- 1.2. Time is a material consideration in the performance by the Consultant under this Agreement. The Consultant shall complete its work and services within the Project schedule, including any established milestones and task completion dates, and the Period of Performance, set forth in the Scope of Work. The completion dates for tasks may be modified by a written directive; however, the Period of Performance for the Agreement may only be modified through an amendment. No completion dates shall be extended because of any unwarranted delays attributable to the Consultant. Completion dates may be extended in the event of a delay caused by the District which results in a delay in the performance of an affected task, or because of unavoidable delay caused by any governmental action or other conditions beyond the control of the Consultant, which could not be reasonably anticipated and which results in a delay in the performance of an affected task.



- 1.3. Time Extensions. The Total Price, Period of Performance and task budgets shall not be increased because of any unwarranted delays or costs attributable to the Consultant. In the event of a delay not attributable to the Consultant which (1) delay could not be reasonably anticipated and (2) results in an increase in costs to perform the work, the District may, through the execution of an amendment, increase the Total Price, Period of Performance and/or task budget.

## SECTION 2: ADMINISTRATION AND SUPERVISION

- 2.1. **DISTRICT.** An employee of the District, hereinafter called the "Project Manager," who shall be designated in writing by the District, shall perform day-to-day management of this Contract. Unless otherwise indicated in writing by the General Manager or its designee, the Project Manager will issue notices to proceed, approve all requests for payment, authorize termination or modification of tasks, and approve in writing changes to the task budgets outlined in the Cost Summary, Exhibit B attached hereto and incorporated by reference, provided the changes do not impact the Total Price, Period of Performance, and the Fixed Professional Fee. The Project Manager will also be responsible for determining when the Consultant has satisfactorily performed all work and for ensuring that the Consultant complies with all provisions of this Agreement.
- 2.2. **CONSULTANT.** The Consultant represents that it has, or will obtain, all personnel necessary to perform the services required under this Agreement and that such personnel shall be qualified, experienced and licensed as may be necessary or required by laws and regulations to perform such services. All services required under this Agreement shall be performed by the Consultant, its employees, or by subconsultants whose selection has been authorized by the District; provided, that the District's authorization shall not relieve the Consultant or its subconsultants from any duties or obligations under this Agreement or at law to perform in a satisfactory and competent manner. All contractual duties, requirements and obligations that the Consultant owes to the District shall also be owed to the District by the Consultant's subconsultants retained to perform the work pursuant to this Agreement. The term "Consultant" shall refer to **[[[ FIRM NAME ]]]**, and all of its subconsultants.
- A. Authorized Subconsultants. The Contract shall identify in the Cost Summary, Exhibit B, the subconsultants who are authorized to perform work under this Contract.
- B. Process for Adding or Removing Subconsultants. If during the term of this Contract, the Consultant wishes to add or remove a subconsultant, the Consultant shall provide the Project Manager with a written request identifying the proposed change. The written request shall include the following information:
1. Identity of the subconsultant and the work to be performed;
  2. Resumes and documentation outlining the subconsultant's experience;
  3. If the subconsultant is to perform work of the consultant or another subconsultant already identified in Exhibit B, an explanation of why the work is going to be transferred to a new subconsultant.
- C. District Approval of Subconsultants. The District has sole discretion in approving or rejecting proposed subconsultants. Each subcontract shall be available for review and the cost summary subject to review by the Project Manager prior to the subconsultant proceeding with the work. Before any subconsultant not

already identified in the Contract can perform any work under this Contract, the District shall provide written authorization to the Consultant.

- D. Substitution of Personnel. The Consultant recognizes and agrees that if a change is made substituting or changing assigned key personnel, the Consultant shall be responsible for any and all costs associated with "Transfer of Knowledge and Information". The Transfer of Knowledge and Information shall be defined to include the labor hours spent reviewing project documentation, participating in meetings with Project personnel, and participating in site visits to familiarize oneself with the Project and project location(s). The District shall not pay for any time spent for the "Transfer of Knowledge and Information".
1. The Consultant shall provide sufficient advance notice of any intention to remove or reassign key personnel. The Consultant shall not remove or reassign the key personnel assigned to this Project without written consent from the District. Exhibit F, Key Personnel, is a listing of key individuals for this work. Notice for the substitution of individuals and positions identified as Key Personnel shall include the following:
    - a. An explanation of the reason for the reassignment or removal;
    - b. The name of the person proposed to replace the individual; and
    - c. Identification of the experience and qualifications of the individual proposed.
  2. For individuals who are not identified as "Key Personnel" in Exhibit F, the Consultant shall provide documentation supporting the labor rate for the substituted personnel prior to submitting an invoice and the labor rate shall not exceed 110 percent of the originally assigned personnel's labor rate.
  3. District Request Removal Personnel. The Consultant shall remove from the Project any personnel or subconsultant if, after the matter has been thoroughly considered by the District and the Consultant, the District considers such removal necessary and in the best interests of the Project and so advises the Consultant in writing. In this case, the District will compensate the consultant for Transfer of Knowledge costs associated with the removal of any personnel or subconsultant.

### **SECTION 3: SCOPE OF WORK**

- 3.1. The District hereby retains the Consultant upon the terms and conditions contained herein to perform certain work and services on the Project. The work and services for the Project to be performed by the Consultant are set forth in Exhibit A, Scope of Work, attached hereto, and incorporated herein by this reference. The general Project Schedule is set forth in Exhibit C, attached hereto and incorporated herein by reference.
- 3.2. The District shall make available to the Consultant, without cost, copies of as-built plans, drawings, survey notes, studies, soil reports, maintenance and performance records, and other relevant data, and property descriptions of various District facilities related to the Project, which are readily available, and on file at the District. These documents are available solely as additional Information to the Consultant and do not relieve the Consultant of its duties and obligations under this Agreement nor constitute any

representation or warranty by the District as to conditions or other matters related to the Project.

- 3.3. It shall be the responsibility of the Consultant to gather and become familiar with all site information including existing improvements.

#### **SECTION 4: CHANGES IN WORK**

- 4.1. Any direction from the District to perform work that results in an increase or decrease in scope, changes to the Total Price or Period of Performance, or changes impacting the Scope and Budget for the project shall be made only by an amendment prior to the work being performed. A member of the Board of Commissioners for the District is the only authorized District representative who may sign amendments.
- 4.2. In the event the Consultant identifies something that may impact the scope of work, Project Schedule and/or cost, Consultant shall inform the Project Manager within five (5) business days of the event and possible impacts to scope, schedule and cost. If appropriate, the parties shall execute an amendment.
- 4.3. The District may, at any time, by written amendment direct the Consultant to make additions within the general scope of the services or work to be performed under this Agreement, delete portions of the Project, or revise portions of the work. Any changes within the general scope of work, which result in an increase or decrease in time of performance or cost, shall only be made by amendment.

#### **SECTION 5: RESPONSIBILITY OF THE CONSULTANT**

##### **5.1. Standard of Care**

- A. The Consultant shall be responsible for the professional quality, technical adequacy and accuracy, timely completion and coordination of all plans, designs, drawings, specifications, reports and other services prepared or performed pursuant to this Agreement. The Consultant shall perform its work to conform to generally accepted professional standards applicable to the types of services and work provided hereunder. The Consultant shall be responsible for the professional standards, performance and actions of all persons and firms performing work pursuant to this Agreement. The Consultant shall, without additional compensation, correct or revise any errors, omissions or specific breaches of a contractual obligation in such plans, designs, drawings, specifications, reports and other services.
- B. The District's approval of plans, drawings, designs, specifications, reports and other products of the professional services rendered hereunder shall not in any way relieve the Consultant of responsibility for the technical adequacy or accuracy thereof. Neither the District's review, approval or acceptance of, nor payment for, any of the services shall be construed to operate as a waiver of any rights under this Agreement or of any cause of action arising out of the performance of this Agreement.
- C. The Consultant shall be knowledgeable and familiar with the District's Construction General Conditions and any District provided Division 0 (which

includes General and Supplemental conditions and Bidding Provisions) and Division 1 (General Construction Requirements). Any technical specifications drafted by the Consultant shall be consistent with these Divisions and such technical specifications should not create any ambiguity or conflict with these Divisions.

- D. Consistent with generally accepted professional standards, the Consultant shall promptly bring to the District's attention any concerns that the Consultant has regarding the design, or any finding, conclusions, or final decisions made by the District. The Consultant shall, at the District's request, provide the District with a written evaluation of its concerns, along with proposed solutions to any identified problems.

## 5.2. Maintenance of Project Documentation

- A. Upon written request by the Project Manager, the Consultant shall provide the District with access to all documents and correspondence, including e-mail communications, memoranda, and all other written materials prepared or used in performance of work on this Project.
- B. The Consultant is cautioned that information and documentation submitted to the District may become a public record in accordance with the Revised Code of Washington and may not be exempt from disclosure under the Washington State Public Disclosure Act.
- C. The Consultant acknowledges that unauthorized disclosure of information or documentation concerning this Project may cause substantial economic loss or harm to the District. Except as otherwise required by Court Order or subpoena, the Consultant shall not without prior written authorization by the Project Manager allow the release, dissemination, distribution, sharing, or otherwise publication or disclosure of information or documentation obtained, discovered, shared or produced pursuant to this Agreement.

## **SECTION 6: PRODUCTS**

- 6.1. In the performance of this Agreement, the Consultant shall, to the extent practicable, design and draft specifications that provide for maximum use of structures, machines, products, materials, construction methods, and equipment which are readily available through competitive procurement, or through standard or proven production techniques, methods and processes.
- 6.2. The Consultant shall not, in the performance of the work under this Agreement, produce a design or specification which would require the use of structures, machines, products, materials, construction methods, equipment, or processes which the Consultant knows to be available only from a single source, unless the Consultant has provided a written justification for the use of a single source in writing and the District concurs.
- 6.3. The Consultant shall not, in the performance of the work under this Agreement, produce a design or specification which would be restrictive or written in such a manner as to contain proprietary, exclusionary, or discriminatory requirements other than those based upon performance, unless such requirements are necessary to test or demonstrate a

specific thing, or to provide for necessary interchangeability of parts and equipment. The Consultant shall report to the District any single source or restrictive design or specification giving the reason(s) why, in the Consultant's professional judgment, it is necessary to restrict the design or a particular specification. The Consultant shall substantiate in writing, and to the District's satisfaction, the basis for the single source or restrictive design or specification.

- 6.4. When one or more brand names or trade names of comparable quality or utility are listed, the words "or approved equal" shall follow the brand name(s) and the salient characteristics shall be identified.

## **SECTION 7: COMMENCEMENT AND MONTHLY REPORTS**

- 7.1. Notice to Proceed. After execution of this Agreement by the District and the Consultant, the District will issue a written notice to proceed on the Project or specific tasks thereof. Such notices to proceed will be provided for specific tasks identified as necessary to produce specified work products and shall set forth the date of commencement of the work, a description of the work to be performed, the schedule for the work authorized, and the budgets for such tasks. Upon receipt of a notice to proceed, the Consultant shall promptly commence work.
- 7.2. Monthly Reports. Unless otherwise stated in the Scope of Work, not later than the 10th day of each calendar month during the performance of the Project, the Consultant shall submit to the Project Manager, a monthly report, in a format approved by the Project Manager, sufficient to show the activities completed and the Project progress as measured against the Project Schedule and Exhibit B, Cost Summary. At a minimum the monthly report shall identify work completed, costs incurred, budget status (budget vs. estimated balance to complete), amendments, project schedule, any variance between planned vs. actual project performance, all issues that may result in completion of any task beyond the established schedule or task budget, and all issues that may result in an increase in Total Price.

## **SECTION 8: COMPENSATION**

- 8.1. Subject to the provisions set forth in this Agreement, the District will pay the **[[[ FIRM NAME ]]]** for authorized and satisfactorily completed work and services rendered under this Agreement. No more than monthly progress payments shall be full compensation for work performed and services rendered, for all supervision, labor, supplies, materials, equipment or use thereof, taxes, and for all other necessary incidentals, but in no case shall the total progress payment exceed the Total Price as defined herein. The amount to be paid to the Consultant shall be computed as hereinafter set forth; provided, that such payment shall not exceed a maximum amount of **[[[ CONTRACT AMOUNT ]]]** DOLLARS (**(\$???????)**) ("Total Price"). In the event the Consultant incurs costs in excess of the Total Price, the Consultant shall pay such excess from its own funds and the District shall not be required to pay any part of such excess and the Consultant shall have no claim against the District on account thereof.
- 8.2. Compensation for work and services shall be on a cost plus fixed fee basis but not to exceed the Total Price. Compensation and the Total Price shall be the sum of Direct Labor Costs, Indirect Costs, a Fixed Professional Fee, and Other Direct Costs as described and defined below. Costs to be paid are identified in the Cost Summary, which

is attached hereto as Exhibit B and incorporated herein by this reference, and comprise the following:

- A. **Direct Labor Costs.** Direct Labor Costs shall be the total number of allowable hours worked on the Project by each individual multiplied by the Labor Rate identified in the Costs Summary (Exhibit B) for such individual.
1. A Labor Rate shall not exceed \$65.00 per hour, except in exceptional and rare circumstances when the District, in its sole discretion, agrees to pay over \$65.00 per hour.
  2. The District shall only pay the Labor Rate and shall not pay any premium associated with overtime.
  3. The parties agree to the Labor Rates as set forth in Exhibit B, which rates shall be used during the entire term of this Agreement, including all amendments; provided however, Labor Rates may be subject to reasonable adjustments but only in accordance with paragraph 8.4 below.
- B. **Indirect Costs.** Indirect Costs shall be calculated as follows:
1. Indirect Costs shall be the Overhead Rate identified in the Cost Summary (Exhibit B) multiplied by the Direct Labor Rates for every allowable hour worked on the Project and billed by the individual.
  2. The Consultant agrees to the Overhead Rates as set forth in Exhibit B, which rates shall be used during the term of this Agreement, including all amendments.
- C. **Fixed Professional Fee (Profit).** The District shall pay a Professional Fee which shall be calculated as set forth below.
1. The Professional Fee shall be ?.?%, or otherwise represented as a multiplier of 0.???, of the total of the Direct Labor Costs plus the Indirect Costs, as identified in the Cost Summary (Exhibit B).
  2. The Consultant acknowledges and agrees that the Fixed Professional Fee is only due and payable for Project work for which the District has given notice to proceed and which the Consultant has satisfactorily completed. The Fixed Professional Fee will not be paid for any tasks in the Scope of Work and Cost Summary that the District does not authorize the Consultant to perform. The District is entitled to a deductive amendment for any unperformed tasks.
  3. The Consultant acknowledges and agrees that the amount of the Fixed Professional Fee may be adjusted by the District to:
    - a. Reduce the Fixed Professional Fee associated with Scope of Work that was not authorized, or was not performed by the Consultant;
    - b. Reduce the Fixed Professional Fee associated with deletions in the Scope of Work;

- c. Increase the Fixed Professional Fee for additional work included in the Scope of Work through an amendment.
  - 4. The Fixed Professional Fee shall be paid as follows:
    - a. The Fixed Professional Fee will be paid monthly in proportion to the Project work satisfactorily completed. The proportion of work completed shall be determined by earned value of the Project work satisfactorily completed. The Cost Summary shall identify the Project work for payment of the Fixed Professional Fee.
    - b. A payment for an individual month shall include that portion of the Fixed Professional Fee allocable to the Project work satisfactorily completed during said month and not previously paid; and
    - c. Any portion of the Fixed Professional Fee not previously paid in the monthly payments shall be included in the final payment provided that the Consultant satisfactorily completed the entire scope of work subject to the limitations set forth above.
    - d. The Consultant acknowledges and agrees that the Fixed Professional Fee does not and shall not include any profit or other markup on subconsulting costs or Other Direct Costs.
  - D. **Other Direct Costs.** Other Direct Costs ("ODC") are those costs which can be specifically identified with the Contract objectives, are required for performance of the Contract, are approved in advance in writing by the Project Manager, and are actually incurred. Markup on ODC's shall be billed at ???% for subconsultants and at fixed rates as listed in Exhibit E – ALLOWABLE ODC'S.
- 8.3. **Unallowable Costs.** The District shall not pay for any costs or direct charges associated with or relating to the following activities:
  - A. Any resubmission, changes to or adjustments in the invoices, and fixing improper invoices and the preparation and submission of monthly invoices if this cost is not included In the Consultant's overhead.
  - B. Preparation of, discussion and/or negotiation of a request for adjustments in any Labor Rate, Overhead Rate and/or Labor Escalation percentage; and
  - C. Changing or reassigning personnel or subconsultants, including but not limited to preparing requests concerning Transfer of Knowledge for Key Personnel. Exception, the District will pay for costs associated with the change or reassignment resulting from a written request from the District requesting the specific personnel or subconsultant change.
  - D. Preparation of any documentation related to, discussion of, or negotiation of equitable adjustment, disputes, claims or Section 16, Disputes and Remedies.
  - E. Meals, except when in Travel Status.

8.4. Limitations on Changes to Labor Rates.

A. Any changes Labor Rates shall have no impact on the Total Price.

B. Overhead Rates.

C. The Overhead Rates are identified in the Cost Summary, Exhibit B. The Overhead Rates shall not be subject to modification.

D. Labor Rates

1. The Consultant agrees that all Labor Rates identified in this Agreement (Exhibit B) shall be effective for the entire Contract duration, including all amendments; provided however, Labor Rates may be increased at the sole discretion of the District on an annual basis.

2. A Labor Rate shall not exceed \$65.00 per hour except in exceptional and rare circumstances when the District, in its sole discretion, agrees to a Labor Rate over \$65.00.

3. Labor rate increases must be based on actual and verifiable increases in labor costs.

4. Should the Consultant seek an adjustment in Labor Rate(s), Consultant must notify the District in writing of its request to modify the existing labor rate. Consultant shall submit only one request per year that must include all individual rate increase requests. This request shall include the amount of the increase in the rate for each rate increase.

E. Other Direct Costs. Other Direct Costs ("ODC") are those costs which can be specifically identified with the Contract objectives, are required for performance of the Contract, are approved in advance in writing by the Project Manager, and are actually incurred. Allowable ODC are as included in Exhibit E to this Contract.

8.5. Approval of Increases by District: Adjustments in Labor Rates, and the amount of any rate increase require the approval of the Project Manager. The Consultant shall provide additional information as requested by the District. The District shall review the Consultant's request for a rate increase and respond in writing to the request within sixty (60) calendar days of receipt of such request.

8.6. Effective Period. Any change to the Labor shall not be effective until the date the Project Manager approves, in writing, the increase. Labor rates shall not be retroactive. Only services performed after the date the Project Representative approves the rate increase shall be billed at the new labor Rate. The written approval is considered a part of the Contract documents and shall be incorporated into the Contract in the next amendment.

8.7. Invoice Process. The Consultant shall submit to the Project Manager an invoice for payment for Project work completed to the end of the previous month. Such invoices shall be for work performed subsequent to that work covered by all previously submitted



invoices and shall be computed pursuant to the rates and limitations set forth hereinabove.

- A. Invoices shall detail the work by task, hours and employee name and level for which payment is being requested; include copies of all invoices from authorized subconsultants for which payment is being requested; and shall itemize, and include copies of, receipts and invoices for the Other Direct Costs.
  - B. At no time shall the total cumulative amounts paid for Project work exceed the total which would be due upon the completion of all Project work multiplied by the percentage of the required work satisfactorily completed, as determined by the District.
  - C. In the event of a disputed invoice, the District shall pay the undisputed amounts and withhold from payment the disputed portion of the invoice.
- 8.8. Prompt Payment of Subconsultants. Within ten (10) business calendar days of receipt of a progress payment from the District that includes dollars for work performed by subconsultants, Consultant shall pay such subconsultants out of such amounts as are paid by the District, for all work satisfactorily completed by the subconsultant.
- 8.9. Final Payment. Final payment of any balance earned by and payment to the Consultant for Project work will be made within sixty (60) calendar days after all of the following:
- A. Satisfactory completion of all work required by this Agreement;
  - B. Receipt by the District of the plans, studies, surveys, photographs, maps, calculations, notes, reports and all other documents and/or deliverables which are required to be prepared and submitted by the Consultant under this Agreement;
  - C. Delivery of all equipment/materials purchased specifically for the Project where the District has reimbursed the Consultant for such costs;
  - D. Receipt by the District of a fully executed final statement of amounts Invoiced by and paid to each subconsultant under this Agreement; and,
  - E. Execution and delivery by the Consultant of a release of all claims against the District arising under or by virtue of this Agreement, other than such claims, if any, as may be specifically exempted by the Consultant from the operation of the release in stated amounts to be set forth therein.
  - F. No payment, whether monthly or final, to the Consultant for any Project work shall constitute a waiver or release by the District of any claims, right or remedy it may have against the Consultant under this Agreement or by law; nor shall such payment constitute a waiver, remission or discharge by the District of any failure or fault of the Consultant to satisfactorily perform the Project work as required under this Agreement.

## **SECTION 9: TERMINATION OF AGREEMENT**

9.1. Termination for Default

- A. The District may terminate this Agreement, in whole or in part, in writing if the Consultant substantially fails to fulfill any or all of its material obligations under this Agreement through no fault of the District.
- B. If the District terminates all or part of this Contract for default, the District shall determine the amount of work satisfactorily performed to the date of termination and the amount owing to the Consultant using the criteria set forth below; provided, that (a) no amount shall be allowed for anticipated profit on unperformed services or other work and (b) any payment due to the Consultant at the time of termination may be adjusted to the extent of any additional costs the District incurs because of the Consultant's default. In such event, the District shall consider the actual costs incurred by the Consultant in performing the Project work to the date of termination, the amount of work originally required which was satisfactorily completed to the date of termination, whether that work is in a form or of a type which is usable and suitable to the District at the date of termination, the cost to the District of completing the work itself or of employing another firm to complete it and the inconvenience and time which may be required to do so, and other factors which affect the value to the District of the Project work performed to the date of termination. Under no circumstances shall payments made under this provision exceed the Total Price set forth in this Agreement. This provision shall not preclude the District from filing claims and/or commencing litigation to secure compensation for damages incurred beyond that covered by withheld payments.
- C. Upon receipt of a termination notice the Consultant shall at no additional cost to the District:
1. Promptly discontinue all services affected (unless the notice directs otherwise);
  2. Terminate all subcontracts to the extent they relate to the work terminated; and
  3. No later than thirty (30) calendar days after receipt of termination, promptly deliver or otherwise make available to the District all data, drawings, electronic drawing files, specifications, calculations, reports, estimates, summaries, Official Project Documentation and other Project documentation, such other information and materials as the Consultant or subconsultants may have accumulated in performing this Agreement, whether completed or in progress and all equipment/materials purchased specifically for the Project where the District has paid the Consultant for such items.
- D. Termination for Convenience.
1. The District may terminate this Agreement, in whole or in part, for the convenience of the District. The District shall terminate by delivery to the Consultant a Notice of Termination specifying the extent of the termination and the effective date.

2. If the District terminates this Contract for convenience, the District shall pay the Consultant only for the following items:
  - a. An amount for Direct Labor Costs and Indirect Costs in accordance with the Contract and Exhibit B for services satisfactorily performed to the date of termination;
  - b. Actual and reasonable Other Direct Costs incurred before the termination; and
  - c. Actual and Reasonable termination settlement costs the Consultant reasonably incurs relating to commitments which had become firm before the termination, unless the District determines to assume said commitments. Reasonable termination settlement costs include settlement costs for subconsultants and actual reasonable accounting and clerical costs related to preparing Termination Settlement Proposal.
3. Upon receipt of a termination notice the Consultant shall at no additional cost to the District:
  - a. Promptly discontinue all services affected (unless the notice directs otherwise);
  - b. Terminate all subcontracts to the extent they relate to the work terminated;
  - c. No later than thirty (30) calendar days after receipt of termination, promptly deliver or otherwise make available to the District all data, drawings, specifications, calculations, reports, estimates, summaries, Official Project Documentation, other Project documentation, and such other information and materials as the Consultant may have accumulated in performing this Agreement, whether completed or in progress and all equipment/materials purchased specifically for the Project where the District has reimbursed the Consultant for such costs;
  - d. Take any action necessary, or that the District may direct, for the protection and preservation of property related to this Agreement that is in the possession of the Consultant and in which the District has or may acquire an interest.

## **SECTION 10: OWNERSHIP AND USE OF DOCUMENTS**

- 10.1. Reports, studies, drawings, specifications, calculations or other information developed under the terms of this Agreement shall become the property of the District after full payment to Consultant for their preparation. Any reuse of drawings/plans, specifications and/or calculations for another project without written verification or adaptation by Consultant will be at the District's sole risk and without liability or legal exposure to Consultant. District shall defend, indemnify and hold Consultant harmless from all claims, damages, losses, and expenses, including attorney's fees, arising out of or resulting therefor. The District further acknowledges that it may receive certain materials from Consultant by way of electronic file and agrees that should it modify such materials

in connection with their subsequent use, that Consultant shall bear no responsibility for the contents thereof.

## **SECTION 11: THIRD-PARTY CLAIMS AND DISPUTES**

- 11.1. At the District's request, Consultant will assist the District in review and evaluation claims and disputes, preparing information for the District's legal counsel, providing services as witness in litigation or arbitration to which the District is a party and providing other services in connection with actual or potential claims or disputes arising out of the work, regardless of whether or not consultant is named in such legal action. The parties shall cooperate to agree on the compensation for such services. If Consultant is determined to be responsible for the claim, dispute or litigation due to its negligence or breach of the contract herein, it shall remit back to the District the amounts paid under this section to the extent of such negligence or breach.

## **SECTION 12: AUDIT AND ACCESS TO RECORDS**

- 12.1. The Consultant, including its subconsultants, shall maintain books, records, documents, and other evidence directly pertinent to performance of the work under this Agreement in accordance with generally accepted accounting principles and practices consistently applied. The District, or any of its duly authorized representatives, shall, for the purpose of audit and examination, have access to and be permitted to inspect such books, records, documents, and other evidence for inspection, audit and copying for a period of six years after completion of the Project. The District shall also have access to such books, overhead data, records and documents during the performance of Project work if deemed necessary by the District to verify work performed and Invoices, to assist in negotiations for amendments to the Agreement or modifications to tasks, and to resolve claims and disputes.
- 12.2. Audits conducted under this Section shall be in accordance with generally accepted auditing standards and established procedures and guidelines of the reviewing or audit agency(ies).

## **SECTION 13: LEGAL RELATIONS**

- 13.1. The Consultant shall comply, and shall ensure its subconsultants comply, with all the terms of this Agreement and the District resolutions and federal, state and local laws, regulations and ordinances applicable to the work and services to be performed under this Agreement.
- 13.2. In performing work and services hereunder, the Consultant and its subconsultants, employees, agents and representatives shall be acting as independent contractors and shall not be deemed or construed to be employees or agents of the District in any manner whatsoever. The Consultant shall not hold itself out as, nor claim to be, an officer or employee of the District by reason hereof and will not make any claim, demand or application to or for any right or privilege applicable to an officer or employee of the District. The Consultant shall be solely responsible for any claims/costs and/or losses arising from the Consultant's failure to pay wages, compensation, benefits or taxes and/or pay for services, supplies and/or materials provided by Consultant employees, agents and representatives, including subconsultants, and will protect, defend, indemnify and hold the District harmless there from.

- 13.3. To the maximum extent permitted by law, the Consultant agrees to indemnify and save harmless the District, its officers, agents and employees, from and against any and all suits, claims, actions, losses, costs, reasonable attorney fees and expenses, penalties, judgments, settlements and damages of whatsoever kind or nature arising out of, in connection with, or incident to errors or omissions in the performance of contractual obligations, and/or the negligent performance of work or services provided by or on behalf of the Consultant, except to the extent caused by the negligence of the District. The Consultant's Indemnity obligation includes an obligation to (a) satisfy any judgment or other final decision of a court or other tribunal; (b) pay any reasonable settlement negotiated by the District with respect to claims that are within the scope of the indemnity obligation; and (c) pay all claims against the District by an employee or former employee of the Consultant or its subconsultants, and for this purpose, by mutual negotiation, the Consultant expressly waives, as respects the District only, all Immunity and limitation on liability under any industrial insurance act, including Title 51 RCW, other worker's compensation act, disability benefit act, or other employee benefit act of any jurisdiction which would otherwise be applicable in the case of such claim, The Consultant further agrees to defend all claims against the District and its officers, agents, and employees which, if proven, could result in liability of the District, its officers, agents, or employees for loss or damage caused by any such errors, omissions, or negligent work or services performed by the Consultant. The Consultant's obligation to defend shall include timely payment of all reasonable attorney fees, costs and expenses incurred in the defense of such claims. In the event of litigation between the parties to enforce the rights under this paragraph, reasonable attorney fees and expenses shall be allowed to the prevailing party.
- 13.4. The District's rights and remedies in this Agreement are in addition to any other rights and remedies provided by law.
- 13.5. The indemnification, protection, defense and save harmless obligations contained herein shall survive the expiration, abandonment or termination of this Agreement.

#### **SECTION 14: INSURANCE**

- 14.1. Prior to execution of the Agreement, the Consultant shall file with the District certificates of insurance and endorsements from the insurer(s) certifying to the coverage of all insurance required herein. All evidences of insurance must be certified by a properly authorized officer, agent, general agent or qualified representative of the insurer(s) and shall certify the name of the insured, the type and amount of insurance, the location and operations to which the insurance applies, the expiration date, and provides that the District receives notice at least thirty (30) calendar days prior to the effective date of any policy limit or cancellation of required coverages. The Consultant shall notify the District at least thirty (30) calendar days prior to the effective date of any cancellation or reduction in coverage in the policy. Documentation of coverage shall be provided on each insurance renewal date. The Consultant shall, upon demand of The District, make available to The District at Consultant's local office in The District all such policies of insurance and the receipts of payment of premiums thereon. Failure to provide such policies of insurance within a time acceptable to The District shall entitle The District to suspend or terminate the Consultant's work hereunder, Suspension or termination of this Agreement shall not relieve the Consultant from its insurance obligation hereunder.

- 14.2. The Consultant shall obtain and maintain at a minimum the limits of insurance set forth below. By requiring such minimum insurance, the District shall not be deemed or construed to have assessed the risks that may be applicable to the Consultant under this Agreement. The Consultant shall assess its own risks and, if it deems appropriate and/or prudent, maintain greater limits and/or broader coverage.
- 14.3. Each insurance policy shall be written on an "occurrence" form; excepting that insurance for professional liability, errors and omissions when required, is acceptable on a "claims made" form.
- 14.4. If coverage is approved and purchased on a "claims made" basis, the Consultant shall continue coverage either through (1) policy renewals for not less than seven years from the date of completion of the work which is the subject of this Agreement or (2) the purchase of an extended discovery period for not less than seven years from the date of completion of the work which is the subject of this Agreement, if such extended coverage is available.
- 14.5. If, in order to meet the requirements of this Section, the Consultant must rely on the insurance to be provided by one or more subconsultant, then such subconsultant(s) shall be required to meet all of the requirements herein applicable to the insurance they are providing, and shall include District and Consultant as additional insureds on all liability policies except Professional Liability/Errors & Omissions and Workers Compensation. The District will not make any payments on work performed by subconsultants until all insurance documentation from such subconsultants has been received and accepted by the District.
- 14.6. Provided the affected insurance policies permit the following waiver, without voiding coverage, Consultant and District waive all rights against each other to subrogation for damages covered by property insurance.
- 14.7. The Consultant shall maintain limits no less than, for:
  - A. General Liability. \$1,000,000 combined single limit per occurrence for bodily injury, personal injury and property damage, and for those policies with aggregate limits, a \$1,000,000 aggregate limit. Coverage shall be at least as broad as Insurance Services Office form number (CG 00 01) covering COMMERCIAL GENERAL LIABILITY.
  - B. Professional Liability Errors and Omissions. \$2,000,000 per claim and in the aggregate.
  - C. Automobile Liability. \$1,000,000 combined single limit per accident for bodily injury and property damage. Coverage shall be at least as broad as Insurance Services Office form number (CA 00 01) covering BUSINESS AUTO COVERAGE, symbol 1 "any auto"; or the combination of symbols 2, 8, and 9.
  - D. Workers' Compensation. Statutory requirements of the State of residency. Coverage shall be at least as broad as Workers' Compensation coverage, as required by the Industrial Insurance Act of the State of Washington, as well as any similar coverage required for this work by applicable Federal or "other States" State Law.

- E. Employer's Liability or "Stop Gap". Coverage shall be at least as broad as the protection provided by the Workers Compensation policy Part 2 (Employers Liability) or, in states with monopolistic state funds, the protection provided by the "Stop Gap" endorsement to the general liability policy.
- 14.8. Any deductibles or self-insured retentions must be declared to, and approved by, the District. The deductible and/or self-insured retention of the policies shall not limit or apply to the Consultant's liability to the District and shall be the sole responsibility of the Consultant.
- 14.9. The insurance policies required in this Agreement are to contain, or be endorsed to contain the following provisions:
- A. Liability Policies except Professional Liability & Errors and Omissions and Workers Compensation:
    - 1. The District, its officers, officials, employees and agents are to be covered as additional insured as respects liability arising out of activities performed by or on behalf of the Consultant in connection with this Agreement. Such additional insured status shall include Products-Completed Operations.
    - 2. To the extent of the Consultant's negligence, the Consultant's insurance coverage shall be primary insurance as respects the District, its officers, officials, employees and agents. Any insurance and/or self-insurance maintained by the District, its officers, officials, employees or agents shall not contribute with the Consultant's insurance or benefit the Consultant in any way.
    - 3. The Consultant's insurance shall apply separately to each insured against whom a claim is made and/or lawsuit is brought, except with respect to the limits of the insurer's liability.
    - 4. The Consultant's Protection and Indemnity (to include Jones Act) policy shall waive rights of subrogation against the District.
- 14.10. If at any time of the foregoing policies shall fail to meet the minimum standards above, the Consultant shall, upon notice to that effect from the District, promptly obtain a new policy, and shall submit the same to the District, with the appropriate certificates and endorsements, for approval.

## **SECTION 15: DISPUTES AND REMEDIES**

- 15.1. Choice of Law. This Agreement and all provisions hereof shall be interpreted in accordance with the laws of the State of Washington in effect on the Effective Date.
- 15.2. General Manager Review. All claims, counter-claims, disputes and other matters in question between the District and the Consultant arising out of or relating to this Agreement or the breach of it shall be referred to the General Manager or a designee for determination, together with all facts, data, contentions and so forth which relate thereto. The General Manager shall make a determination within thirty (30) calendar days of such referral.

- 15.3. Mediation and Arbitration. The parties will first attempt to mediate any dispute arising under or in connection with this Agreement, in accordance with the provisions of the Washington Uniform Mediation Act, Ch. 7.07 RCW. In the event such mediation is unsuccessful, any such dispute will be settled by arbitration as set forth in this Section 15.3. No legal right of action may arise out of any such dispute until arbitration has been completed. Each party, however, will have full access to the courts to compel compliance with these arbitration provisions, to enforce an arbitration award or to seek injunctive relief, whether or not arbitration is available or under way. The arbitration will take place as follows:
- A. Notice. The party demanding arbitration must give the other parties a written notice. The written notice must contain, in addition to the demand for arbitration, a clear statement of the issue or issues to be resolved by arbitration, an appropriate reference to the provision of the Agreement which is involved, the relief the party requests through arbitration, and the name and address of the arbitrator requested by the demanding party.
  - B. Response. The party receiving the notice of the demand for arbitration must provide a written response to the demand within fifteen (15) days following receipt of the notice. The response must contain a clear statement of the respondent's position concerning the issue or issues in dispute and the name and address of the arbitrator it selects as the arbitrator to hear the dispute. If the parties fail to agree upon an arbitrator within five (5) days following the time allowed for this response to the demand for arbitration, the demanding party may apply to the presiding department of the Superior Court for Whatcom County, Washington to designate the arbitrator.
  - C. Arbitration. The arbitrator will meet in Bellingham, Washington, within twenty (20) days after the selection of the arbitrator and will allow each party an opportunity to submit oral and written evidence and argument concerning the issue in dispute. The arbitrator may resolve only the question or questions submitted to arbitration and must include as part of his consideration a full review of the Agreement and all material incorporated in the Agreement by reference.
  - D. Decision. The decision of the arbitrator will be final and will bind the parties.
  - E. Consent to Change. By consent of all parties to any dispute under this Agreement, the method of selection of an arbitrator or arbitrators, or even the arbitrator(s) selected, may be changed at any time.
  - F. Payment of Costs. Subject to the provisions of Section 13.3, in any arbitration, each party will pay its own costs, witness fees and attorneys' fees. The fees charged by the arbitrator and the costs of the proceeding shall be borne equally.
  - G. State Law. Except to the extent inconsistent with the terms of this Agreement, the terms and provisions of Chapter 7.04A RCW are incorporated in and made a part of this Agreement.



- 15.4. Exhaustion of Administrative Remedies. Referral to and determination by the General Manager or a designee and mediation and arbitration shall be a condition precedent to the commencement of a civil action to adjudicate such dispute.
- 15.5. Jurisdiction & Venue. Subject to these provisions herein, the Superior Court of Whatcom County, Washington, shall have exclusive jurisdiction and venue over any legal action arising under this Agreement and the laws of the state of Washington shall apply.

## SECTION 16: NOTICE

- 16.1. Any notice required to be given under the terms of this Agreement shall be in writing and directed to the party at the address set forth below. Notice shall be considered issued and effective upon receipt thereof by the addressee-party. Facsimile notice shall be considered effective with proof of confirmation that the addressee has received the facsimile. Such proof would be a confirmation sheet evidencing such receipt at the fax number listed below.

[[[ NAME OF FIRM ]]]  
Attn: ??????????  
[[[ ADDRESS ]]]

Fax No.: ??????????  
Phone: ??????????

Lake Whatcom Water and Sewer District  
Attn: Justin Clary PE, General Manager  
1220 Lakeway Drive  
Bellingham, WA 98229  
Fax No.: 360-738-8250  
Phone: 360-734-9224

## SECTION 17: ENTIRETY, AMENDMENT AND EXECUTION OF AGREEMENT

- 17.1. This Agreement merges and supersedes all prior negotiations, representations and agreements between the Parties relating to the subject matter hereof and constitutes the entire agreement between the Parties.
- 17.2. The Contract documents included in the Agreement are identified below. Any inconsistency or conflict between the Contract documents shall be resolved by giving precedence in the following descending order of importance:
- A. Agreement for Professional Services for **GENEVA RESERVOIR AND SVWTP PUMP HOUSE SEISMIC UPGRADES**, as modified by the latest amendment;
  - B. Exhibit A, Scope of Work, as modified by the latest amendment;
  - C. Exhibit B, Cost Summary, as modified by the latest amendment;
  - D. Exhibit C, Project Schedule, as modified by the latest amendment;
  - E. Exhibit D, Insurance;
  - F. Exhibit E, Allowable ODC's;
  - G. Exhibit F, Key Personnel List; and
  - H. Other
- 17.3. This Agreement shall be executed in two (2) counterpart copies, any of which shall be considered for all purposes as the original.

**IN WITNESS WHEREOF**, the Parties hereto have caused this Agreement to be executed by their respective authorized officers or representatives as of the day and year written below.

Lake Whatcom Water and Sewer District

Consultant

By: \_\_\_\_\_  
(Justin Clary, General Manager)

By: \_\_\_\_\_

Printed Name: \_\_\_\_\_

Title: \_\_\_\_\_

Dated: \_\_\_\_\_

Dated: \_\_\_\_\_

---

APPROVED AS TO FORM:

By: \_\_\_\_\_  
(Robert Carmichael, Attorney for Lake Whatcom  
Water and Sewer District)

Dated: \_\_\_\_\_

---

## **EXHIBIT A**

### **SCOPE OF SERVICES**

#### **Lake Whatcom Water and Sewer District GENEVA RESERVOIR AND SVWTP PUMP HOUSE SEISMIC UPGRADES**

Funding for this project is through a FEMA Hazard Mitigation Grant. The Consultant and its subconsultants agree to include clauses and conditions in the contract scope of work as required by the FEMA Hazard Mitigation Grant.

##### **A1. Project Management**

1. Organize, manage, and coordinate the disciplines required to accomplish the services required for this project. Perform quality assurance/quality control of all final documents. Maintain and enforce the project schedule and budget. Consultant will provide backup documentation of work products as appropriate to adequately record the Consultant's work, including assumptions made, regulation interpretations, methodology used, calculations, rationale supporting recommendations, and meeting or conversation records. Standards for the design deliverables will be provided to the selected consultant during negotiations.

##### **A2. Permitting**

The Consultant shall:

1. Identify all temporary and permanent permits for required construction,
2. Prepare permit applications,
3. Schedule and conduct meetings with permitting agencies, and
4. Assist District with discussions and negotiations with permitting agencies.

##### **A3. Design and Bidding**

The Consultant shall:

1. Develop the design into detailed construction contract documents consisting of plans, specifications, and engineer's cost estimate.
2. The Consultant shall maintain a Plan Holder's List,
3. Conduct a pre-bid conference,
4. Respond to bidder inquiries,
5. Prepare and distribute addenda, and
6. Attend bid opening.

#### A4. Services During Construction

The Consultant shall fully perform or assist with:

1. Construction support services including providing an experienced and qualified project representative to monitor the on-site progress and quality of the executed work,
2. Attend progress meetings,
3. Prepare agenda and meeting notes,
4. Review contractor submittals and shop drawings for conformance to the contract documents,
5. Review and respond to contractor's requests for information and issue design clarifications as necessary,
6. Prepare change orders,
7. Review and approve contractor's payment requests,
8. Coordinate and evaluate specialized testing,
9. Prepare record drawings, and
10. Prepare project close-out documentation.

**EXHIBIT B**

**BILLING RATES**

**Lake Whatcom Water and Sewer District  
GENEVA RESERVOIR AND SVWTP PUMP HOUSE SEISMIC  
UPGRADES**

All work shall be billed per the attached Billing Rate schedule.

Sample

**EXHIBIT C**

**PROJECT SCHEDULE  
GENEVA RESERVOIR AND SVWTP PUMP HOUSE SEISMIC  
UPGRADES**

**Project Schedule**

Permitting and Design	Completion by December 31, 2024
Bidding	Completion by March 1, 2025
Services During Construction	Completion by December 31, 2025

**EXHIBIT D**

**INSURANCE**

**Lake Whatcom Water and Sewer District  
GENEVA RESERVOIR AND SVWTP PUMP HOUSE SEISMIC  
UPGRADES**

[Attach Insurance Certificate and Endorsements]

## **EXHIBIT E**

### **ALLOWABLE OTHER DIRECT COSTS (ODC's) Lake Whatcom Water and Sewer District GENEVA RESERVOIR AND SVWTP PUMP HOUSE SEISMIC UPGRADES**

Allowable ODC's include Subconsultants and Reimbursables as listed in Exhibit B – Billing Rates:

#### **Subconsultants:**

- List Subconsultants.

#### **Reimbursables:**

- Publication charges
- Project application fees, project permit fees
- Reproduction of drawings and construction documents
- Direct expenses for travel, meal and lodging outside of Whatcom and Skagit Counties
- Mileage at project-current IRS mileage rates
- Specialized equipment rental, at rental rate



**EXHIBIT F**

**KEY PERSONNEL LIST  
Lake Whatcom Water and Sewer District  
GENEVA RESERVOIR AND SVWTP PUMP HOUSE SEISMIC  
UPGRADES**

**Key Personnel List**

- Name?
- Name?
- Name?
- Name?

Sample

**GENEVA RESERVOIR AND SVWTP  
PUMP HOUSE SEISMIC UPGRADES  
ATTACHMENT A  
PROJECT INFORMATION**

**Lake Whatcom Water and Sewer District  
Reservoir Seismic Vulnerability Assessment  
Technical Report**

**November 2016**



BHC Consultants, LLC  
1601 Fifth Ave. Suite 500  
Seattle, WA 98101  
(206) 505-3400  
[www.bhcconsultants.com](http://www.bhcconsultants.com)

## 5. Summary of Findings – Structural

### 5.1 Geneva Reservoir

#### 5.1.1 Record Information

The Geneva Reservoir was constructed by Reliable Steel Fabricators (no longer in business) of Olympia, WA in 1979. Original design and shop drawings were provided by the District, along with a December 13, 2012 investigation report by Wilson Engineering of Bellingham, WA and a cleaning and inspection report and video by H2O Solutions dated July 9, 2012. In addition, a soils report by Anvil Corporation dated March 1979 was available. Design drawings and specifications dated May 1979 by Yoshida, Inc. of Seattle, WA were available, as well as shop drawings by Reliable Steel dated May 24, 1979 (see Figures 1 and 2). The shop drawings indicate design in accordance with AWWA D100-84, Seismic Zone 3.






Figure 1 Site Plan from Original Design Drawings



**Figure 2 Elevation View from Original Design Drawings**

The reservoir has a mildly sloped cone roof, supported by 27 channel-shaped rafters which span from the shell to a steel center column. The Wilson report noted a few bolts were missing at rafter connections, but the missing bolts did not appear to be critical. A site location map for the Geneva Reservoir is provided in Figure 3.



GIS Data: Whatcom County GIS.  
 This map is a geographic representation based on information available.  
 No warranty is made concerning the accuracy, currency, or completeness  
 of data depicted on this map.



**BHC Consultants, LLC**  
 1601 Fifth Avenue, Suite 500  
 Seattle, Washington 98101  
 206.505.3400  
 206.505.3406 (fax)  
 www.bhcconsultants.com



**GENEVA RESERVOIR**

Lake Whatcom Reservoir Seismic Vulnerability  
 Lake Whatcom Water & Sewer District  
 November 2016

Figure

**3**

**Figure 3 Geneva Reservoir**



**5.1.2 BHC Field Observations**

General condition, appurtenances, and site conditions appeared consistent with record information. The tank has a single 30 inch diameter shell manhole, and a 2 feet square roof hatch with partial roof railing. The roof is accessed by caged exterior ladder and an un-caged interior ladder (see Figure 4).



**Figure 4 Geneva Reservoir, September 1, 2015**

Water level at the time of examination on July 15, 2015 was 31.3 feet. BHC measured the tank diameter and height, and the height and metal thickness of shell courses, floor, and roof plates. Metal thickness for the shell and roof was measured using a Cygnus 6 Plus Ultrasonic Thickness Gauge. Other dimensions were measured using a steel tape. Record metal thicknesses and measurements are shown in Table 3 below. For analysis, thicknesses were rounded to the nearest 1/32 inch.

**Table 3 – Metal Thicknesses – Geneva Reservoir**

Item	Distance from Top of Floor Plate to Top of Shell Course (ft)		Metal Thickness (in)				
	Record	Measured By Tape	Record	Measured By Tape	Measured Using UT Gauge	Average	Used for Analysis
Roof Plate	N/A		3/16	N/A	0.120, 0.120, 0.120	0.120	3/16
Shell Course 4 (highest)	32.67	32.67	1/4	N/A	0.245, 0.245	0.245	1/4
Shell Course 3	24.52	24.52	1/4	N/A	0.230, 0.230	0.230	1/4
Shell Course 2	16.34	16.34	9/32	N/A	0.265, 0.265	0.265	9/32
Shell Course 1 (lowest)	8.17	8.17	11/32	N/A	0.35, 0.345, 0.345	0.35	11/32
Floor Plate	N/A		1/4	1/4	N/A	1/4	1/4



The measured diameter of the tank is 52 feet, and the shell height is 32 feet 8 inches. The overflow elevation (record) is 32 feet above the floor, for a top capacity of 519,206 gallons compared to a nominal capacity of 500,000 gallons. The tank is held down by 12 steel plate anchors embedded in a concrete ringwall foundation. The ringwall record dimensions are 18 inches wide by 36 inches high. The observed configuration and spacing of the anchors was consistent with the record drawings. Grade was approximately 7 inches below the top of the ringwall. Photos from the site visit are shown in Figures 5 and 6.

Anchored tanks are required by AWWA D100 to have a grout layer between the floor plate and the ringwall at the shell; however, no grout was observed.



**Figure 5 Geneva Reservoir at Shell to Foundation Interface**



**Figure 6 Roof at Entry Hatch**

The interior was observed from the roof hatch and photographed without entering. Framing conditions appeared consistent with record information.

*5.1.3 Summary of Findings – Structural*

Table 4 compares the results of the seismic analysis to standards in AWWA D100-11. Supporting calculations for these ratios are provided in Appendix B.1. The recommended allowable forces do not represent failure loads, but have a liberal safety factor. Anytime the ratio of actual to allowable exceeds about two, however, the demand is approaching ultimate capacity and should be a cause for concern. When comparisons are made on an ultimate strength basis, the safety limit has been reached when the ratio of factored loads to allowable strength is less than 1.0.

Because the predicted sloshing wave will contact the tank roof, the seismic load is considerably increased compared to a tank with adequate freeboard.

<b>Table 4 – Seismic Load vs AWWA D100 Allowable – Geneva Reservoir</b>			
	<b>Analysis</b>	<b>AWWA Requirement</b>	<b>Result</b>
<b>Sloshing Wave</b>			
First Mode Amplitude	3.60 ft.	N/A	
Freeboard at Maximum Operating Level (MOL)	1.17 ft.	N/A	
Wave contacts roof	Yes	No	
Ratio of Wave Height to Wave Freeboard	3.13	≤1.00	<b>No Good</b>

**Lake Whatcom Water and Sewer District  
Reservoir Seismic Vulnerability Assessment  
Technical Report**

<b>Table 4 – Seismic Load vs AWWA D100 Allowable – Geneva Reservoir</b>			
	<b>Analysis</b>	<b>AWWA Requirement</b>	<b>Result</b>
<b>Seismic Load Increase Due to Sloshing Wave Roof Contact</b>			
Base Shear Without Roof Contact	727 kip	N/A	
Base Shear With Roof Contact	913 kip	N/A	
Increase Due to Roof Contact	+26%	N/A	
Overturning Without Roof Contact	9,207 kip-ft.	N/A	
Overturning With Roof Contact	11,229 kip-ft.	N/A	
Increase Due to Roof Contact	+22%	N/A	
Sloshing Force on Roof-Shell Joint	1,201 plf	N/A	
<b>Shell Static Stress</b>			
Maximum hoop tensile stress/allowable ratio	1.05 at base. 1.02 at bottom of second course	1.0	Say OK See Item 1 in Seismic Evaluation Summary below
<b>Shell Seismic Stress</b>			
Maximum hoop tensile stress/allowable Ratio	1.36	≤ 1.33	Say OK See Item 1 in Seismic Evaluation Summary below
Maximum longitudinal compressive stress/allowable Ratio	0.67	≤ 1.33	OK
Maximum longitudinal tensile stress/allowable ratio	0.15	≤ 1.33	OK
Maximum shear stress/allowable at shell to floor connection	0.24	≤ 1.33	OK
<b>Anchors</b>			
Anchor spacing	12.5 ft.	≤ 10 ft.	No Good
Predicted/Allowable Stress Ratio (anchor top plate)	9.61	≤ 1.33	No Good
Predicted/Allowable Stress Ratio (anchor embedded plate)	6.40	≤ 1.33	No Good
Predicted/Allowable Stress Ratio (anchor weld at shell)	7.15	≤ 1.33	No Good
Predicted/Allowable Stress Ratio (anchor splice weld))	5.36	≤ 1.33	No Good
Bond Stress/Allowable Stress (embedded plate)	7.27	≤ 1.33	No Good
<b>Foundation</b>			
Overturning safety factor	0.92	≥ 1.67	No Good
Uplift safety factor	0.24	≥ 1.0	No Good, Uplift occurs

<b>Table 4 – Seismic Load vs AWWA D100 Allowable – Geneva Reservoir</b>			
	<b>Analysis</b>	<b>AWWA Requirement</b>	<b>Result</b>
Base shear/friction resistance at floor level	0.24	≤ 1.33	OK
Bearing pressure/allowable	2.44	≤1.33	No Good
<b>Check Stability As Unanchored Tank</b>			
Stability ratio, J	9.45	≤1.54	Unstable

**5.1.4 Seismic Evaluation Summary**

1. The static hoop stress at the base of the shell is overstated because the calculations typically ignore the restraint provided by the floor plate. The static hoop stress at the base of the second shell course is within 2 percent of allowable. Consider all shell plates adequate for static as well as seismic hoop and compression stresses.
2. Anchors are inadequate. If anchors fail, the tank would behave as if unanchored but the tank does not have the required stability without anchors and could fail catastrophically.
3. The existing ringwall does not provide enough weight to prevent uplift by a wide margin, even assuming it could be adequately anchored. This means that much of the ringwall will be subject to bending and torsional forces for which it was not designed, and the bottom of the tank could pull apart from the shell, with catastrophic failure.
4. The safety factor against overturning is insufficient.

**5.2 Division 22 Reservoir**

**5.2.1 Record Information**

The Division 22 Reservoir was constructed by Union Tank Company (no longer in business) of Seattle, WA in 1971. The nameplate indicates the use of the AWWA D100 standard. Original design drawings were prepared by Horton Dennis Engineers and were provided to BHC by the District, along with a cleaning and inspection report and video by H2O Solutions dated July 12, 2012 (see Figures 7 through 9). The Division 22 Reservoir design drawing provided basic dimensional data for the Division 7 and 30 Reservoirs on the same sheet. An original soils report by Dames and Moore was referenced but the report was unavailable.

A new reservoir near the existing one has been proposed with a capacity of 630,000 gallons. A recent soils report for this companion reservoir was prepared by PanGeo in December 2014 and recommended the use of Site Class C for design purposes. A site location map for the Division 22 Reservoir is provided in Figure 10.

# LAKE WHATCOM WATER AND SEWER DISTRICT

WHATCOM COUNTY

WASHINGTON



## SUDDEN VALLEY WATER TREATMENT PLANT ASSESSMENT REPORT

G&O #20434  
JULY 2020



**Gray & Osborne, Inc.**  
CONSULTING ENGINEERS



# LAKE WHATCOM WATER AND SEWER DISTRICT

WHATCOM COUNTY

WASHINGTON



## SUDDEN VALLEY WATER TREATMENT PLANT ASSESSMENT REPORT



G&O #20434  
JULY 2020



**Gray & Osborne, Inc.**

CONSULTING ENGINEERS

# TABLE OF CONTENTS

## EXECUTIVE SUMMARY

### CHAPTER 1 – INTRODUCTION AND EXISTING FACILITIES

INTRODUCTION .....	1-1
BACKGROUND AND EXISTING FACILITIES .....	1-1
Water Rights and Projected Demand .....	1-2
Water Treatment Plant (WTP) .....	1-3
Raw Water Intake .....	1-3
Raw Water Pumps .....	1-4
Raw Water Flow Meter .....	1-4
Flocculation .....	1-5
Rapid Rate Filters .....	1-5
Clearwell .....	1-7
Chlorine Disinfectant Injection System .....	1-8
Chlorine Contact Basin .....	1-8
Finished Water Pumping .....	1-10
Chemical Dosing Systems .....	1-10
Auxiliary Power Systems .....	1-11
Instrumentation .....	1-11

### CHAPTER 2 – WTP CONDITION ASSESSMENT

INTRODUCTION .....	2-1
TREATMENT/PROCESS CONDITION ASSESSMENT .....	2-1
WTP Main Building .....	2-1
Intake Piping .....	2-1
Raw Water Pumps .....	2-2
Raw Water Flow Meter .....	2-3
Flocculation .....	2-3
Rapid Rate Media Filters .....	2-4
Clearwell .....	2-5
Chlorine Disinfectant Injection System .....	2-6
Chemical Dosing Systems .....	2-7
Instrumentation .....	2-9
Finished Water Pump Building .....	2-9
Finished Water Pumping .....	2-9
Chlorine Contact Basin .....	2-10
STRUCTURAL CONDITION ASSESSMENT .....	2-10
WTP Main Building .....	2-11
Finished Water Pump Building .....	2-12
Chlorine Contact Basin .....	2-13
ARCHITECTURAL CONDITION ASSESSMENT .....	2-13
General Architectural .....	2-13
WTP Main Building .....	2-14
Finished Water Pump Building .....	2-16

MECHANICAL CONDITION ASSESSMENT .....	2-17
WTP Main Building.....	2-17
Finished Water Pump Building.....	2-18
ELECTRICAL CONDITION ASSESSMENT .....	2-18
General Electrical.....	2-18
WTP Main Building.....	2-19
Finished Water Pump Building.....	2-20
Telemetry/SCADA .....	2-21

### **CHAPTER 3 – TREATMENT IMPROVEMENTS**

INTRODUCTION .....	3-1
TREATMENT/PROCESS RECOMMENDATIONS .....	3-1
High Priority Improvements .....	3-1
WTP Main Building.....	3-1
Recommended Improvements .....	3-4
WTP Main Building.....	3-4
Finished Water Pump Building.....	3-6
STRUCTURAL RECOMMENDATIONS.....	3-6
High Priority Improvements .....	3-6
WTP Main Building.....	3-6
Finished Water Pump Building.....	3-7
Recommended Improvements .....	3-7
WTP Main Building.....	3-7
Chlorine Contact Basin.....	3-7
ARCHITECTURAL RECOMMENDATIONS .....	3-8
High Priority Improvements .....	3-8
WTP Main Building.....	3-8
Finished Water Pump Building.....	3-9
Recommended Improvements .....	3-9
General Architecture.....	3-9
WTP Main Building.....	3-9
MECHANICAL RECOMMENDATIONS .....	3-10
High Priority Improvements .....	3-10
WTP Main Building.....	3-10
Recommended Improvements .....	3-10
General Mechanical .....	3-10
Finished Water Pump Building.....	3-10
ELECTRICAL RECOMMENDATIONS .....	3-10
High Priority Improvements .....	3-10
General Electrical.....	3-10
WTP Main Building.....	3-11
Finished Water Pump Building.....	3-12
Recommended Improvements .....	3-12
WTP Main Building.....	3-12
Finished Water Pump Building.....	3-12
SUMMARY .....	3-13



## LIST OF TABLES

<b><u>No.</u></b>	<b><u>Table</u></b>	<b><u>Page</u></b>
ES-1	Sudden Valley WTP High Priority Modifications Summary .....	E-2
1-1	Water Rights Summary .....	1-2
1-2	Water Demand Summary .....	1-3
1-3	Sudden Valley WTP Media Filter Summary .....	1-6
1-4	Sudden Valley WTP Chlorine Contact Basin Design Criteria Summary .....	1-9
1-5	Sudden Valley WTP Flow Meter Summary .....	1-12
3-1	Sudden Valley WTP High Priority Modifications Summary .....	3-14
3-2	Sudden Valley WTP Recommended Modifications Summary .....	3-15

## LIST OF FIGURES

<b><u>No.</u></b>	<b><u>Figure</u></b>	<b><u>Follows Page</u></b>
1-1	Reservoir Service Areas and Existing Facilities .....	1-2

## LIST OF APPENDICES

- Appendix A – Existing Facility Photographs
- Appendix B – Daily Monitoring Report Information
- Appendix C – Tier 1 Seismic Analysis Checklist
- Appendix D – WSDOH 2020 Sanitary Survey
- Appendix E – Chlorine Gas Storage Information

## **EXECUTIVE SUMMARY**

The Lake Whatcom Water and Sewer District (District) contracted with Gray & Osborne to perform a condition assessment for their existing Sudden Valley Water Treatment Plant (WTP). This assessment is part of a larger project that includes a holistic analysis of the South Shore Water System and its components, including treatment, distribution systems, and water sources. The first step in this process is to complete a condition assessment of the existing treatment plant system. The purpose of the assessment is to investigate the integrity of the existing WTP facilities from a structural, electrical, mechanical, architectural, and process perspective in order to guide the District's decisions on use and/or modifications at the WTP. Following this assessment, the District along with Gray & Osborne will complete an alternatives analysis based on the findings and recommendations within the assessment report. Using this alternatives analysis report, the District can then select the most cost-effective alternative(s) and proceed with selected modifications.

The existing WTP is a rapid rate direct filtration plant that uses chlorine gas for disinfection. The plant was originally constructed in 1972 and has a rated capacity of 2.0 million gallons per day (mgd). The WTP has been upgraded several times since its construction, most recently in 1992. The WTP treats surface water from Lake Whatcom and is located on Morning Beach Drive approximately 1 mile northeast of the intersection of Lake Whatcom Boulevard and Marigold Drive.

A site visit was completed on February 12, 2020 by Gray & Osborne process, mechanical, electrical, and structural engineers. During the visit, Gray & Osborne discussed the current operations, perceived deficiencies, and desired needs for the WTP with operations staff, and also assessed the condition of the existing facilities at both the WTP Main Building, Finished Water Pump Building, and Chlorine Contact Basin.

The condition assessment found several items for improvement, but did not find any significant structural, electrical, mechanical, or operational issues that would prevent the WTP from successful operation for the foreseeable future. In general, the facilities are in good condition and only require minor repairs and the completion of regular maintenance items in order to maintain their current function.

The report below does make some recommendations for alternatives that, if enacted, may improve the operational efficiency of the WTP. In addition to these recommendations and the listed repairs, this assessment has identified a number of high-priority improvements that should be addressed to ensure the successful operation of the facility in the future. Table ES-1 provides a summary of the high priority repairs and improvements to the facility.

**TABLE ES-1**

**Sudden Valley WTP High Priority Modifications Summary**

<b>Modification</b>	<b>Location<sup>(1)</sup></b>	<b>Discipline<sup>(2)</sup></b>
Conduct chlorine disinfection system alternatives analysis	MB	P
Chlorine gas system modifications	MB	P
Alum storage and metering pump system modifications	MB	P
Soda Ash storage and metering pump system modifications	MB	P
Conduct backwash system alternatives analysis	MB	P
Replace existing clearwell and CCB level switches	MB	P
Replace corroded steel supports	MB	S
Prepare and coat steel tanks (Floc, Soda Ash, and Filters 1/2)	MB	S
Install seismic bracing for electrical conduit, electrical equipment, and treatment equipment	MB/FPB	S
Complete detailed structural evaluation	MB/FPB	S
Relocate existing laboratory electrical equipment	MB	A
Remove soil cover, vegetation growth, and organic debris from building exterior and roof	MB	A
Provide water upgrades to safety shower and eyewash	MB	A
Add fire and smoke alarm system	MB/FPB	A
Investigate current heating schedule	MB/FPB	M
Combine all existing plant records into a single as-built planset	MB/FPB	E
Complete a comprehensive electrical system audit	MB/FPB	E
Remove chemicals and metering equipment away from MCCs	MB	E
Review historical peak demand electrical consumption	MB/FPB	E
Replace MCC1 and MCC2 with new, current technology	MB/FPB	E
Replace MCC3 to address panel and interior component corrosion	MB	E

(1) MB = WTP Main Building. FPB = Finished Water Pump Building. CCB = Chlorine Contact Basin.

(2) P = Process, S = Structural, A = Architectural, M = Mechanical, and E = Electrical.

If the recommendations listed in Table ES-1 are addressed, the WTP appears capable of successfully, effectively, and efficiently meeting the District’s water treatment needs for at least the next 10 to 20 years. Although the original facility is nearly 50 years old, the structures are in good overall condition and do not appear to need significant structural, electrical, mechanical or process modifications.

Based on the findings listed in table ES-1, the District along with Gray & Osborne will complete the second phase of the project. This second phase will include a more thorough analysis of treatment alternatives that will help fully identify the desired scope of modifications to the WTP. This analysis will also help define key design parameters, system requirements, and permitting issues. Lastly, defining the full and complete scope of modifications will also allow the District to develop accurate cost estimates that can be used for budgeting and planning purposes.

# **CHAPTER 1**

## **INTRODUCTION AND EXISTING FACILITIES**

### **INTRODUCTION**

The Lake Whatcom Water and Sewer District (District) contracted with Gray & Osborne to perform a condition assessment for the existing Sudden Valley Water Treatment Plant (WTP) as part of a larger effort to analyze the District's water treatment facilities in order to prioritize funds for rehabilitation, modification, and/or replacement projects. The goal of the assessment is to identify potential improvements for the existing structures and current treatment processes in an attempt to maximize treatment efficiency and extend the operational life of these facilities. The report can also be used to guide selection of feasible water treatment alternatives for longer term treatment of the Lake Whatcom source.

This report summarizes the findings of the WTP condition assessment, which was conducted on February 12, 2020. During this assessment Gray & Osborne personnel investigated the process, operations, structural, architectural, mechanical, and electrical components for the WTP.

Chapter 1 of this report provides a brief background on the District's South Shore Water System and description of water rights for the system. It also includes a description of each of the components utilized for water intake and treatment at the WTP.

Chapter 2 of this report summarizes the findings of the assessment with regards to process, structural, architectural, mechanical, and electrical disciplines.

Finally, Chapter 3 of this report provides a summary of the improvements that would be required for these facilities to meet current structural, mechanical, and electrical codes. This chapter also summarizes the modifications that may help to optimize the treatment process and provide a more efficient workspace for operations staff.

### **BACKGROUND AND EXISTING FACILITIES**

The District operates three Group A water systems - South Shore (DOH #95910), Eagleridge (DOH #08118), and Agate Heights (DOH #52957) - all of which are in and around the shores of Lake Whatcom, which lies southeast of Bellingham in Whatcom County, Washington. The District serves approximately 3,900 residential and commercial water system connections with a residential population of approximately 10,000 people.

The South Shore system is the largest of the three systems and is supplied wholly by water treated at its Sudden Valley Water Treatment Plant. In addition to the WTP, the

District also owns and maintains surface water source, storage, and distribution system facilities. Figure 1-1 shows a map of the District’s service area and highlights the location of major facilities. The distribution system includes multiple pressure zones, four booster stations, and approximately 2.8 MG of storage in five reservoirs.

The District also maintains a secondary intertie with the City of Bellingham Water System (DOH #50600) that is used only during emergency situations.

**WATER RIGHTS AND PROJECTED DEMAND**

The District’s Sudden Valley water rights are summarized in Table 1-1. A more detailed discussion of the District’s water rights is included in the current Water System Plan (*Wilson Engineering, 2018*). According to the Water System Plan, the District maintains adequate water rights for their existing demands as well as projected maximum day demands.

**TABLE 1-1**


**Water Rights Summary**

Location	Type	Number	Instantaneous Flow (gpm)	Maximum Annual Withdrawal (acre-feet)
South Shore (Sudden Valley and Geneva)	Surface Water	S1-00736C S1-00734C R1-25120C S1-25121P	1,526	1,800
Eagle Ridge	Intertie <sup>(1)</sup>	N/A	150	-
Agate Heights	Groundwater	G1-22681P CG1-22763P CG1-23449C	438	506.9
<b>Total</b>			<b>1,964<sup>(2)</sup></b>	<b>1,800</b>

(1) With City of Bellingham, who maintains a large surface water source from Lake Whatcom.

(2) Does not include Eagleridge Intertie water rights.


The District’s average day demand (ADD) and maximum day demand (MDD) are summarized in Table 1-2. A more detailed discussion of the District’s historical, current, and projected system demands is included in the current Water System Plan (*Wilson Engineering, 2018*). According to the Water System Plan, the District's existing water rights are sufficient to meet projected ADD and MDD for the South Shore system. While the District may possess sufficient water rights to meet projected demands, the data in Table 1-2 suggest that the existing WTP cannot meet these projected demands with its current operational flow of 700 gallons per minute (gpm). The assessments below will address capacity limitations for the individual components of the treatment process. Additionally, Appendix B contains a summary of the District’s monthly treatment reports for 2018 and 2019.



**Legend**

- ZONES
- GENEVA RESERVOIR
- DIVISION 22 RESERVOIR
- DIVISION 30 RESERVOIR
- DIVISION 7 RESERVOIR

Source: City of Bellingham, Whatcom County & LWUSD



**LAKE WHATCOM WATER & SEWER DISTRICT**  
**SUDDEN VALLEY WTP ASSESSMENT**  
 FIGURE 1-1  
 RESERVOIR SERVICE AREAS  
 AND EXISTING FACILITIES

**Gray & Osborne, Inc.**  
 CONSULTING ENGINEERS

**TABLE 1-2**

**Water Demand Summary**

<b>Parameter</b>	<b>2020</b>	<b>2036</b>	<b>Buildout</b>
Sudden Valley ADD (gpd) <sup>(1)</sup>	405,000	415,500	490,000
Geneva ADD (gpd)	200,000	208,000	217,000
<b>Combined ADD (gpd)</b>	<b>605,000</b>	<b>623,500</b>	<b>707,000</b>
Sudden Valley MDD (gpd) <sup>(2)</sup>	675,000	691,000	817,000
Geneva MDD (gpd)	422,000	440,000	458,500
<b>Combined MDD (gpd)</b>	<b>1,097,000</b>	<b>1,131,000</b>	<b>1,275,500</b>
8-Hour Filter Capacity (gallons @ 700 gpm/1,000 gpm)	336,000/480,000		
16-Hour Filter Capacity (gallons @ 700 gpm/1,000 gpm)	672,000/960,000		
WTP Rated Capacity (gpd) <sup>(3)</sup>	2,000,000		

- (1) ADD values taken from 2018 WSP and based on consumption of 150 gpd/ERU.
- (2) MDD values taken from 2018 WSP and based on consumption of 250 gpd/ERU.
- (3) Based on a current filter surface area of 252 sf and a maximum allowable filtration rate of 6.0 gpm/sf.

**WATER TREATMENT PLANT (WTP)**

The existing WTP is a rapid-rate, direct filtration plant with a rated capacity of 2.0 million gallons per day (mgd) but currently operates at approximately 1.01 mgd (700 gpm). The WTP is housed in a partially below grade concrete building located on Morning Beach Drive approximately 1 mile northeast of the intersection of Lake Whatcom Boulevard and Marigold Drive. The facility was constructed in 1972 and has undergone several minor improvements since that time, but was most recently upgraded in 1992. The WTP provides coagulation, flocculation, filtration, disinfection, and chlorine contact time before treated water is pumped to the distribution system and storage reservoirs. Each of the individual components of the treatment process is described below. Photographs of the components listed below are provided in Appendix A.

**Raw Water Intake**

The raw water intake draws from within Lake Whatcom, the shoreline of which is approximately 300 feet from the WTP. The intake structure is located approximately 300 feet from the shoreline at a depth of approximately 70 feet below the water surface. The intake structure consists of a 36-inch diameter tee fitting, intake screens, and transition fittings to connect to the 24-inch ductile iron pipe that proceeds from the intake structure to the shoreline. Near the shoreline, the piping transitions from 24-inch to 10-inch diameter. Approximately 100 feet inland from shore, the incoming piping

includes valves for system isolation, check valves to maintain a flooded pipe, overflow/pressure relief appurtenances, and fittings necessary to direct the pipe to the WTP. From this valve assembly, the 10-inch diameter ductile iron pipe continues an additional 200 feet to the entrance at the WTP.

Raw water quality is typically good throughout the year at this location. Annually, raw water temperature ranges between 5.0 - 10.0 degrees C, pH ranges between 6.9 - 7.5, and turbidity ranges between 0.1 - 1.4 NTU. Turbidity fluctuates seasonally and tends to increase during the spring and fall stormy season, or during periods of extended wet weather. A summary of daily water quality information for 2018 and 2019 is provided in Appendix B.

The intake piping is inspected every 5 years, was most recently inspected in 2017 by H<sub>2</sub>O Solutions, LLC.

### **Raw Water Pumps**

Inside the WTP, two raw water pumps move raw water from the intake piping, past the chemical injection point, and up to the flocculation tank. Both raw water pumps are located below grade level in a pit adjacent to the flocculation tank. The pumps are accessed by a single, vertical, ladder. The pump pit is covered with aluminum grating and clear plastic sheeting to prevent small objects from falling into the pit.

Both Raw Water Pump 1 and Raw Water Pump 2 are horizontal, centrifugal pumps. The pumps are driven by 20 hp, 3-phase, 1,180 rpm, totally enclosed, fan cooled (TEFC) variable speed motors. Each pump is capable of providing up to 1,400 gpm at 25 feet total dynamic head (TDH). The pumps are operated on an alternating lead/lag schedule and their operational motor speed is controlled by their variable frequency drive (VFD) motor starter which is currently set to deliver approximately 700 gpm each. Both Raw Water Pumps were installed in 1992. In 2002, the District replaced the motor on Raw Water Pump 1. Both pumps are maintained regularly according to the manufacturer's recommended schedule, and performance issues with the pumps are addressed as required.

### **Raw Water Flow Meter**

The raw water flow meter is located at grade level downstream from the raw water pumps. The flow meter is a 10-inch diameter Toshiba LF400 Series magnetic flow meter with an integral transmitter, local display, and flanged connections. The display shows both the instantaneous flow as well as the cumulative total flow through the meter. The flow values are also displayed on the WTP Supervisory Control and Data Acquisition (SCADA) system and are recorded for trending and tracking purposes. In 2020, the District purchased a replacement raw water flow meter, which is stored onsite and can be installed quickly if the existing raw water meter should fail.



## **Flocculation**

Once through the raw water pumps, water proceeds through approximately 30 feet of piping before entering the flocculation tank. The flocculation tank is a painted, welded steel tank with a diameter of 13.5 feet, a height of 8.6 feet, and a nominal volume of 9,000 gallons. The tank is divided into three equal sections and water flows through the tank in an over-under-over pattern. The tank contains one access ladder welded to the outer sidewall. The tank is coated on both the interior and exterior surfaces; however, the specific coating system components are not known.

The flocculation tank is equipped with a high level float. As the water level rises within the flocculation tank, the float activates and de-energizes the raw water pumps, thus stopping flow to the tank and preventing an overflow condition. This high alarm signal is also relayed to the WTP SCADA system which alerts the WTP staff that the system requires inspection.

The flocculation tank can also provide priming water for the raw water pumps should the intake check valve fail or leak. If needed, water is piped from the flocculation tank down to the intake side of the raw water pump to ensure that the intake piping remains full prior to raw water pump startup. Without this piping connection, the intake piping could empty; and the raw water pumps would lose prime, which will lead to excessive wear and in-rush electrical currents during startup. The WTP staff recently replaced the intake check valve and no longer uses this priming piping; however, the piping is maintained so that it is available for future use.

## **Rapid Rate Filters**

Water leaves the flocculation tank via 12-inch diameter ductile iron piping and is conveyed by gravity to the equalization trough. At the trough, water is evenly distributed among the four filter units. Each filter unit consists of an inlet trough, filter media, an underdrain system, surface wash and backwashing equipment, and filtered water piping.

Filter media includes anthracite, sand, and garnet (Table 1-3). Each filter has a surface area of approximately 63 square feet, a depth of 10 feet, and a nominal media volume of 273 cubic feet. At a typical operational flow of 700 gpm (~1 mgd), the surface loading rate for all four filters is 2.8 gpm/sf, which is well within the maximum allowable rate listed by the Washington State Department of Health (DOH) for a multi-media filter (6 gpm/sf). The surface loading rate using only two filters is 5.55 gpm/sf (700 gpm/126 sf), which suggests that the WTP can operate at the typical flow rate with only two filters in service.

Filters 1 and 2 are contained within a common welded and coated steel tank that rests on a concrete equipment pad. Filters 3 and 4 are contained within a marine grade aluminum tank that rests on a concrete equipment pad.

Typically, the WTP operates for 10 to 16 hours each day, and longer during warm summer months when water demand is high.

**TABLE 1-3**

**Sudden Valley WTP Media Filter Summary**

Parameter	Value
Type	Gravity, Direct Filtration
Filter area (sf, total)	252 (4 each at 63 sf)
Rate of Filtration @ 700 gpm (gpm/sf)	2.8
Rate of Filtration @ 1,000 gpm (gpm/sf)	4.0
Rate of Filtration @ 1,390 gpm (gpm/sf) <sup>(1)</sup>	5.5
Rate of Filtration @ 1,526 gpm (gpm/sf) <sup>(2)</sup>	6.0
Rate of Backwash (gpm/sf)	20.6
Design Media Depth (inches)	
#1A Anthracite (1.0 mm - 1.1 mm)	18"
F16 Sand (0.45 mm - 0.55 mm)	9"
#50 Garnet Sand (0.28 mm - 0.38 mm)	4.5"
#12 Garnet Gravel (1.46 mm - 1.56 mm)	4.5"
#3 Gravel (0.375" - 0.1875")	3"
#2 Gravel (0.75" - 0.375")	3"
#1 Gravel (1.50" - 0.75")	10"

(1) Value is based on WTP rated capacity of 2.0 mgd.

(2) Value is based on current South Shore Water System Water Right (Table 1-1).

During normal filter operation, water is distributed evenly to all four cells and flows through the filter media and into the respective underdrain chambers. As it passes through the filter media, flocculated sediment and small particles are trapped by the media. As additional particles are trapped on the surface of the filter, both the headloss through the filter media and the turbidity of the filtered water increases. Per the District's normal operating procedures, each filter bed is backwashed each day prior to operating the filters.

Once through the filters, water flows through the filter discharge piping to the clearwell. The discharge piping at each filter consists of isolation valves, flow control valves, chemical injection fittings, and flow meters in order to ensure consistent operation.

During the backwash of a filter cell, water from the distribution system served by the District 7 Reservoir flows *upward* by gravity through the filter at approximately 1,300 gpm (20.6 gpm/sf). The backwash flowrate is measured by a magnetic flow meter on the backwash line located on the south wall of the WTP. At this flowrate, the media bed is fluidized to remove the accumulated sediment particles and the particle laden backwash water flows into the filter cell waste trough and into the backwash storage basin. Each filter also includes a surface wash system that consists of two supply arms

with up to nine nozzles on each side (18 total nozzles). The pressure and flow of backwash water through these nozzles causes the arms to rotate and disperse spray that agitates the media surface. Spray from these nozzles only occurs during backwash and helps to prevent the formation of mudballs on the media bed. The complete backwash sequence includes the following steps:

- 4.0 minutes of surface wash only;
- 2.5 minutes of surface wash and filter backwash;
- 5 minutes of filter backwash;
- up to 20 minutes settling, equalization, and drainage; and
- 15 minutes of filter to waste.

After this backwash sequence, the filters return to normal operation and water flows through the filters and into the clearwell. According to WTP staff, the entire backwash process for all four filters typically takes 120 to 160 minutes.

The backwash storage basin is located underground between the WTP building and the finished water pump building. The basin has a volume of approximately 16,000 to 17,000 gallons and provides an opportunity for settling of the removed particles. Backwash water within the basin is pumped via one of two submersible pumps several times as part of each backwash sequence. The backwash water is pumped to the residential sewer system where water proceeds to the City of Bellingham's Post Point Wastewater Treatment Plan (WWTP) for treatment. Overflow from the backwash basin is directed back to Lake Whatcom.

## **Clearwell**

Once through the media filters, water flows through 6-, 8-, and 10-inch diameter piping to the clearwell. The clearwell is a concrete basin below the floor slab of the WTP and is accessed via a 24-inch access hatch in the clearwell's northwest corner. The access hatch is located very near the entrance to the WTP and contains a gasketed lid designed to prevent intrusion of liquids or debris.

Based on record drawings, the footprint of the clearwell is 439 square feet, which at the maximum operating depth of 6.25 feet results in a volume of 20,520 gallons.

The WTP utilizes two identical transfer pumps to move water from the clearwell to the chlorine contact basin and pump operation is rotated for each pumping cycle. Each transfer pump is a 20 hp, 60 Hz, 1,760 rpm, Peerless vertical turbine pump with a listed capacity of 1,400 gpm at 43 feet TDH. The pumps operate at full speed and flow (1,400 gpm), and cycle on and off depending on the water level within the clearwell.

The clearwell contains a pressure transducer that reads and records the water level. When the water level within the clearwell rises to the upper setpoint, one transfer pump will energize. There is a 3-foot operating range within the clearwell based on the upper

water level setpoint of 6'-3" and the lower water level setpoint of 3'-3". If the high alarm water level setpoint (7'-2") in the clearwell is reached, the filter system will shut down to avoid additional filling of the clearwell. High level indication/alarm is provided by an Autocon Selectrol 3500 mercury switch. The clearwell also contains an overflow pipe with an elevation of 8'-0" above the floor. This overflow pipe will deliver water by gravity back to Lake Whatcom.

### **Chlorine Disinfectant Injection System**

The WTP utilizes a gas chlorine injection system to provide disinfectant chemicals to the filtered water. This disinfectant provides the necessary chlorine residual to meet the concentration and contact time (CT) requirements set forth by DOH. Commercially prepared chlorine gas is delivered to the WTP in 150-pound cylinders and stored within a separate room inside the WTP. Two active cylinders and two spare cylinders are maintained onsite at all times. The active cylinders are stored on a scale, and specialized gas regulators and flow meters provide the desired gas flow. The chlorine supply to Filters 1 and 2, Filters 3 and 4, and the flocculation tank are all controlled separately using individual flow regulators and meters.

Chlorine gas is mixed with a sidestream of filtered water creating a hypochlorite solution that is then injected to the piping between the filter units and the clearwell. Additionally, a small amount of chlorine solution is injected to the first chamber of the flocculation tank, which helps prevent algal growth on the filter media. Because the WTP operates at a single flow rate, the chlorine system is adjusted manually as needed and does not include automated flow control.

The chlorine room at the WTP contains two chlorine gas sensors, which will warn operations staff of a potential leak so that appropriate ventilation and safety procedures can be followed.

### **Chlorine Contact Basin**

Filtered water is pumped from the clearwell via the transfer pumps to the chlorine contact basin (CCB). The CCB was constructed in 1994 and is a circular, baffled, welded steel reservoir located adjacent to the Finished Water Pump Building. Design information for the CCB is summarized in Table 1-4.

**TABLE 1-4**

**Sudden Valley WTP Chlorine Contact Basin Design Criteria Summary**

<b>Parameter</b>	<b>Value</b>
Year Constructed	1994
Type	Welded steel
Shape	Circular
Height (ft)	25
Diameter (ft)	40
Base elevation (ft)	336.0
Overflow elevation (ft)	360.0
Volume (gal)	225,000
Gallons per foot	9,400
Inlet/Outlet	10-inch Perforated Riser

Water enters the CCB via a diffuser riser at one end and flows in a serpentine fashion between three steel baffles to the outlet diffuser. The inlet diffuser consists of a 10-inch diameter PVC pipe with 25, 2-inch diameter holes drilled at approximately 9.25-inches on center. The outlet diffuser riser consists of a 10-inch diameter PVC pipe with 50, 2-inch diameter holes drilled at approximately 9.25-inches on center. These risers act to promote consistent flow throughout the full depth of the water column from the inlet to the outlet. The CCB has both exterior and interior coatings. The CCB is inspected every 5 years, was most recently inspected in 2017 by H<sub>2</sub>O Solutions, LLC.

The CCB utilizes a single, mercury level switch for high level alarm within the tank; however, the District plans to install a redundant alarm sometime in 2020. The switch communicates the alarm signal to the WTP PLC, which relays the alarm to WTP staff. Water level (depth) is measured using a pressure transmitter. Access to the CCB is provided by two 36-inch diameter manways located on opposite sides of the tank at ground level, as well as a 24-inch access hatch on the roof of the tank.

In 2016, Gray & Osborne conducted a formal tracer analysis on the District’s CT system, which included the chlorine gas injection system and CCB. Surface water systems in Washington must provide a minimum level of CT to protect water quality and ensure disinfection of treated water. CT is the product of the chlorine residual (C) and the residence time within the contact basin (T). The residence time used for calculating CT is a function of the flow through the basin, minimum volume within the contact basin, and the baffling efficiency of the basin. The study conducted on the CCB at the WTP in 2016 showed a baffling efficiency of 0.3, which is less than the theoretical value of 0.7 that the WTP had previously been using. As a result of the tracer study, the WTP staff have made several operational changes in order to ensure that they consistently provide suitable disinfection of treated water leaving the WTP. One of these operational changes was to maintain a maximum allowable flow through the plant of 1,000 gpm while a

second operational change was to increase the target chlorine residual dose from 0.8 to a minimum of 1.0 mg/L.

### **Finished Water Pumping**

Four finished water pumps pump water from the CCB to either the Division 7 or the Division 22 Reservoirs. These pumps are energized and/or de-energized based on the water levels within these reservoirs. The pumps are located in the Finished Water Pump Building adjacent to the CCB. This building also contains electrical equipment for the pumps, a small laundry facility, network and surveillance equipment, as well as the auxiliary generator for the WTP. The building also contains two adjoining public restrooms (mens and womens) available for use by beach/park patrons. At the time of our onsite assessment, the restrooms had been closed for the winter and were inaccessible.

The four pumps are served by a common 10-inch intake header with two pumps providing flow to the Division 7 Reservoir and two pumps providing flow to the Division 22 Reservoirs. The Division 7 Reservoir pumps are 100 hp, 60 Hz, 1,780 rpm, vertical centrifugal pumps with a design point of 700 gpm at 445 feet TDH. The Division 22 Reservoir pumps are 150 hp, 60 Hz, 1,780 rpm, vertical centrifugal pumps with a design point of 700 gpm at 608 TDH. Each pump is connected to a discharge flow control valve that regulates the discharge flow and pressure to the distribution system. Flow from each set of pumps is monitored by a flow meter. Instantaneous and total flow are measured by the meter and displayed and recorded on the WTP's SCADA system.

### **Chemical Dosing Systems**

The WTP utilizes two chemicals in its treatment system in addition to chlorine disinfectant. The first is potassium aluminum sulfate (alum), which is a common coagulant used in water treatment processes. Alum is stored within a 1,900-gallon polyethylene storage tank with a diameter of 6.2 feet and a height of 8.5 feet. The storage tank supplies a diaphragm chemical metering pump, which injects the alum in to the raw water piping upstream of the flocculation tank. The alum chemical feed pump is a Pulsatron E Series with a listed capacity of 44 gpd and a maximum pressure of 100 psi.

Alum is delivered by a commercial vendor approximately every 3 months. The vendor connects a hose from the delivery vehicle to the tank inlet camlock fitting and pumps the alum solution into the tank.

The second chemical utilized at the WTP is soda ash for pH control. Soda ash is mixed and stored in a 1,200-gallon, open top, welded steel tank with a diameter of 5.6 feet and a height of 6 feet. The tank includes a shaft driven mixer as well as a polycarbonate hinged access lid. WTP staff must prepare the soda ash solution as needed by manually adding 50-pound bags of dry soda ash to the tank. Bags of dry soda ash are delivered to the WTP where staff transfer the bags to a rolling cart which is used to transport them to their

various temporary storage locations within the WTP. When ready to use, the staff haul the bags up a small platform and manually dump them into the soda ash storage tank. Filtered water is then added to the tank in the appropriate volume to create the working solution. This filtered water supply includes a totalizing flow meter used to track the flow. Approximately 16 to 20 bags of soda ash are mixed approximately every 11 to 12 days to create the dosing solution. Soda ash is injected to the filtered water between the filters and the clearwell.

Soda ash solution is delivered from the storage tank to the injection location via a Pulsatron E Series diaphragm metering pump with a listed capacity of 600 gpd and a maximum pressure of 30 psi. The chemical metering pump is located near the top level of the soda ash storage tank in order to reduce potential for crystallization within the check valve and to reduce the risk of siphoning.

Both the soda ash and alum feed pumps are manually calibrated on a daily basis using a graduated cylinder near the injection location. Based on the daily calibration, the dose rate from the pumps is modified and/or the WTP staff performs maintenance on the pumps/piping to address flow issues.

### **Auxiliary Power Systems**

The WTP utilizes a 450-kW diesel-powered auxiliary generator to provide standby power in the event of a loss of power to the WTP. This generator also provides auxiliary power to the Afternoon Beach Sewer Pump Station, which is located approximately 300 feet northwest of the Finished Water Pump Building. The generator, installed in 2014, is located inside the Finished Water Pump Building and diesel fuel is provided to the tank via an above grade diesel storage tank located between the Finished Water Pump Building and the CCB. The generator can provide power for the complete WTP facility and sewer pump station for up to 96 hours.

### **Instrumentation**

The WTP uses various instruments and equipment to monitor and control the overall treatment process. A description of the key components used by the WTP is provided below.

#### Flow Meters

Information on the flow meters utilized at the WTP are summarized in Table 1-5.

**TABLE 1-5**

**Sudden Valley WTP Flow Meter Summary**

<b>Meter Name</b>	<b>Location</b>	<b>Type<sup>(1)</sup></b>	<b>Make/Model</b>
Raw Water	Grade level near WTP entrance	Magnetic, FL	Toshiba LF400
Filter Outlet	Downstream of each filter outlet	Magnetic, FL	Badger Primo
Backwash	Vertical pipe on south wall of WTP	Magnetic, FL	Badger Primo
Division 7 Finished Water	Finished water pump building	Magnetic, FL	Endress & Hauser Promag 500
Division 22 Finished Water	Finished water pump building	Magnetic, FL	Badger Primo Advanced U

(1) FL = flanged connections, MJ = mechanical joint connections, TD = threaded connections.

Turbidimeters

The WTP staff recently replaced all of their existing HACH 1720E inline turbidimeters with new HACH 5300 laser turbidimeters in 2018 and 2019. As required by DOH, turbidity is measured for the raw water, at each filter, and for the combined filter effluent. These data are displayed at the SCADA system and are also tracked and logged for reporting purposes.

Chlorine Analyzers

The WTP staff replaced their previous chlorine analyzers with HACH CL17 analytical equipment in 2018.

Temperature/pH Analyzers

pH and temperature are measured using standard probes procured from HACH. Both raw and finished water pH and temperature are measured via a flow-cell and probe assembly. The equipment is calibrated and maintained on a regular basis.

Streaming Current Monitors

The WTP maintains a streaming current monitor which is designed to assist with determining the coagulant dose prior to flocculation. WTP staff use the streaming current monitor to identify large scale changes in water chemistry that may impact coagulant dose, but they do not use the equipment to optimize their coagulant dose on a daily or weekly basis. The system collects a sample of raw water after coagulant addition and typically, the streaming current monitor is used only to identify an overfeed condition.



Pressure Transducers

The WTP utilizes a Keller Level Rat pressure transducer sensor within the clearwell.

The CCB also utilizes a pressure transducer to measure the water level (depth) within the tank.

Float Switches

The WTP utilizes float switches within the flocculation tank and mercury based level switches within the clearwell and the CCB. These switches provide a high alarm in the event that the water levels in the tanks rise above the high level setpoint. These switches were installed in 1994 with construction of the WTP.

## **CHAPTER 2**

### **WTP CONDITION ASSESSMENT**

#### **INTRODUCTION**

On, February 12, 2020, engineers from Gray & Osborne visited the Sudden Valley WTP to perform a condition assessment of the existing facilities. Russell Porter P.E., Aaron Pease P.E., Myron Basden P.E./S.E., Keith Stewart P.E., and Perry McKay from Gray and Osborne met District WTP operator Kevin Cook and electrician Ken Zangari onsite at the WTP.

Mr. Cook described the treatment equipment and provided operations and technical information on all facets of the treatment plant. After becoming familiar with the WTP facilities, the assessment team split up and performed assessments on all of the facilities with a specific focus on their area of expertise. The following sections include a summary of the issues identified by each discipline at our condition assessment.

#### **TREATMENT/PROCESS CONDITION ASSESSMENT**

The process condition assessment included all of the components and processes used to generate potable water at the WTP including equipment, operations, maintenance, chemicals, and monitoring and controls. Information was collected from on-site observations, discussions with operations staff regarding system performance, and previous experience at the WTP through the completion of other projects. The treatment equipment was described previously, and the assessments below correlate to the areas described in these previous sections.

#### **WTP MAIN BUILDING**

##### **Intake Piping**

- The intake piping is inspected every 5 years and was most recently inspected in 2017 by H<sub>2</sub>O Solutions, LLC. The inspection revealed no significant damage or deterioration of intake structure and piping between the intake and the shoreline. Furthermore, the report had no recommendations for additional modifications.
- Check valves between the shoreline and the WTP have recently been modified/replaced and are in good condition.
- Inspection of the below grade raw water intake piping between the shoreline and the WTP was not included in this assessment; however, WTP staff believe that the piping is in good condition.

- Within the WTP Main Building, raw water piping is coated 10-inch diameter ductile iron materials and overall is in good condition.

While the total installed raw water pump capacity is 2,800 gpm (1,400 gpm per pump), the typical and maximum flow rate through the filters is 700 gpm, and 1,000 gpm, respectively. The fluid velocities within the 10-inch raw water piping at 700 gpm and 1,000 gpm are 2.9 feet per second (fps) and 4.0 fps, respectively. Both of these values are within the recommended velocity range for municipal treatment systems (2 to 8 fps) and, as such, appear to maintain sufficient capacity. To maintain fluid velocities below the recommended maximum value of 8.0 fps, flow through the intake piping should not exceed 1,950 gpm. This value is above the Sudden Valley water right value of 1,526 gpm and as such, it is doubtful that the raw water intake piping would ever need to be upsized to serve the current facility.

### **Raw Water Pumps**

- Both raw water pumps were installed in 1992 and although the pumps are in good condition, function as designed, and the motor for Raw Water Pump 1 was replaced in 2002, the pumps are approaching the end of their useful life.
- The floor in the raw water pump pit does not slope to the sump in all directions and allows for localized ponding and sediment accumulation. The presence of these sediments, especially when wet, creates slippery and dirty conditions within the pit.
- Although a supplementary raw water connection is available at grade level downstream of the existing raw water pumps, the WTP does not possess a suitable auxiliary raw water pump in the event that both raw water pumps are out of service.
- Signage indicating that the raw water pump pit is considered a confined space is not currently provided.

Because of the potential for entrapment and the single ingress/egress ladder, the raw water pump pit should be considered a confined space and confined space entry procedures should be followed whenever entering.

- Lowering piping, fittings, or equipment into the pump pit is difficult due to restricted access in that area. No portable hoist was observed, and access for a mobile hoist is restricted by existing piping and chemical

storage. The lack of a hoist will make lowering heavy piping and fittings into the raw water pit difficult.

### **Raw Water Flow Meter**

- The existing raw water flow meter has a listed range between 100 to 2,000 gpm and has sufficient capacity to operate under the maximum allowable flows through the WTP.
- The raw water flow meter is different from the remaining flow meters utilized in the WTP, which increases the number of spare and replacement parts required for maintenance.
- The meter is old and no longer supported by Toshiba nor is this meter commonly used in the municipal surface water treatment industry.

### **Flocculation**

- The flocculation tank contains piping directly above the tank walls and interior space which will make removal/modifications to this piping and/or the flocculation tank difficult. Corrosion was noted on this piping and its current location may promote corrosion on the upper lip of the flocculation tank wall.

One of these items is a tube-style high level alarm and sensor. This style of equipment is old and prone to sticking.

- Access to the full circumference of the flocculation tank is poor and restricted by the chemical dosing systems, raw water inlet pipe, and overhead water piping and electrical conduit.
- The flocculation tank appears to be undersized for the typical operational flow.

Flocculation basins are typically designed using two criteria: hydraulic retention time and mixing energy. Assuming a sidewater depth of 7.5 feet, the operational volume of the flocculation basin is approximately 8,000 gallons. Given the typical flow through the WTP of 700 gpm, this results in a hydraulic retention time of 11.4 minutes (8,000 gallons/700 gpm), which is significantly lower than the design recommendation of 30 to 45 minutes for baffled channel contact flocculation basins (*Integrated Design and Operation of Water Treatment Facilities, S. Kawamura, 2000*). To achieve the recommended retention time of 30 minutes, flow through the flocculation tank should be reduced to 270 gpm or the flocculation tank volume should be increased to 21,000 gallons.

The mixing energy is calculated using the hydraulic retention time and the headloss through the basin. Assuming a range of headlosses between 0.5 to 2.0 feet, the mixing energy is between 37 - 74 s<sup>-1</sup>, respectively. The recommendation for mixing energy in baffled channel contact flocculation basins is 55 - 10 s<sup>-1</sup> (*Kawamura, 2000*). As such, it appears that the existing flocculation tank at the WTP provides more mixing energy than recommended for ideal flocculation of entrained particles. Providing extra mixing energy will reduce the effectiveness of floc creation prior to filtration.

### **Rapid Rate Media Filters**

- Discussions with the WTP staff suggest that the backwash sequence is successful at cleaning the filters. There is no apparent long-term decrease in filter run times, and the filtration performance appears to be consistent immediately following a backwash. During our site visit, two backwash sequences were observed and our observations agree with WTP's description of the backwash system and its performance.
- Access to the filter discharge piping and fittings is limited and restricted due to the presence and the location of the equalization trough.
- Access to each filter platform is provided by only a single, vertical ladder. This represents a safety risk in the event that the existing ladder becomes obstructed or blocked.
- Media depth, consistency, and particle size breakdown were not investigated during the assessment. Discussions with WTP staff indicate that the filter media performance is good. WTP staff add additional anthracite on an annual basis to bring the total depth of anthracite (top layer) back up to the original design depth (Table 1-3).
- The underdrain system was not accessible during the WTP assessment; however, WTP staff believe that the underdrain system is in good condition.
- Discussions with WTP operations staff indicate that typical filter run times have remained stable for several years.

Backwash flow and volume appears to be within the design range identified in the O&M manual. The backwash cycle appears to sufficiently remove trapped sediments.

Typical mixed media backwash flows are between 10 to 20 gpm/sf (*Integrated Design and Operation of Water Treatment Facilities, S. Kawamura, 2000*). At the WTP, current backwash flow is approximately 1,300 gpm, or 20.6 gpm/sf (1,300 gpm/63 sf), which is at the maximum recommended range noted above.

The backwash water is currently stored in a wastewater holding tank adjacent to the WTP. When the tank is full, the wastewater is pumped to the gravity sewer by up to two submersible pumps and then is conveyed to the City of Bellingham Post Point WWTF for treatment. This process is expensive and cumbersome for the District and their staff. The District has indicated that costs for backwash disposal to the WWTF have increased in recent years and has expressed a desire to modify this system if possible to minimize the volume of water sent to the City's municipal sewer system.

- The maximum allowable filter rate for multi-media direct filtration units is 6.0 gpm/sf. Given the total filter area for all four filters of 252 sf, and a typical flow rate of 700 gpm, the current filtration rate at the WTP is approximately 2.8 gpm/sf, which is below the maximum allowable value. Using the existing filter units, the WTP could filter up to 1,510 gpm – which is very nearly the current Sudden Valley instantaneous water right of 1,526 gpm (Table 1-1) – and still meet the maximum filtration rate requirement.

WTP staff have indicated that they are interested in investigating the possibility of utilizing a mono-media filtration system in an attempt to improve filter run times. This may be feasible; however, it should be noted that the maximum allowable filtration rate (6.0 gpm/sf) would be reduced to 3.0 gpm/sf per Washington Administrative Code (WAC) 246-290-654. Given the current filter surface area, this would reduce the maximum filtration flow through the WTP to 755 gpm, which is above the current typical operational flow, but below the historical maximum operational flow of 1,000 gpm. This reduced flow rate also does not appear to be large enough to meet projected ADD and MDD for the South Shore System as shown in Table 1-2.

### Clearwell

- The clearwell appears to be in good condition, although a thorough investigation was not possible as part of this assessment since the WTP was in operation during the site visit.

- The existing transfer pumps appear to be in good condition. However, the pumps were installed in 1992, are nearly 30 years old, and are approaching the end of their useful life.
- There is staining on the concrete walls within the clearwell. The presence of stains can hide other, more serious defects and detracts from the aesthetic appearance of the clearwell.
- The single access hatch represents a source of contamination to the filtered water. The hatch is adjacent to the path travelled by soda ash chemicals and is a potential source of contamination for spilled liquids.
- The hatch represents a trip hazard for WTP staff and is not highlighted or indicated by high visibility colors.
- The clearwell is considered a confined space; however, no signage or other information noting the access restrictions was noted in the vicinity or on the lid.
- Confined space entry equipment was not noted onsite.

### **Chlorine Disinfectant Injection System**

- The chlorine disinfection system appears to be functioning as desired. Piping, tubing, and equipment appear to be in good condition.
- Gaseous chlorine presents some level of risk to WTP operations staff in the event of a leak, and a significant safety risk in the event of a fire or explosion.

While the existing chlorine gas disinfection facilities likely meet building code requirements in place at the time of their construction, the current chlorine gas storage facilities do not appear to meet current building code requirements.

The 2015 International Building Code defines the Maximum Allowable Quantities of hazardous materials that can be stored or used within a facility without triggering specific design and construction criteria. Gaseous chlorine is considered both an oxidizing gas (a physical hazard) and a toxic gas (a health hazard) and as such, the maximum allowable quantity is 150 pounds as a liquefied gas, or 810 cubic feet at NTP as a gas (both of which correspond to a single 150-pound cylinder). Several exceptions allow this maximum allowable quantity to be increased by 100 percent in buildings equipped with an approved automatic sprinkler system and by an additional 100 percent when approved storage cabinets

are used. Therefore, in a building with a sprinkler system and if all the chlorine gas is stored within approved cabinets, a total of 600 pounds of chlorine gas, or four 150-pound cylinders can be used before triggering a hazardous, H-3 occupancy. A building with an H-3 occupancy is required to have several additional safety and building protection systems including additional planning documents, ventilation system requirements, gas cabinets, smoke detection and alarm systems, emergency power supplies, and emergency alarm systems, among other requirements.

Any significant modifications to the chlorine disinfectant injection system would require that the system be modified to meet current building code requirements for the use and storage of chlorine gas.

Additional code requirements regarding chlorine use and storage are provided in Appendix E.

- Flow directions and labels for chlorine flow meters are not sufficiently labeled which may cause confusion for staff.
- Spare chlorine cylinders are not labeled sufficiently as spares, or as empty/full which may cause confusion for staff and insufficient gas redundancy.
- The coating system in the chlorine room has failed in areas and shows signs of significant fatigue in other areas.
- The spare gaseous chlorine cylinders have only one safety restraint chain near the top of the cylinder. Two chains, one near the top and another near the bottom should be provided for cylinder storage and security.
- Active gaseous chlorine cylinders are secured with a single, loose chain to the scale stanchion, which is bolted to the scale, which in turn is bolted to the floor. This arrangement will not sufficiently secure the active cylinders during a seismic event.

### **Chemical Dosing Systems**

- Material Safety Data Sheets (MSDS) files were not inspected during this assessment. MSDS files were recently updated and are located above the existing laboratory workspace.
- The existing chemical storage facilities for alum and soda ash do not appear to violate the maximum allowable chemical quantities identified by International Building, Fire, or Mechanical Codes.



- The alum storage tank is old, beyond its useful life of 15 to 17 years, and shows signs of degradation.
- Alum is provided by a commercial vendor, and WTP staff have noted that this process is cumbersome and requires two individuals to prevent overflow since there is no direct line of sight between the parking lot and storage tank.
- Alum tank does not contain electronic level sensing equipment which can help staff identify when additional solution is needed.
- Alum dosing is manually calibrated on a daily basis, which is cumbersome and messy for WTP staff. Calibration is performed at the injection location requiring fittings to be loosened and reconnected each time a calibration is performed.
- The WTP maintains sufficient spare pumps/parts for the alum diaphragm metering pump.
- The soda ash storage tank is mislabeled as “Caustic Soda” (Sodium Hydroxide).
- The soda ash storage tank appears to be in good condition and does not show significant signs of coating damage or fatigue.
- The soda ash mixer appears to be in poor condition, is highly corroded, and is likely beyond its useful life.
- Soda ash solution must be prepared manually by WTP staff, and bags of soda ash must be moved at least three times between delivery and mixing. This process is cumbersome and exposes the staff to chemicals and heavy lifting requirements.
- The soda ash tank can only be accessed via a single, small access platform. This platform and its coating system show signs of fatigue. The platform limits access to the soda ash tank and other facilities due to its size and location.
- The location of the soda ash system likely contributes to corrosion and degradation of the electrical equipment within the WTP building.

## **Instrumentation**

- The WTP utilizes several various flow meters for flow measurement. This makes maintaining spare parts more difficult and requires specialized knowledge for each type of meter.
- The WTP does not maintain spare flow meters for each type of unit utilized, which reduces the overall WTP reliability in the event that one of the meters fails.
- The WTP recently upgraded to HACH TC5300 turbidity meters units for measurement of raw, filtered, and finished water turbidity. The staff is pleased with the level of performance and the ease of maintenance associated with this equipment and the equipment is in good condition.
- The WTP recently upgraded to HACH CL17 chlorine analyzers. The staff is pleased with the level of performance and the ease of maintenance associated with this equipment and the equipment is in good condition.
- The WTP utilizes HACH equipment for temperature and pH monitors. The WTP monitors the temperature and pH of raw water, filtered water, and finished water. The staff is pleased with the level of performance and the ease of maintenance associated with this equipment and the equipment is in good condition.
- The WTP maintains streaming current monitoring equipment but does not currently utilize this equipment for coagulant/flocculant optimization. The staff is pleased with the level of performance and the ease of maintenance associated with this equipment and the equipment is in good condition.
- The existing clearwell level switch is out of date and utilizes mercury, which is not suitable for use with potable water.

## **FINISHED WATER PUMP BUILDING**

### **Finished Water Pumping**

- The finished water pumps appear to be in good condition. However, the pumps were installed in 1992, are nearly 30 years old, and are approaching the end of their useful life.
- The District does not currently maintain spare finished water pumps and/or motors, which reduces the overall level of redundancy if one or more of the pumps or motors should fail.

- The WTP cannot run more than two finished water pumps concurrently. Discussions with the WTP staff suggest that this is due to the high in-rush and amperage draw for the finished water pumps.
- The finished water pumps have not been flow tested within the last 10 years to verify their performance.
- Access to all sides of each finished water pump is somewhat restricted by the piping arrangement within the building.
- Pressure gauges have not been tested or certified within the last 5 years, which reduces the confidence in their ability to accurately read the system pressure.

### **CHLORINE CONTACT BASIN**

- A full and complete investigation of the CCB was not conducted as part of this assessment because the WTP was in operation during the site visit.

The tank was most recently inspected by certified divers in 2017 by H<sub>2</sub>O Solutions, LLC. The inspection revealed no significant damage or deterioration for the suction and its components. Furthermore, the report had no recommendations for additional modifications.

- As mentioned previously, the District recently completed a tracer study investigation on its CT system – which included the CCB. The results of this investigation found that the theoretical baffling efficiency (0.7) used to estimate the CT for the system was higher than the empirically determined baffling efficiency of 0.3.

As a result of that study, DOH set the maximum allowable flow through the WTP at 1,000 gpm. Since that directive, WTP staff have reduced the flow through the WTP to 700 gpm and increased the target chlorine residual value to a minimum of 1.0 mg/L. These changes have worked well and help ensure that the WTP provides sufficient disinfection for its treated water; however, this reduced operational flow will inhibit the WTP's ability to meet projected ADD and MDD demands for the South Shore water system

### **STRUCTURAL CONDITION ASSESSMENT**

The structural assessment included the WTP Main Building, the Finished Water Pump Building, items within these two buildings, and the CCB. Information was collected from on-site observations as well as available original drawings for the existing structures. The structural assessment included a review of the condition of structural

members, notes of any items not complying with current building code, preliminary seismic review, and potential structural modifications that may provide benefit for operation of the plant. The building code used for this evaluation is the 2015 International Building Code (IBC). The preliminary seismic evaluation was completed using Tier 1 checklists from ASCE 41 *Seismic Evaluation and Retrofit of Existing Buildings*.

## **WTP MAIN BUILDING**

The WTP Main Building is a one-story building consists of precast concrete tee beams overlain by 4-inch concrete topping slab at the roof. The tee beams are supported at the perimeter of the building by cast-in-place concrete walls. The building is built into a hillside so its walls are partially to fully buried below grade except at the entrance on the north side of the building. The north wall with the entrance is a glass and metal framed “storefront” façade. According to record drawings, the roof structure has 3-ply built up roofing, overlain by 2 inches of sand, overlain by up to 18 inches of soil fill. Below are specific items noted during the assessment.

- In general, the concrete structure is in good condition. No major cracks or spalling were found. In isolated locations, reinforcement on the underside of the precast concrete tee beams is exposed and shows signs of minor corrosion that does not appear to have impacted the strength of the beams.
- According to record drawings, the topping slab over the tee beams is only 2-inches thick at the perimeter. It increases to 4-inches thick at the center of the roof to provide an external slope to promote drainage. The flanges of the tee beams are also relatively thin, tapering down to 1.5-inches thick at the ends of the flange. While the flanges and topping slab could not be directly observed in the field due to the presence of plant matter and soil cover, it appears all components of the structure conform with the record drawings. According to the original record drawings, the roof was designed for 40 pounds per square foot (psf) live load and a maximum soil depth of 18 inches. Based on our investigation of the record drawings, the roof is not expected to be capable of supporting loads from added items such as equipment or tanks without installing structural retrofits.
- Miscellaneous structural steel supports such as pipe, conduit, and equipment supports are corroded. In some cases, the corrosion is severe enough that the strength of the support has been reduced.
- There are several steel tanks inside the building. The steel is coated with paint and in some areas the paint has failed leading to corrosion of the steel. Specifically, corrosion was noted on the flocculation tank, the distribution trough, and Filters 1 and 2. There is also some minor signs of

corrosion on the roof of the clearwell. The corrosion does not appear to be advanced enough to affect the structural integrity of the tanks.

- Various segments of piping and its associated fittings show minor signs of corrosion. This corrosion tends to be located at joints, fasteners, or edges which is typical for piping within a moist environment. The observed level of corrosion does not appear to have affected the integrity of the piping and/or fittings.
- A preliminary Tier 1 seismic evaluation was performed for the building. The Tier 1 evaluation is a checklist that allows quick screening of the building for significant seismic deficiencies. For the purpose of this evaluation, the building is categorized as a Type C2 with concrete shear walls and stiff diaphragm. The checklist did not find any major seismic deficiencies in the building, with only one minor item flagged by the checklist, namely the vertical rebar anchoring connection at the perimeter walls. A copy of the checklist is provided in Appendix C.
- Many of the interior tanks and miscellaneous items supported from the building structure do not appear to have adequate seismic anchorage and/or bracing. These items are at risk of experiencing excessive movement and damage during a design-level earthquake. Interior tanks appear to be unanchored to the floor. Piping connections to the tanks do not appear to have flexible connections, which puts them at risk of damage if tanks move laterally during a design-level earthquake.

## **FINISHED WATER PUMP BUILDING**

This one story building was constructed in 1992 and consists of prefabricated wood trusses at the roof supported by CMU walls at the perimeter of the building. Below are specific items noted during the assessment.

- In general, the prefabricated wood trusses and CMU walls were found to be in good condition. No water damage was found.
- Electrical conduit in the attic had only occasional bracing that did not appear to be adequate for the design-level earthquake. Insufficient bracing increases the risk of electrical failures after a design-level earthquake.
- A preliminary Tier 1 seismic evaluation was performed for this building. For the purpose of this evaluation, the building is categorized as a Type RM1 with reinforced masonry bearing walls and flexible diaphragm. The checklist found two seismic deficiencies of concern. The first deficiency concerns the transfer of horizontal shear forces from the roof diaphragm to the CMU wall at the south side of the building. The cantilevered roof over

the exterior porch on the south side of the building does not appear to have a load path to transfer forces from the roof diaphragm to the CMU wall. There is a risk of damage or partial roof collapse in the design-level earthquake. The second deficiency is insufficient out-of-plane anchorage of the top of CMU walls to the roof diaphragm which results in some risk of damage to the wall and roof if the top of the wall moves away from the intended bearing point of the roof trusses during a design-level earthquake.

## **CHLORINE CONTACT BASIN**

The CCB was described previously, but is a welded, coated, steel tank located just south of the Finished Water Pump Building that provides contact time for chlorinated filtered water from the clearwell.

- The exterior coating system on the CCB shows many localized areas of damage and/or failure. Corrosion of the steel wall is evident at these locations. Previous areas of corrosion have been addressed by WTP staff through surface preparation and spot coating repair.
- The interior coating system of the CCB appears to be in fair condition and shows only minor signs of corrosion at select areas (edges) within the tank.
- A seismic vulnerability assessment was completed in 2016 and had two significant recommendations for the CCB. First, the report stated that the concrete ringwall foundation should be retrofitted to increase uplift resistance during the design-level earthquake. Secondly, flexible piping connections were recommended to reduce the risk of damage that would result in emptying of the reservoir. Otherwise the report did not find deficiencies regarding the steel shell or anchorages to the foundation.

## **ARCHITECTURAL CONDITION ASSESSMENT**

The architectural assessment included the WTP Main Building and the Finished Water Pump Building. Information was collected from on-site observations as well as original drawings for the existing structures. The assessment included a review of the condition of non-mechanical building systems and workspaces and compliance with current codes. The code used for this evaluation is the 2015 International Building Code (IMC).

### **GENERAL ARCHITECTURAL**

The WTP has sufficient building access restrictions, but the property has minimal site security measures. Both the WTP Building and Finished Water Pump Building are secured with door locks. The CCB is secured with a padlocked ladder guard to prevent

access to the tank. The generator fuel tank is secured behind a wood slat fence and gate secured with a padlock. The WTP does not contain any site fencing.

Camera surveillance is provided at the WTP Building and the CCB; however, this system is not used for alarming due to the high volume of nuisance alarms caused by wildlife and visitors to the adjacent Afternoon Beach Park.

## **WTP MAIN BUILDING**

- This building includes a small water quality lab area that is comprised of approximately 10 linear feet of base cabinets and countertop. Within the countertop is a 24-inch sample sink that receives flow streams of filtered water and finished water for water quality sampling and analysis. The remainder of the available countertop area is utilized for water quality analysis instruments and as the plant operator's work station for computer access and required monthly reporting. The WTP's Human Machine Interface (HMI) computer is located here and is housed within one of the base cabinets with a shelf above the countertop holding two monitors.

The location of this work station near the sink and lab area places the computer equipment and necessary paperwork/files at greater risk for damage.

- This building includes a small bathroom along the west wall. The bathroom includes a toilet and a utility sink along with some open wall shelving for storage of janitorial supplies. Hot water is supplied to the utility sink via a mini-tank style Bosch water heater located within the closet adjacent to the bathroom. The water heater appears to be less than 5 years old.

The bathroom is functional but shows typical signs of deterioration associated with use and age including some light moisture damage, paint deterioration, staining, and poor lighting.

- Additional filter media is currently stored south of Filters 3 and 4 between the filter tank and the building wall. While neat and organized, this location significantly restricts access to all sides of the filters for inspection and/or maintenance. This location also makes access to the filter media bags cumbersome for WTP staff.
- The facility includes an emergency eye and face wash station located on a wall adjacent to the lab area and an emergency drench shower located on the northeast corner of the Filter 3 and 4 vessel. Emergency eyewash and shower equipment is now regulated through the plumbing code by ANSI/ISEA Z358.1 - American National Standard for Emergency

Eyewash and Shower Equipment. This standard not only includes requirements for the fixtures, but also water supply to the fixtures and access to the fixtures within a facility. Eye and face wash stations should be located to be accessed in no more than 10 seconds by a user and should provide uninterrupted flow of 3.0 gpm for 15 minutes. Drench showers should also be located to be reached within 10 seconds and should provide uninterrupted flow of 20 gpm for 15 minutes. The access pathways to both types of emergency fixtures should be free and clear of obstructions and the water supply should be tempered to a temperature between 60 degrees F and 100 degrees F. In addition, emergency fixtures should also be activated weekly to ensure flow and should be tested and certified annually.

Given the location of the existing equipment within the Main Building, neither the eyewash or drench shower is in compliance with the access requirements of ANSI Z358.1. Flow and temperature for these units were not tested during the site visit, but given the date of their installation, they may not meet current flow or temperature requirements. In addition, the supply to both of these fixtures is not tempered and therefore does not meet the temperature requirements.

- There is evidence of moisture weeping through the east wall directly above the electrical gear for the raw water pumps as indicated by some rust staining down the wall at the beam-to-wall interface. It does not appear this location has leaked in the recent past and there was no apparent direct water damage to the electrical gear.
- There is evidence of moisture weeping through the east wall near the second beam to the south of the raw water pump electrical gear (MCC 3). This location had some shiny or reflective spots, indicative of a wet surface during this assessment.
- There is evidence of moisture weeping through the aluminum storefront entrance area predominantly at the easterly interface where the aluminum framing meets the concrete wall. There is staining down this wall, down the vertical framing along the wall, at the floor, and on the adjacent wall around the corner to the east. This moisture appears to be coming from outside within the entrance alcove.
- The existing aluminum storefront window entrance alcove restricts the ability to move supplies and equipment in and out. The existing aluminum-framed, glass door is 42-inches wide; however, for deliveries of chemicals on pallets and other supplies for the WTP, a double door or an overhead coiling door would be preferred.



In addition, any major work to the facility to replace or repair equipment, tanks, etc. would require that the storefront system be disassembled.

- At the concrete slab roof overhang above the alcove there was moisture staining coming in from the leading edge as well as at several locations along the joint between the concrete walls and slab extending above. In addition, it appears an attempt to seal some of these joints may have been done in the past as evidenced by some seams of white caulk.
- Some of portions of the facility's floors appear to be continually wet, particularly between the tanks and filters. The concrete floor is painted and is in good condition; however, the standing water on portions of this makes the flooring slippery and represents a potential safety hazard.
- The front and side exterior faces of the structure are covered with significant growth. This growth appears to be English Ivy and overhangs the building roof on three sides. While it is apparent this growth allows for significant camouflaging of the structure from the roadway, it does impede inspections of the structure, waterproofing systems, and roof drainage. In addition, roots from organic growth can be tenacious, can deteriorate waterproofing systems, and can work their way into structural joints potentially causing damage.
- Similar to the exterior wall faces, the roof is overgrown with plant life and also includes some large woody debris that has blown and/or fallen down on to the roof from the adjacent woods.
- Chlorine room access door and frame show signs of corrosion and the coating system is showing signs of fatigue.
- The building does not currently utilize an effective smoke or fire alarm system.

## **FINISHED WATER PUMP BUILDING**

- The downspout on the northeast corner of the building has a leak in a joint near the soffit causing enough of a splash at grade that the cedar siding appeared to be constantly wet. The continuous presence of moisture will deteriorate the siding in this area.
- The roof and siding appear to be in good condition.
- Each end of this building includes a light well (skylight) framed through the attic with domed skylights. These areas are subject to water damage if not maintained, cleaned, and inspected on a regular basis.

- The building does not currently utilize an effective smoke or fire alarm system.

## **MECHANICAL CONDITION ASSESSMENT**

The mechanical/HVAC assessment included the WTP Main Building and the Finished Water Pump Building. Information was collected from on-site observations as well as original drawings for the existing structures. The assessment included review of the condition of mechanical heating/cooling equipment, dehumidifiers, ventilation equipment, and compliance with current mechanical codes, namely, the 2015 International Mechanical Code (IMC).

### **WTP MAIN BUILDING**

- This building includes a single, ceiling-hung, electric air handling unit that supplies the space with ventilation and heating and is controlled by a programmable Honeywell thermostat located within a ventilated lockbox. The internal fan has a capacity of up to 1,900 cubic feet per minute (cfm) at approximately 0.3 inches of water column (in-WC) and the heating coil has a capacity of 16 kW. This unit has a mixing box with a fixed bypass damper that allows control of the amount of outside air that is brought in and the amount of inside air that is recirculated. This unit is over 10 years old and was rebuilt in 2018 due to corrosion of the electric heating coils. In its current conditions, this unit appears to have many years of service life remaining. The unit includes a filter box with 2-inch pleated filters; however, the filters were not accessible at the time of the assessment.

When outside air ventilation is being provided, a discharge relief louver ducted through the Chlorine Gas Room allows exhaust air to leave the space. Plant operators indicate that there are no issues or concerns with heat capacity or ventilation; however, it was noted the electric heat is expensive to operate during winter months.

Heating and ventilating equipment is in good condition with years of service life remaining.

- This building also includes two, stand-alone industrial dehumidifiers. Each has a rated capacity of 195 pints of water removal per day at 80 degrees F and 60-percent humidity. These units include 2-inch MERV 8 pleated filters. Plant operators note that since the installation of these dehumidifiers, interior moisture control has significantly improved and has not posed an issue in recent years.

The dehumidifiers are in good condition with years of service life remaining.

- Air flow through the Chlorine Gas Room is provided via an intake louver installed within the door and an exhaust fan with a 12" x 12" louvered gravity backdraft damper. The operable louvers of the gravity backdraft damper are partially restricted by plant growth on the building exterior.

## **FINISHED WATER PUMP BUILDING**

- This facility includes a 40,000 btu/hr, natural gas unit heater in the southeast corner, and generator louvers which remain closed unless the generator is in operation. These components are in excellent condition with years of service life remaining.
- There appears to be a small exhaust leak in a pipe joint where the generator exhaust connects into the underside of the silencer. A portion of the insulation blanketing was stained with black soot.

## **ELECTRICAL CONDITION ASSESSMENT**

The electrical assessment included the WTP Main Building and Finished Water Pump Building. Information was collected from on-site observations, discussions with WTP treatment staff, as well as original drawings for the existing structures. The electrical assessment included a review of the condition of existing equipment, use of the existing equipment, compliance with current electrical codes (NEC 2020), and potential modifications that may benefit the operation of the plant.

The existing utility service includes a pad mounted 300 kVA, 480/277 VAC (360 full load amps) three phase electrical transformer. This transformer is owned and managed by Puget Sound Energy and has PSE identification number 462999-164283. This service feeds a 480 VAC motor control center (MCC 1) located in the Finished Water Pump Building through a 600-amp main circuit breaker, also located in the Finished Water Pump Building. MCC 1 is generator-backed by a 600-amp rated automatic transfer switch and 450kW (~680 amp) generator. MCC 1 also provides a 150-amp 480/277 VAC feed to the treatment building, which distributes power from its own MCCs (MCC 2 and MCC 3). The generator in the Finished Water Pump Building also serves the nearby Afternoon Beach Sewer Pump Station which has its own utility feed.

## **GENERAL ELECTRICAL**

- An overarching concern is the size of the utility transformer and its ability to provide power to the WTP. As stated above the transformer has the capacity to provide 360 amps but the facility is designed to distribute 600 amps. The load study from the 1992 WTP Upgrade Improvements Project indicates a peak requirement of 449 amps, suggesting that the

existing transformer is not sized to fully power the complete operation of the WTP for an extended period of time.

- Occupational Health and Safety Association (OSHA) mandates that electrical distribution equipment, that is likely to require service while energized, be labeled with arc flash protection labels indicating the safe working distances and the correct personal protective equipment (PPE) required. The existing electrical distribution equipment in both the WTP Main Building and Finished Water Pump Building does not currently have these labels.
- The auxiliary power generation system is new and is in excellent condition. The system is tested for approximately 30 minutes each week in accordance with the manufacturer's recommendations.
- Based on previous observations by District staff, buried conduits and/or conductors show signs of corrosion and are likely in fair/poor condition.

## **WTP MAIN BUILDING**

At the WTP Main Building, the power enters MCC 2 which is located on the west wall and contains the clearwell transfer pumps, a panelboard, and HVAC power. MCC 2 feeds MCC 3, which is located on the east side of the WTP Main Building and contains the motor starters for the raw water pumps.

- MCC 2 is in fair/poor condition and is a GE 8000 series product which is no longer manufactured or supported with spare components.
- The original circuit breakers in MCC 2 are approaching the end of their recommended service life.
- There is a concrete pad for a previously utilized transmission pump in front of MCC 2, which violates the NEC clear space requirement for this MCC. According to the NEC, at least 42 inches of clear space are required.
- MCC 3 is a Square D Series 6 MCC which is a currently supported product line. The unit is in fair/poor condition, most likely due to its proximity to bags of soda ash. This close proximity to chemicals and water metering equipment makes the equipment more susceptible to corrosion, degradation, and places the equipment at a greater risk for failure. The panel cover shows signs of corrosion. Although the MCC interior was not inspected as part of this assessment because the WTP was in operation, WTP staff have noted that the interior components of MCC 3 exhibit signs of corrosion.

- The electrical equipment in the chlorine room includes outlets and conduit and is in excellent condition primarily due to the use of PVC-RGS conduit within the space. Several existing conduits in this room are uncapped, allowing chlorine gas fumes to enter the associated panelboard, and subsequently, the WTP Main Building.
- In several locations, electrical conduit is mounted to the floor of the building. This installation location creates a tripping hazard and makes transportation of heavy items using wheeled carts or hand trucks more difficult.
- On the wall immediately south of MCC 2 there are two panels leftover from the control panel improvements project. These panels are not labeled but are a blue panel manufactured by S&B with several unused level displays, and a grey panel manufactured by QCC immediately to its right. These two panels contain field wiring that run to the main control panel for the WTP, which is designated as MCP 1. Using a control panel as a pulling point and/or junction box is not allowed by the NEC.
- There are several additional panelboards and control panels not currently used for their original design function. These panels take up valuable wall space, create confusion and difficulty in tracing wires and cables, and provide the opportunity for additional violations of current and future electrical code requirements.
- MCC 2 and the panelboards immediately following the existing 208/240V transformer do not utilize surge protection devices (SPD). SPD's help protect the electrical equipment from damage due to in-rush currents and inconsistencies in the electrical service during both normal operation and when starting up after a loss of power.

## **FINISHED WATER PUMP BUILDING**

- MCC 1 is old and has reached the end of its recommended service life. The motor control center's product line (GE 8000 series) is no longer manufactured and in 2017 GE sold this portion of its business to Allen Bradley (ABB). ABB does offer support but the availability of new components is questionable and will continue to become more difficult with each passing year.
- The existing motor starters for the finished water pumps are auto-transformers which is an outdated technology.

- The original circuit breakers are near the end of their recommended service life.
- The generator is approximately 6 years old; however, the adjacent washing machine infringes upon the minimum required clear space around the generator. Per the NEC Article 110, a minimum of 42 inches is required in front of equipment operating at 600 V or less which is likely to require examination, adjustment, servicing, or maintenance while energized.
- The external fuel tank is less than 5 horizontal feet from the eave of the building. The 2015 International Fire Code (IFC) #5704 stipulates that diesel fuel tanks of that size must be at least 5 feet from building eaves.
- This building utilizes fluorescent light fixtures, which are outdated and inefficient.
- MCC 1 and the panelboards immediately following the existing 208/240V transformer do not utilize surge protection devices (SPD). SPD's help protect the electrical equipment from damage due to inrush currents and inconsistencies in the electrical service during both normal operation and when starting up after a loss of power.
- All of the conduits between the Main Building and the Finished Water Pump Building are routed through a common 3-foot hand hole. This hand hole contains low voltage conductors, high voltage conductors, 24VDC signal cables, and ethernet cables. Current NEC does not permit both low and high voltage cables to occupy the same space.

## **TELEMETRY/SCADA**

The existing supervisory control and data accusation (SCADA) system consists of a computer-based HMI that communicates with a programmable logic controller (PLC) in the WTP. HMI software is the iFIX platform. In addition to monitoring and controlling activities at the WTP, the PLC also communicates with, and monitors the Division 7 and Division 22 Reservoirs directly via leased phone lines. Discussions with operations staff indicate that the Comcast broadband connection from the WTP to the internet for remote monitoring is generally reliable; however, there is already work in progress to add a local copy of the alarming software (WIN 911) across the water system in case of the loss of communication at the site. The existing SCADA system allows the operations staff to operate the WTP automatically based on the real time water system demand.

- In general, the District is pleased with both the reliability and performance of the SCADA system. Typically, WTP staff have a monthly call with their integrator (QCC Inc.) to discuss any issues and possible

improvements. This proactive approach helps to ensure that the system is maintained in good working order.

- The process control panels in the water treatment building were updated in 2012 to an Allen Bradley CompactLogix PLC based system and have had very few modifications since that time. MCP-1 (located on the west wall of the WTP Main Building) acts as the master while MCP-2 (east wall of the WTP Main Building) acts as a remote I/O base. Both these panels are in good condition. MCP-2 does not appear to have suffered from the corrosive environment despite being adjacent to the MCC 3.

## **CHAPTER 3**

### **TREATMENT IMPROVEMENTS**

#### **INTRODUCTION**

This chapter presents recommendations for modifications or actions based on the assessment observations noted in Chapter 2 for each discipline. The recommendations are divided into high-priority and recommended improvements. For each discipline as well as each building at the WTP, high-priority improvements are listed first, followed by recommended improvements.

In addition to the improvements recommended as a result of our assessment, the lists of recommendations below also include items noted during preparation of the most recent Water System Plan completed by Wilson Engineering in 2018 as well as the WTP Sanitary Survey completed by DOH in March 2020.

High priority improvements should be addressed within 5 years in order to help ensure the integrity of the existing facilities as well as WTP operations. Recommended improvements should be addressed within 5 to 15 years and would provide additional convenience and efficiency to the WTP operations staff and would help ensure the long-term longevity of the WTP structure and components.

#### **TREATMENT/PROCESS RECOMMENDATIONS**

##### **HIGH PRIORITY IMPROVEMENTS**

###### **WTP Main Building**

- Replace the existing clearwell level alarm switch to one that does not utilize mercury.
- Replace the existing CCB level alarm switch to one that does not utilize mercury.
- Address issues with existing chlorine disinfection system.
  - In addition to the condition assessment provided as part of this project, perform an alternatives analysis to determine whether disinfection with chlorine gas continues to be the best alternative for use at the WTP. While gaseous chlorine is a viable method for disinfection of potable water – especially for small-scale water treatment facilities – many municipalities choose to disinfect using liquid sodium hypochlorite or other liquid based chemicals due to



the inherent safety risks of chlorine gas. The alternatives analysis should investigate options such as continuing gas chlorination, disinfection with bulk sodium hypochlorite, and disinfection through onsite hypochlorite generation, and should evaluate these alternatives in the context of other process improvements that may be desired.

- If an alternative technology is desired, then proceed with the design and implementation of the desired technology.
- If continued use of gas chlorination is desired, then complete the following modifications and any recommendations provided in the alternatives analysis:
  1. Assess ventilation system and air exchange.
  2. Revise labels for chlorine solution tubing.
  3. Remove existing coatings, prepare surfaces, and provide new coating system for interior walls.
  4. Add additional chain restraint system for spare cylinders approximately 18-inches from the floor.
  5. Revise scale orientation to allow for an additional chain restraint to active cylinders approximately 18 inches from the floor.
  6. Remove existing coatings, prepare surfaces, and provide new coating system for existing door (interior and exterior sides).
  7. Address existing chlorination system issues such as safety systems (fire, sprinkler, alarming, etc.), maximum storage allowances through the installation of Chlortainers and removal of spare cylinders, indicators and alarms, and storage containers in accordance with the codes listed in Appendix E.
- Address shortcomings with the existing alum system.
  - If modifications to other systems at the WTP will allow for relocation of the alum tank, we recommend that the following modifications be completed at the final tank location. Otherwise,

the following recommendations could be completed for the existing alum tank location.

1. Replace existing alum storage tank with new HDPE full draining tank. New tank should be double containment style for safety against leaks/spills.
  2. Provide relocated alum fill connection to allow for easier delivery of chemical and easier observation of tank level during filling.
  3. Provide level sensing equipment and/or external sight gauge for alum tank.
  4. Install alum duplex chemical metering pump skid.
  5. Compile and update MSDS files for all chemicals used at the WTP and store this information at the existing laboratory workspace.
  6. As recommended by the DOH Sanitary Survey (Appendix D), prepare and file standard alum chemical quality specifications and standard delivery procedures for review prior to/during chemical delivery.
- Address shortcomings with the existing soda ash system.
    - For continued use of the existing soda ash mixing/storage tank, we recommend that the following modifications be completed at the final tank location.
      1. Drain, clean, remove the existing coating, prepare and recoat the existing alum tank.
      2. Install level markings on the interior of the tank to facilitate easier chemical addition and filling.
      3. Revise tank and platform orientation to provide for easier access by staff with chemicals.
      4. Replace existing soda ash mixer.
      5. Provide common soda ash duplex chemical metering pump skid.

- If modifications to the other chemical systems, equipment, or layout of the WTP Main Building will allow for relocation of the soda ash tank, we recommend that a new, similarly sized, HDPE soda ash tank be provided in the desired location.
- Address shortcomings with existing backwash system.
  - In addition to the condition assessment provided as part of this project, perform an alternatives analysis for the existing backwash storage and pumping system. While the current backwash method and settling tank is sufficient for WTP operation, the process is expensive due to costs associated with pumping large volumes of water to the City of Bellingham municipal sewer system. The alternatives analysis should investigate methods to optimize the backwash process and reduce operating costs such as discharging backwash supernatant back to Lake Whatcom, installing a larger settling tank, or utilizing backwash recycle storage and pumping equipment. These alternatives should be evaluated in the context of other process improvements that may be desired.

## RECOMMENDED IMPROVEMENTS

### WTP Main Building

- Address shortcomings with raw water pumping area and equipment.
  - Complete raw water pump performance testing.

Depending on the results of this performance test, repair, rehabilitate, replace, or procure spare equipment for each pump and/or pump motor as required.
  - Purchase/procure an auxiliary/portable raw water pump for connection to the auxiliary WTP inlet. Alternatively, a spare raw water pump may be purchased to replace one of the existing raw water pumps in the event that it fails.
- Procure a spare backwash flow meter.
  - In conjunction with this recommendation, it may be useful to centralize the flow meters using a common manufacturer or model number. This will provide commonality of operation and will allow a common supply of spare parts to be used for all of the meters.

- Address shortcomings with the existing flocculation tank.
  - For continued use of the existing flocculation tank, the existing coating system should be addressed as described in the structural recommendations section.
  - If a larger tank that will provide the minimum recommended residence time of 30 minutes is desired, the above modifications can be omitted and the tank can be replaced with a new, 21,000-gallon tank.

A tank with the same footprint as the existing tank would need to be approximately 21 feet tall (including 1-foot of freeboard), which is taller than the existing 13-foot ceiling in the WTP Main Building. Given the maximum tank height of 10.5 feet (to allow for access) including 1-foot of freeboard, a 21,000-gallon tank would have a diameter of approximately 19.5 feet. This size tank will not fit within the existing WTP Main Building footprint without significant other modifications. As such, it is anticipated that modifications to the flocculation tank will be done in conjunction with a larger WTP modifications project and/or remodel effort.

It should be noted that although a new, larger tank would bring the residence time and mixing energy values closer to theoretical design values, the current flocculation tank does not inhibit the WTP from meeting the current performance requirements.

- Regrade and resurface the raw water pump pit floor to promote good drainage to the sump area and prevent the accumulation of sediments.
- Procure confined space access equipment dedicated to the WTP.
- Relocate existing small diameter piping at the flocculation tank so that piping and conduit located within the tank footprint is minimized.
- Furnish and install additional ladder access to the east side of Filter 1 and 2 and to the west side of Filter 3 and 4.
- Revise CT calculations to include the clearwell volume and an assumed baffling efficiency of 0.1.
- Provide high visibility painting or indicators for the clearwell access hatch.

- Complete transfer pump performance testing.  
  
Depending on the results of this performance test, repair, rehabilitate, replace, or procure spare equipment for each pump and/or pump motor as required.
- Drain and clean the clearwell.
- Provide additional "Operator in Trouble" motion sensors and alarm systems.
- Replace existing tube-style high level alarm in the flocculation tank.

### **Finished Water Pump Building**

- Replace/test existing finished water pressure gauges.
- Complete finished water pump performance testing.  
  
Depending on the results of this performance test, repair, rehabilitate, replace, or procure spare equipment for each pump and/or pump motor as required.
- Procure spare finished water pump motor.
- Provide additional "Operator in Trouble" motion sensors and alarm systems.

## **STRUCTURAL RECOMMENDATIONS**

### **HIGH PRIORITY IMPROVEMENTS**

#### **WTP Main Building**

- Replace corroded steel supports for miscellaneous items such as conduit, piping, and equipment.
- If the existing floc tank is to be reused, prepare and coat both the interior and exterior of these tanks to prevent additional loss of metal. Preparation should be a minimum of SSPC-SP10 and coatings should be NSF61 approved for use with potable water. Fill the existing void space below the tank with high-strength grout.

- If the existing Filter 1 and 2 is to be reused, prepare and coat the lower 2 feet of the vessel to prevent additional loss of metal. Preparation should be a minimum of SSPC-SP3 or SSPC-SP11 and coatings should be NSF61 approved for use with potable water.
- Perform a detailed structural evaluation of seismic anchorage and bracing of interior components including, but not limited to, anchorage of interior tanks, flexible connections of piping, bracing of piping and conduit, wall-mounted electrical transformers, anchorage and bracing of miscellaneous equipment. A detailed structural evaluation was completed for the District's reservoirs in 2016, but was not completed for the WTP Main Building or Finished Water Pump Building.
- Furnish and install seismic bracing and flexible connections for tanks and other key equipment as identified by the seismic evaluation.

### **Finished Water Pump Building**

- Add additional seismic bracing to electrical conduit in the attic to meet the demands of the design-level earthquake.
- Perform a detailed structural analysis and develop seismic retrofit design to address the deficiencies identified by the Tier 1 evaluation regarding the connection between the roof diaphragm and top of CMU wall. Implement the modifications to the Finished Water Pump Building structure as recommended from the detailed structural seismic evaluation.

## **RECOMMENDED IMPROVEMENTS**

### **WTP Main Building**

- Prepare existing exposed rebar on concrete ceiling to SSPC-11 Standards and coat the exposed metal with appropriate, high quality commercial primer/paint system.

### **Chlorine Contact Basin**

- Perform a formal coating inspection on the interior and exterior of the CCB.

This inspection should be conducted by a consultant specializing in the testing and inspection of potable water storage facility coating systems. The inspector should be NACE Certified and the coating assessment should include pull tests, metal thickness inspection, a formal visual assessment of the coating system, and any other recommended testing that

will assess the viability of the coating system and/or integrity of the steel tank.

- Develop a plan for treatment and disinfection operations during the time period that the CCB is offline for maintenance.

Pending the results of the coating inspection recommended above, the CCB will require both interior and exterior coating system improvements. During this time period, which can last up to 3 months, the CCB will be unavailable for use and a system should be devised for how disinfection of filtered water will be provided.

## **ARCHITECTURAL RECOMMENDATIONS**

### **HIGH PRIORITY IMPROVEMENTS**

#### **WTP Main Building**

- Address the risk for corruption of the electronic equipment at the existing work counter by relocating the electrical equipment to another area of the WTP.

One alternative to complete this recommendation is to convert the totality of the existing counter space to laboratory and wet-work (sampling, analysis, etc.) and relocate the computer work station. It is anticipated this will be done in conjunction with a larger WTP modifications project and/or remodel effort.

- Remove the soil cover and associated plant growth down to the cast concrete curb that is likely at the base of the existing chain link fence. In addition, heavy, woody debris should be removed from the roof on an annual basis.
- Remove ivy and other plant vegetative growth from building exterior.
- Replace and/or revise the existing safety shower and eyewash systems to be in compliance with ANSI Z358.1.
- Add an effective smoke and fire alarm system. The system should be in accordance with IFC requirements and should include heat/rise and smoke detection systems, and egress pull stations should be linked to the existing SCADA system to notify District staff that an alarm has been activated.

### **Finished Water Pump Building**

- Remove any debris and clean existing roof on an annual basis.
- Add an effective smoke and fire alarm system. The system should be in accordance with IFC requirements and should include heat/rise and smoke detection systems, and egress pull stations should be linked to the existing SCADA system to notify District staff that an alarm has been activated.

## **RECOMMENDED IMPROVEMENTS**

### **General Architecture**

- Investigate alternatives to provide additional site security measures such as fencing, restricted access gates, and cameras. The investigation should address the District's tolerance for risk, public safety, park access, and desired level of security, all in conjunction with other measures and large-scale modifications proposed for the WTP.

### **WTP Main Building**

- Address deteriorating conditions in the restroom. Modifications should include replacement of damaged drywall, new paint, and new fixtures.
- Remove heavy, woody debris from the roof on an annual basis.
- Address wall weeping on the east wall above MCC 3.
- Address leakage at existing storefront windows and above the windows on concrete alcove. This may be addressed by removing damaged or deficient seals and replacing with new materials.
- Address pooling of water on WTP floor to avoid potential hazards. This may be addressed by grinding or grooving the floor to promote drainage to the existing trench, and then recoating the modifications.
- Revise the existing storefront window arrangement to allow for a new, wider door that will facilitate easier delivery of pallets or other large items. It is anticipated this is done in conjunction with a larger plant modifications project and/or remodel effort.
- Relocate stored filter media to another area of the facility, or a new facility in order to provide unhindered access to all sides of Filters 3 and 4. It is anticipated this is done in conjunction with a larger plant modifications project and/or remodel effort.



- Relocate stored/extra/damaged materials in the SE corner of the building to another area of the facility, or to a new facility in order to provide unhindered access to all sides of Filters 1 and 2. It is anticipated this is done in conjunction with a larger plant modifications project and/or remodel effort.

## **MECHANICAL RECOMMENDATIONS**

### **HIGH PRIORITY IMPROVEMENTS**

#### **WTP Main Building**

- Investigate current heating schedule and equipment to optimize it for plant operation, staff comfort, protection of equipment, energy efficiency, and cost.

### **RECOMMENDED IMPROVEMENTS**

#### **General Mechanical**

- Perform an energy audit to identify the primary source of energy consumption and heat loss.

This audit should be conducted by Puget Sound Energy or another subconsultant familiar with the function and use of a treatment facility and experienced in providing comprehensive energy audit assessments. The audit should include all components of both the WTP Main Building and Finished Water Pump Building and should identify ways the WTP can reduce its energy footprint and operational costs.

#### **Finished Water Pump Building**

- Complete repairs to leak in the generator exhaust piping.

## **ELECTRICAL RECOMMENDATIONS**

### **HIGH PRIORITY IMPROVEMENTS**

#### **General Electrical**

- Combine all plant records into a new and complete electrical record set that incorporates all the changes made into a single current as-built for power distribution and controls.

- Perform a complete audit of the electrical system to focus on the electrical reliability of the circuit breakers and fuses in the MCCs as well as safety and code compliance.

This work is typically completed by a consultant specializing in electrical analysis and various companies perform this work including Vertiv, Eaton's electrical engineering services group, and Siemen's electrical services group.

This audit should accomplish the following tasks:

- Identify any deficiencies with the physical condition or operation of electrical distribution equipment that could not be investigated as part of this assessment. This would include buried conduits and/or conductors. Coordinated outages to portions of the WTP facility will be required.
  - Coordinate the circuit breakers and/or list the modifications required to selectively coordinate the system,
  - Provide OSHA compliant labeling for arc and shock hazards, and
  - Identify available fault current at key points in the system and identify which devices to not have sufficient withstand ratings,
  - Recommend a schedule for the replacement of the original circuit breakers.
- Perform an electrical analysis to review the peak demand usage from historical utility bills to evaluate how well the PSE installed transformer is able to meet the facility's needs.

### **WTP Main Building**

- Remove all chemical storage and metering pump equipment from the vicinity of MCC 2 and MCC 3. While the NEC requires at least 42-inches of clear space, 8 to 10 feet is often provided as "good practice" to help protect electrical equipment.
- Install surge protection devices (SPDs) at the first panelboards after the transformer.
- Replace MCC 2 with new equipment including motor starters, circuit breakers, surge protection devices, and VFD load filters.

- Replace MCC 3 with new equipment to address existing component corrosion.

### **Finished Water Pump Building**

- Replace MCC 1 with new equipment including motor starters, circuit breakers, surge protection devices, and VFD load filters.
- Install surge protection devices (SPDs) at the first panelboard downstream of the wall mounted transformer.

## **RECOMMENDED IMPROVEMENTS**

### **WTP Main Building**

- Replace florescent lighting with LED lighting. This replacement should provide a small reduction in energy consumption but will require significantly less maintenance than current light fixtures.
- Replace AC UPS backed systems with DC UPS backed systems for increased reliability.
- Consolidate small panelboards and/or panelboards that are not currently used for their original design intent into fewer panels to provide a simpler, more streamlined distribution system. Address any open conduits to these panels through removal of capping.
- Reroute floor mounted electrical conduits to the walls and/or ceiling in order to eliminate tripping hazard.
- Reroute field wiring within the blue / grey panels manufactured by S&B and QCC through a different pathway, then remove the panel(s) if possible. Alternatively, the panels could be made into junction boxes by removing any remaining control apparatus as well as any connections associated with door mounted devices.
- Assess the likelihood of installing a third transfer pump at the WTP. If a third pump is not likely, remove the existing transfer pump pad and anchors to provide code-compliant clear space in front of MCC 2.

### **Finished Water Pump Building**

- Replace florescent lighting with LED lighting. This replacement should provide a small reduction in energy consumption but will require significantly less maintenance than current light fixtures.

- Continue to test the auxiliary generator under load on a regular basis to ensure that it will successfully provide the necessary power to operate the entire facility. On an annual basis provide a full loading test on the generator using a load bank.
- Investigate options for relocation of existing generator fuel tank.

## **SUMMARY**

Table 3-1 below provides a modification summary, discipline, and location for the High Priority Improvements. Table 3-2 provides this information for the Recommended Improvements. It is important to note that while the recommended improvements are not explicitly and immediately required, they are recommended in order to ensure the longevity of the existing facilities and their ability to provide the desired level of filtration and output.

**TABLE 3-1**

**Sudden Valley WTP High Priority Modifications Summary**

<b>Modification</b>	<b>Location<sup>(1)</sup></b>	<b>Discipline<sup>(2)</sup></b>
Conduct chlorine disinfection system alternatives analysis	MB	P
Chlorine gas system modifications	MB	P
Alum storage and metering pump system modifications	MB	P
Soda Ash storage and metering pump system modifications	MB	P
Conduct backwash system alternatives analysis	MB	P
Replace existing clearwell and CCB level switches	MB	P
Replace corroded steel supports	MB	S
Prepare and coat steel tanks (Floc, Soda Ash, and Filters 1/2)	MB	S
Install seismic bracing for electrical conduit, electrical equipment, and treatment equipment	MB/FPB	S
Complete detailed structural evaluation	MB/FPB	S
Relocate existing laboratory electrical equipment	MB	A
Remove soil cover, vegetation growth, and organic debris from building exterior and roof	MB	A
Provide water upgrades to safety shower and eyewash	MB	A
Add fire and smoke alarm system	MB/FPB	A
Investigate current heating schedule	MB/FPB	M
Combine all existing plant records into a single as-built planset	MB/FPB	E
Complete a comprehensive electrical system audit	MB/FPB	E
Remove chemicals and metering equipment away from MCCs	MB	E
Review historical peak demand electrical consumption	MB/FPB	E
Replace MCC1 and MCC2 with new, current technology	MB/FPB	E
Replace MCC3 to address panel and interior component corrosion	MB	E

(1) MB = WTP Main Building. FPB = Finished Water Pump Building. CCB = Chlorine Contact Basin.

(2) P = Process, S = Structural, A = Architectural, M = Mechanical, and E = Electrical.

**TABLE 3-2****Sudden Valley WTP Recommended Modifications Summary**

<b>Modification</b>	<b>Location<sup>(1)</sup></b>	<b>Discipline<sup>(2)</sup></b>
Modify/repair existing flocculation tank	MB	P
Provide new grout floor within raw water pump pit	MB	P
Drain and clean the clearwell	MB	P
Procure spare backwash flow meter	MB	P
Procure dedicated confined space equipment for the WTP	MB	P
Install additional access ladder to Filters 1 and 2 and Filters 3 and 4	MB	P
Revise CT calculations to include clearwell and BE of 0.1	MB	P
Revise piping and conduit above flocculation tank	MB	P
Provide additional Operator In Trouble alarming equipment	MB/FPB	P
Replacing existing tube-style level alarm at flocculation tank	MB	P
Procure a spare finished water pump motor	FPB	P
Replace existing pressure gauges	FPB	P
Improve the visibility of the existing clearwell hatch	MB	P
Complete a performance test of the raw water, transfer, and finished water pumps	MB/FPB	P
Prepare and coat exposed ceiling rebar	MB	S
Address deficiencies found in 2016 seismic report	CCB	S
Perform formal CCB coating inspection	CCB	S
Address deteriorating conditions in restroom	MB	A
Investigate additional site security measures	MB/FPB	A
Remove heavy organic debris from roof	FPB	A
Repair wall seepage above MCC3	MB	A
Repair seepage/leaks at storefront window assemblies	MB	A
Modify floor to promote drainage to existing trench drain	MB	A
Revise existing storefront window to provide larger door opening	MB	A
Relocate stored filter media and other supplies equipment	MB	A
Conduct energy and heat audit	MB/FPB	M
Repair crack in generator exhaust piping	FPB	M
Conduct annual load testing for existing generator	FPB	E
Replace existing fluorescent light fixtures with LED equipment	MB/FPB	E
Replace AC backed system with DC backed systems	MB/FPB	E
Consolidate existing electrical panelboards	MB/FPB	E
Reroute floor mounted electrical conduit	MB/FPB	E
Reroute field wiring within grey/blue wall mounted panels	MB	E
Modify transfer pump pad based on long-term operations strategy	MB	E
Fuel tank relocation investigation	FPB	E

(1) MB = WTP Main Building. FPB = Finished Water Pump Building. CCB = Chlorine Contact Basin.

(2) P = Process, S = Structural, A = Architectural, M = Mechanical, and E = Electrical.

**A19: Finished Water Pump Building**



***Photographed:***  
Finished Water Pump Building north façade.



## **A20: Finished Water Pumps**




***From Left to Right:***

Finished water pumps and suction piping. Finished water pumps and discharge piping.



## A21: Auxiliary Generator



***Clockwise from Left:***

Auxiliary generator with washing machine and intake louver (background). Auxiliary generator. Auxiliary generator.

**A22: External Generator Diesel Fuel Tank**



***From Left to Right:***

Auxiliary generator diesel fuel tank. Auxiliary generator diesel fuel tank and Finished Water Pump Building south façade.




# WHATCOM COUNTY WATER DISTRICT NO. 10

## SUDDEN VALLEY

### WATER TREATMENT PLANT UPGRADE

#### TABLE OF SHEETS

CIVIL	CI - C4
ARCHITECTURAL	A1 - A4
ELECTRICAL	E1 - E16
PROCESS & INSTRUMENTATION DIAGRAMS	P1 - P5
REFERENCE	R1 - R10



VICINITY MAP  
(NOT TO SCALE)

NO.	REVISIONS	BY	DATE

**Wilson Engineering**  
CONSULTING ENGINEERS & SURVEYORS


805 DUPONT STREET #7  
BELLINGHAM, WA 98225  
(206) 733-6100  
FAX: (206) 647-9061

DESIGNED BY:  
MAC  
DRAWN BY:  
RAM  
CHECKED BY:  
MAC

WHATCOM CO. WATER DIST. NO. 10  
SUDDEN VALLEY  
WATER TREATMENT PLANT UPGRADE

JUL 24 1992  
B:\DWG\92006-C.DWG  
DATE: JUNE, 1992  
SHEET:    
SCALE: NONE  
JOB NUM: 92006

REBAR MARKED  
H. DENNING  
L.S. 10957



**Wilson Engineering**  
CONSULTING ENGINEERS & SURVEYORS


805 DUPONT STREET #7  
BELLINGHAM, WA 98225  
(206) 733-6100  
FAX: (206) 647-9061

DESIGNED BY:  
MAC  
DRAWN BY:  
RAM  
CHECKED BY:  
MAC


WHATCOM CO. WATER DIST NO. 10  
WATER TREATMENT PLANT  
SITE PLAN

JUL 24 1992  
B:\DMG\82006-C1.DWG  
DATE: MAY, 1992  
SCALE: AS SHOWN  
JOB NUMBER: 92006  
SHEET: C1 OF C4


NO.	REVISIONS	BY	DATE




**RAW WATER PUMPS & PIPING**  
NOT TO SCALE




**SECTION A**




**TRANSFER PUMPS & PIPING**  
NOT TO SCALE




**PLAN**




**FILTER PIPING MODIFICATIONS**  
NOT TO SCALE



**SODA ASH TANK - DETAIL C**  
NOT TO SCALE



**ALUM TANK - DETAIL D**  
NOT TO SCALE



NO.	REVISIONS	BY	DATE

**Wilson Engineering**  
CONSULTING ENGINEERS & SURVEYORS


805 DUPONT STREET #7  
BELLINGHAM, WA 98225  
(206) 733-6100  
FAX: (206) 647-9061

DESIGNED BY:  
MAC  
DRAWN BY:  
RAM  
CHECKED BY:  
MAC


WHATCOM CO. WATER DIST. NO. 10  
WATER TREATMENT PLANT  
PUMP & PIPING MODIFICATIONS

DATE	SHEET
MAY, 1992	C2
SCALE	OF
AS SHOWN	C4
JOB NUMBER	
92006	


JUL 2 4 1992  
B:\DWG\92006-C2.DWG



**WATER STORAGE TANK - PLAN**  
1" = 5'-0"



**WATER STORAGE TANK - ELEVATION**  
1" = 5'-0"



**1 INLET, OUTLET DIFFUSER - TYPICAL**  
NOT TO SCALE

NO.	REVISIONS	BY	DATE

**Wilson Engineering**  
CONSULTING ENGINEERS & SURVEYORS


805 DUPONT STREET #7  
BELLINGHAM, WA 98225  
(206) 733-6100  
FAX: (206) 647-9061

DESIGNED BY:  
MAC  
DRAWN BY:  
RAM  
CHECKED BY:  
MAC


WHATCOM CO. WATER DIST. NO. 10  
WATER TREATMENT PLANT  
STORAGE & CHEMICAL TANKS

DATE	SHEET
MAY, 1992	C3
SCALE	OF
JOB NUMBER 92006	C4


JUL 24 1992  
P: DMC/92006-C3



SECTION B  
NOT TO SCALE



SECTION A  
NOT TO SCALE



PLAN  
NOT TO SCALE

NO.	REVISIONS	BY	DATE

**Wilson Engineering**  
CONSULTING ENGINEERS & SURVEYORS


805 DUPONT STREET #7  
BELLINGHAM, WA 98225  
(206) 733-6100  
FAX: (206) 647-9061

DESIGNED BY:  
MAC  
DRAWN BY:  
RAM  
CHECKED BY:  
MAC

WHATCOM CO. WATER DIST. NO. 10  
WATER TREATMENT PLANT  
TRANSMISSION PUMPING UNIT

JUL 24 1992  
B:\DW9206-C4.DWG

DATE	SHEET
MAY, 1992	C4
SCALE	OF
AS SHOWN	
JOB NUMBER	C4
92006	



PERSPECTIVE SKETCH

# WATER TREATMENT PLANT CONTROL BUILDING

## Morning Beach Drive, Sudden Valley, Washington

Water District 10 Sudden Valley  
**Water Treatment Plant Control Bldg.**  
 Morning Beach Drive Sudden Valley, WA

Job Number 9210  
 Drawn By KCG  
 Checked By RCR  
 Date 6 15 92  
 Revisions

**A1**

ARCHITECTURAL ABBREVIATIONS					REFERENCE SYMBOLS		MATERIALS		The Drawings, Specifications and other portions of the Contract Documents are instruments of the Architect's service for use solely with respect to the Project and, unless otherwise authorized in writing by the Architect, any use or re-use is strictly prohibited. Written Dimensions have precedence over scaled measurements. Dimensions and detail conditions shall be verified by the Contractor with the Architect before proceeding with the Work.
<b>SYMBOLS USED AS ABBREVIATIONS</b> angle centerline channel penny perpendicular plus round diameter  <b>ABBREVIATIONS</b> ABV above AFF above finished ACG access AC, ACOUS acoustical ACT acoustical tile ADD addendum ADJ adjacent AGG adjustable ALT alternate AL ALUM aluminum AB anchor bolt ANOD anodized APPROVAL written approval D by the Architect APPROX approximate ARCH architect ASB asbestos ASPH asphalt AUTO automatic  BSMT basement BRG bearing BM bench mark BETW between BVL BLK, BLKG block, blocking BD board BOT BTM bottom BRK brick BLDG building BUR built up roofing  CAB cabinet CPT carpet CSMT cast iron CI cast iron CB catch basin CLK culk CLG, CEIL ceiling CEM cement CER ceramic CHAM ceramic tile CHAM chamfer CIR circle	CLR clear COL column COMB combination COMPOS composition, (composite) COMP compress (rod) CONG concrete CMU concrete masonry unit CONST construction CONT continuous or continuous contract (or) CONTR control joint CJ control joint CG corner guard CORR corrugated, floor CTR counter CTSK counter/sunk CRS course (s) DEMO demolition DTL detail DIAG diagonal HDW hardware HDR header HTG heating HVAC heat/ventilating HT air conditioning HC hollow core HM hollow metal HOR, H, HORIZ horizontal HB hose bibb HWH, HWT hot water heater, tank  ID inside diameter INSTALL apply or install only INS, INSUL insulate (d), (on) INT interior INV invert JC jointer's closet JT, J joint KPL kickplate KIT kitchen KO knockout LAB laboratory LAD ladder LBL leg bolt LAM laminate (d) LAV lavatory LH left hand L length	FE fire extinguisher FEC fire extinguisher cabinet FPL fireproof FLG, FLASH floor (ing) FLR floor FD floor drain FTG, FOOT footing FND, FOUN Foundation FR, FRM frame (d), (ing) FURNISH supply only  GA gauge GALV galvanized GI glass, glazing GLB, GLK glass block GB grab bar GVL gravel GT grout GWB gypsum wall board  HBD hardboard HDW hardware HDW hardware HDR header HTG heating HVAC heat/ventilating HT air conditioning NR noise reduction NRC noise reduction coefficient NOM nominal N north NIC not in contract NTS not to scale  OBS obscure OC on center (s) OPP opposite OPH opposite hand OD outside diameter OH overhead  PNL panel PNB panel bar PTD paper towel dispenser PTL paper towel PVR particle board PWB partition PVT pavement PERF perforate (d) PLS plaster PLAM plastic laminate PL plate PWD, PLYW plywood LH left hand L length PVC polyvinyl chloride	LT, LITE light LW lightweight LP low point  M B machine bolt M H manhole MFR manufacture (or) M RB marble M KBD marker board MAS masonry M O masonry opening MTL material (s) MAX maximum MECH mechanic (a) MC medicine cabinet MED medium MBR member MBR membrane MET metal MWK millwork MIN minimum MIR mirror MISC miscellaneous MOD modular MLD molding MT mount (ed), (ing) MULL mullion  NAT natural ND noise reduction NR noise reduction NRC noise reduction coefficient NOM nominal N north NIC not in contract NTS not to scale  OBS obscure OC on center (s) OPP opposite OPH opposite hand OD outside diameter OH overhead  PNL panel PNB panel bar PTD paper towel dispenser PTL paper towel PVR particle board PWB partition PVT pavement PERF perforate (d) PLS plaster PLAM plastic laminate PL plate PWD, PLYW plywood LH left hand L length PVC polyvinyl chloride	PCF pounds per cubic foot PFL pounds per linear foot PSF pounds per square foot PSI pounds per square inch PFN prefinished PL furnish & install QT quarry tile RBT rabbit RAD radius REF reference RFL reflect (ed), (vs), (or) REFR, RFR refrigerator REG register RE, REINF reinforcement (d), (ing) RES resilient MOD modular RA return RH right hand RH right of way RO roof RD roof drain RFH roof hatch RFG roofing RM room RO rough opening RB rubber base  SCH schedule SNT, SEAL sealant SEC section SELECTED as selected by the Architect SHTH sheathing SHT sheet SH, SHLV shelving SHOWN as shown or noted on the drawings SIM similar SKL, SKLT skylight SC solid core SF soundproof S south SPK speaker SPEC specification (s) SQ square SBT stainless steel STD standard STA station ST, STL steel SD storm drain STR structural SUS suspended SYM symmetry (cal)	SYS system TKBD tackboard TEL telephone TV television THK thick (ness) THR threshold TP toilet partition TPD toilet paper dispenser T & G tongue and groove TOB top of slab T towel bar T tread TYP typical UNFIN unfinished UR urinal VJ v-joint (ed) VB vapor barrier VAR varnish VBR veneer VERT, V vertical VG vertical grain VIN vinyl VCT vinyl composition tile VB vinyl base VF vinyl fabric VT vinyl tile WSCOT water closet WC watercloset WP waterproofing WWF welded wire fabric W west W width, wide W/ with WIN, WDW window WM mesh WO wood	North True North (if not called North)  Finish Grade Elevation  Existing Contour  New Contour  Level Line  Center Line  Match Line, Cut Line  Property Line  Project Limit Line  Grid Number/Letter  Building Section Letter Sheet Where Shown Wall Section Letter Sheet Where Shown Detail Number Sheet Where Shown  <b>1 DETAIL</b> Detail Number & Title SCALE: 3/4" = 1'-0" Dash on Sheet Where Shown (and Sheet Where Called If Both on Same Sheet). Scale Sheet Where Shown Interior Elevation Key Numbers Room Number Door Number Window/Patio Letter Revision	Acoustic Tile or Board Brick Ceramic Tile or Concrete Concrete Masonry Earth Glass Gypsum Wall Board Ball Insulation Rigid Insulation Metal Plaster on Metal Lath Mortar, Plaster or Grout Plywood Rock FB Sand Stone Finish Wood Framing Lumber Blocking Lumber		







Water District 10  
**Water Treatment Plant Control Bldg.**  
Morning Beach Drive  
Sudden Valley, WA

Job Number 0210  
Drawn By KGA  
Checked By RCR  
Date 6/15/92  
Revisions


**A2**




**Section C-C**




**Section D-D**



**Section B-B**



**Section A-A**




**Floor Plan**

SCALE: 1/4"=1'-0"  
ALL DRAWINGS THIS SHEET




Water District 10 Sudden Valley  
**Water Treatment Plant Control Bldg.**  
 Morning Beach Drive Sudden Valley, WA

Job Number 0210  
 Drawn By KCA  
 Checked By RCR  
 Date 6/15/92  
 Revisions








South

West






East


North  
**Elevations**  
 SCALE: 1/4" = 1'-0"  
 ALL DRAWINGS THIS SHEET



**Roof Framing Plan**  
 SCALE: 1/4" = 1'-0"



ABBREVIATION	SYMBOL	DESCRIPTION	SYMBOL		DESCRIPTION	SYMBOL		DESCRIPTION
			SCHEMATIC	PLAN		SCHEMATIC	PLAN	
A, AMP - AMPERE								
AL - ALARM								
AC - AIR COMPRESSOR								
AF - AMPERE FRAME								
AFF - ABOVE FINISHED FLOOR								
AFS - AMPERE FUSE								
AI - ANALOG INPUT POINT (PLC)								
AIL - AMBER INDICATING LIGHT								
ALT - ALTERNATOR								
AO - ANALOG OUTPUT POINT (PLC)								
AS - AMPERE SWITCH								
AT - AMPERE TRIP								
ATS - AUTOMATIC TRANSFER SWITCH								
BC - BATTERY CHARGER								
BH - BLOCK HEATER								
BIL - BLUE INDICATING LIGHT								
BP - BYPASS CONTACTOR								
C - CONDUIT (GRS)								
CB - CIRCUIT BREAKER								
CP - CONTROL PANEL								
CPT - CONTROL POWER XFMR								
CT - CURRENT TRANSFORMER								
CV - CHECK VALVE								
DB - DIRECT BURIED								
DEM - DEMAND								
DF - DEMAND FACTOR								
DIAC - AC DIGITAL INPUT POINT (PLC)								
DOAC - AC DIGITAL OUTPUT POINT (PLC)								
EF - EXHAUST FAN								
EX, EXIST. - EXISTING								
GND - GROUND								
GRC - GALVANIZED RIGID STEEL (CONDUIT)								
H - HOT, HIGH								
HH - HIGH HIGH								
HOA - HAND-OFF-AUTO								
IC - ISOLATION CONTACTOR								
ISR - INTRINSICALLY SAFE RELAY								
KVARH - KILOWATT HOUR								
KWH - KILOWATT HOUR								
L - LOW								
LS - LIMIT SWITCH								
N - NEUTRAL								
MCP - MAIN CONTROL PANEL								
MOV - MOTOR OPERATED VALVE								
OIT - OPERATOR IN TROUBLE								
PB - PUSH BUTTON								
PFR - PHASE FAILURE RELAY								
PS - PRESSURE SWITCH								
PT - POTENTIAL TRANSFORMER								
PVC - POLY VINYL CHLORIDE (CONDUIT)								
RHP - RADIANT HEAT PANEL								
RIL - RED INDICATING LIGHT								
RTM - RUN TIME METER								
SV - SOLENOID VALVE								
TC - TIME CLOCK								
TDOE - TIME DELAY ON ENERGIZATION								
TDOO - TIME DELAY ON DE-ENERGIZATION								
TWSP - TWISTED SHIELDED PAIR								
TWST - TWISTED SHIELDED THREE CONDUCTOR								
UH - UNIT HEATER								
VFD - VARIABLE FREQUENCY DRIVE								
VGS - VOLATILE GAS SENSOR								
WIL - WHITE INDICATING LIGHT								
WP - WEATHER PROOF								
WV - WASTE VALVE								
XFMR - TRANSFORMER								
<b>REFERENCE SYMBOLS</b>								
(P1)	POWER CONDUIT & WIRE TAG, SEE SCHEDULE							
(C1)	CONTROL CONDUIT & WIRE TAG SEE SCHEDULE							
(S1)	SIGNAL CONDUIT & WIRE TAG, SEE SCHEDULE							
(T1)	TELEPHONE CONDUIT & WIRE TAG							
1	SHEET NOTE							
P-01	MECHANICAL EQUIP. DESIGNATION							
PSL-101	INSTRUMENT DESIGNATION							
A	SECTION NUMBER							
E1	SECTION CUT							
A	SHEET ON WHICH SECTION APPEARS							
A	SECTION NUMBER							
E1	SECTION SCALE							
A	SHEET ON WHICH SECTION CUT APPEARS							
		FLUORESCENT LIGHTING FIXTURE "F1" INDICATES TYPE AS PER LIGHTING SCHEDULE, "2" INDICATES CIRCUITING			GROUND WELL			METAL OXIDE VARISTOR
		INCANDESCENT LIGHTING FIXTURE SURFACE			GROUND ROD			DISCRETE (120V) TERMINAL STRIP POINT
		INCANDESCENT LIGHTING FIXTURE, WALL MOUNT.			HANDHOLE WITH DESIGNATION			CIRCUIT DISCONNECTING DISCRETE TERMINAL STRIP POINT
		EXIT LIGHT WITH BATTERY PACK			PANELBOARD			SIGNAL (ANALOG OR 24Vdc) TERMINAL STRIP POINT
		EMERGENCY WALL PACK.			TRANSFORMER			CIRCUIT DISCONNECTING SIGNAL TERMINAL STRIP POINT
		JUNCTION BOX WITH BLANK COVER			CURRENT TRANSFORMER, NUMERAL INDICATES NUMBER OF C.T.'S			RUNNING TIME METER
		DUPLEX RECEPTACLE "2" INDICATES CIRCUITING IG INDICATES ISOLATED GROUND.			LOUVER (SPRING OPEN, MOTOR CLOSE)			SMOKE DETECTOR
		DUPLEX RECEPTACLE WITH GROUND FAULT PROTECTION			METER & SWITCH: A=AMP V=VOLT			TELEPHONE OUTLET
		208V, 3#, RECEPTACLE			BATTERY			SOLENOID VALVE
		SINGLE POLE SWITCH.			FUSE			ANALYTICAL TRANSMITTER
		DOUBLE POLE SWITCH.			MOTOR, NUMBER INDICATES HORSEPOWER			LEVEL TRANSMITTER
		THREE WAY SWITCH.			EXHAUST OR SUPPLY FAN NUMBER INDICATES HOREPOWER			PRESSURE TRANSMITTER
		CONDUIT HOME RUN 3/4" C, 2#12 & 1#12 GND. TO PANEL L, CKT. 7 UNLESS SHOWN OTHERWISE			ELECTRIC HEATER WINDING			FLOW TRANSMITTER
		CONDUIT HOME RUN -- SEE SCHEDULE.			GENERATOR			FLOW SWITCH
		(C10) TO MCP, (L-10) TO PANEL "L", (P10) TO MCC			DISCONNECT SWITCH NON FUSED. NO (60) INDICATES AMPERAGE RATING.			LIMIT SWITCH, NORMALLY OPEN
		CONDUIT EXPOSED, NEW			DISCONNECT SWITCH FUSED 200=SWITCH RATING, 100=FUSE RATING.			LIMIT SWITCH, NORMALLY CLOSED.
		CONDUIT EXPOSED, EXISTING			MOTOR WINDING HEATER			LEVEL SWITCH, NORMALLY OPEN
		CONDUIT UNDERGROUND OR IN FLOOR SLAB.			FULL VOLTAGE STARTER / NEMA SIZE MS=MOTOR STARTER CONTACT			LEVEL SWITCH, NORMALLY OPEN
		CONDUIT FLEXIBLE.			WATT HOUR METER			PRESSURE SWITCH, NORMALLY OPEN
		CONDUIT UP.			CONTROL RELAY			DOOR SECURITY SWITCH
		CONDUIT DOWN.			PHASE FAIL RELAY & FUSE			TIME DELAY RELAY, ON DELAY. (DELAY TIME)
		CONDUIT CAPPED			INDICATING LIGHT: G=GREEN, R=RED, A=AMBER, B=BLUE, W=WHITE			TIME DELAY RELAY, OFF DELAY. (DELAY TIME)
		PHOTO ELECTRIC CELL			ANNUNCIATOR WINDOW: G=GREEN, R=RED, A=AMBER, B=BLUE, W=WHITE			CONDUCTORS NOT CONNECTED.
		TO BE REMOVED			HORN			CONDUCTORS CONNECTED
		TO BE REMOVED			SELECTOR SWITCH: HOA=HAND-OFF-AUTO AS=AMP SWITCH VS=VOLT SWITCH			TWISTED SHIELDED PAIR (TWSP)
		EXISTING UNDERGROUND POWER			PUSHBUTTON SWITCH, MOMENTARY ON			PULL OUT SWITCH
		EXISTING UNDERGROUND TELEPHONE			PUSHBUTTON SWITCH, MOMENTARY OFF			BLOWN FUSE INDICATOR
		EXISTING UNDERGROUND WATER			SELECTOR SWITCH: RUN-STOP/ON-OFF			TERMINAL IN MCC
		EXISTING UNDERGROUND GAS			LOCAL EQUIPMENT CONTROL PANEL			TERMINAL REMOTE DEVICE OR PANEL
					CONDUIT WITH SEAL FITTING			NORMALLY OPEN CONTACT.
					HAND-OFF-REMOTE SELECTOR SWITCH			NORMALLY CLOSED CONTACT.
					GREEN INDICATOR LIGHT /WHITE INDICATOR LIGHT			THERMAL OVERLOAD HEATER.



EDPMS 4/17/94 EDPMS 4/17/93

NO.	REVISIONS	BY	DATE

**Wilson Engineering**  
CONSULTING ENGINEERS & SURVEYORS

805 DUPONT STREET #7  
BELLINGHAM, WA 98225  
(206) 733-6100  
FAX: (206) 647-9061


**CASNE ENGINEERING, INC.**  
P.O. BOX 7207  
BELLINGHAM, WA 98208  
(206) 464-3050

DESIGNED BY: DMB/VMF  
DRAWN BY: TEO  
CHECKED BY: KLA


WHATCOM COUNTY  
WATER TREATMENT PLANT  
LEGEND AND ABBREVIATIONS

DATE	SHEET
July 1992	E01
SCALE NONE	OF
JOB NUMBER 92021A	16


92021E01




**HANDHOLE/MANHOLE**  
N.T.S.




**CONDUIT FLOOR TERMINATION**  
N.T.S.




**TYPICAL FREESTANDING EQUIPMENT MOUNTING**  
N.T.S.




**SHIELDED WIRE TERMINATION**  
N.T.S.




**MAKEUP AT MOTOR**  
N.T.S.




**GROUND ROD DETAIL**  
N.T.S.




**CIRCUIT BREAKER PANELBOARD AND TRANSFORMER TYPICAL SURFACE MOUNTING ASSEMBLY**  
N.T.S.



**UNACCEPTABLE METHOD OF GROUNDING CONTROL CABLE SHIELD**




**ELEVATION**



**PLAN**

**CONDUIT RACK FOR SEISMIC ZONES 3 & 4**  
N.T.S.



**RESERVOIR LEVEL SWITCH INSTALLATION DETAIL**  
N.T.S.

**NOTES:**  
 1. HARDWARE SHALL BE HOT DIP OR MECHANICALLY GALVANIZED AFTER FABRICATION, EXCEPT FASTENERS MAY BE ZINC PLATED.  
 2. MAX. UNIFORMLY DISTRIBUTED LOAD (CONDUIT AND FILL) PER UNIT TO BE 1000 LBS. CONTRACTOR TO PROVIDE CALCULATIONS WHEN ANY CONDUIT IS OVER 2" IN SIZE OR IF CONDUIT IS INSTALLED ON TOP AND BOTTOM OR RACK.  
 3. HOLE SIZES ON FITTINGS SHALL BE 9/16" DIA WITH 1/2" HED HEAD CAP SCREW 15/16" LONG AND 1/2" CLAMP NUT WITH SPRING.  
 4. SEISMIC CHANNEL BRACING REQUIRED AT INTERVALS OF 60' MAX FOR ZONE 3 AND 40' MAX FOR ZONE 4.

NO.	REVISIONS	BY	DATE


**Wilson Engineering**  
CONSULTING ENGINEERS & SURVEYORS

805 DUPONT STREET #7  
BELLINGHAM, WA 98225  
(206) 733-6100  
FAX: (206) 667-9061

**CASNE ENGINEERING, INC.**  
DESIGNED BY: DMB/vmf  
DRAWN BY: TEO  
CHECKED BY: KLA

**WHATCOM COUNTY WATER TREATMENT PLANT ELECTRICAL DETAILS**

DATE	SHEET
July 1992	E02
SCALE AS SHOWN	OF
JOB NUMBER 92021A	16




DEMAND CALC WATER TREAT BLDG.				
LOAD	HP	kVA	DF	kVA
RWP	20	20	1	20
*RWP	20	20	0	-
XP	25	25	1.25	32
*XP	25	25	0	-
MISC.		40	1	40
<b>TOTAL</b>		<b>130</b>		<b>92</b>
92kA = 111 AMPS @ 480V, 3φ				

DEMAND CALC PUMP BLDG.				
LOAD	HP	kVA	DF	kVA
TRP	150	140	1.25	175
*TRP	150	140	0	-
TRP	100	96	1	96
*TRP	100	96	0	-
MISC.		10	1	10
<b>TOTAL</b>		<b>574</b>		<b>373</b>
373kVA = 449 AMPS @ 480V, 3φ				

\*PUMPS HAVE 100% BACKUP - INTERLOCKED SUCH THAT ONLY ONE OF EACH PAIR WILL RUN AT ONE TIME

LEGEND	
POWER	—————
CONTROL	-----
EXISTING	-----



NO.	REVISIONS	BY	DATE


**Wilson Engineering**  
CONSULTING ENGINEERS & SURVEYORS

805 DUPONT STREET #7  
BELLINGHAM, WA 98225  
(206) 733-6100  
FAX: (206) 647-9061

**CASNE ENGINEERING, INC.**  
DESIGNED BY: DMB/VMF  
DRAWN BY: TEO  
CHECKED BY: KLA


**WHATCOM COUNTY WATER TREATMENT PLANT - ONE LINE DIAGRAM**

DATE	SHEET
July 1992	EO3
SCALE NONE	OF
JOB NUMBER 92021A	16




92021EO3






- NAME PLATES**
1. NORMAL SOURCE
  2. EMERGENCY SOURCE
  3. READY
  4. RUN
  5. FAIL
  6. NORMAL POWER AVAILABLE
  7. EMERGENCY POWER AVAILABLE
  8. AUTOMATIC TRANSFER SWITCH

**MCC 1 - PUMP BUILDING**  
3/4"=1'-0"



**MCC 2 - WATER TREATMENT PLANT**  
3/4"=1'-0" NEMA 12



**WTP CONTROL AREA ELEVATION**  
E7 NTS

LIGHTING FIXTURE SCHEDULE	
F1	4FT. 2-LAMP INDUSTRIAL FLUORESCENT 10X UPLIGHT ENERGY SAVING BALLAST 120V LITHONIA #AF10-240-120-ES.
F2	4FT. 2-LAMP INDUSTRIAL FLUORESCENT GASKETED ALUMINUM HOUSING WITH WET LABEL. INJECTION MOLDED ACRYLIC WRAPAROUND LENS. CORROSION RESISTANT FINISH, -0 DEGREE BALLAST, 120V HOLOPHANE #7200-4-LT-P1.
F3	4 FT., 2-LAMP WALL MOUNT TASK LIGHT WITH #12 ACRYLIC LENS, UL DAMP LOCATION LABEL AND ENERGY SAVING BALLAST LITHONIA WS-240-A12-ESDL.
F4	SOFFIT LIGHT, 70W HPS, SQUARE, RECESSED, VANDAL PROOF, SUITABLE FOR DAMP LOCATIONS LITHONIA VRR-70S.
F5	POLE MOUNTED 70W HPS AREA LIGHT, SUITABLE FOR DAMP LOCATIONS, 12" ACRYLIC REFRACTOR WITH GUARD. MOUNT ON STRAIGHT STANTION 1-1/4" PIPE. GE VERSA GUARD H6 SERIES #07S. OR EQUAL.
F6	2-LAMP EMERGENCY WALL PACK RECHARGABLE BATTERY, VOLTMETER, 2 HALOGEN LAMPS 120V, EXIDE F-100-2H-V.

**NOTES:**

- 1 MAINTAINED CONTACT RED MUSHROOM HEAD PUSHBUTTON FOR OPERATOR-IN-TROUBLE TO TELEMETRY



EXPIRES 4/17/94 EXPIRES 4/17/93

NO.	REVISIONS	BY	DATE

**Wilson Engineering**  
CONSULTING ENGINEERS & SURVEYORS

805 DUPONT STREET #7  
BELLINGHAM, WA 98225  
(206) 733-6100  
FAX: (206) 647-9061

**CASNE ENGINEERING, INC.**  
P.O. BOX 7207  
BELLINGHAM, WA 98208  
(206) 464-3555

DESIGNED BY: DMD/VMF  
DRAWN BY: TEO  
CHECKED BY: KLA



**WHATCOM COUNTY**  
WATER TREATMENT PLANT  
MCC ELEV. & LTG. FIXTURE SCHEDULE

DATE	SHEET
July 1992	E04
SCALE AS SHOWN	OF
JOB NUMBER 92021A	16


92021E04

1 HH 2'x3'x3' FOR PULLING-UTILITY VAULT LA-233 WITH H-20 LOADING COVER OR EQUAL


EXISTING SWITCH  
E




**D WTP RESERVOIR DETAIL**  
E5 N.T.S.




**A TRENCH SECTION**  
E5 N.T.S.



**C WTP BLDG CONDUIT PENETRATION**  
E5 N.T.S.



**B TRENCH SECTION**  
E5 N.T.S.



NO.	REVISIONS	BY	DATE

**Wilson Engineering**  
CONSULTING ENGINEERS & SURVEYORS

805 DUPONT STREET #7  
BELLINGHAM, WA 98225  
(206) 733-6100  
FAX: (206) 647-9061


**CASNE ENGINEERING, INC.**  
DESIGNED BY: DMB/VMF  
DRAWN BY: TEO  
CHECKED BY: KLA

**WHATCOM COUNTY WATER TREATMENT PLANT SITE PLAN**

DATE	SHEET
July 1992	E05
SCALE	OF
1"=10'	16
JOB NUMBER	
92021A	

92021E05





**DEMOLITION PLAN**  
**EXISTING POWER CONTROL, REC. & LIGHTING**  
 SCALE: 1/4"=1'-0"

**GENERAL NOTES:**

- 1 REMOVE BASE BOARD HEATER AND ASSOCIATED WIRE, CAP CONDUIT
- 2 REMOVE SERVICE ENTRANCE SWITCHBOARD AND SERVICE CONDUCTORS
- 3 REMOVE MOTOR CONTROL CENTER - DISCONNECT AND STARTER MOUNTED ABOVE MCC
- 4 REMOVE FILTER 1 & 2 BACKWASH CONTROL PANEL
- 5 REMOVE FILTER 1 & 2 AND 3 & 4 TURBIDIMETERS, CONDUIT, & WIRE TO BE REUSED
- 6 REMOVE FILTER 3 & 4 BACKWASH CONTROL PANEL AND ALL ASSOCIATED CONDUIT AND WIRE
- 7 REMOVE PANEL A.
- 8 REMOVE PANEL B TRANSFORMER AND SERVICE CONDUIT/WIRE TRANSFORMER TO BE REUSED MOUNT ABOVE NEW MCC
- 9 REMOVE PANEL B
- 10 REMOVE FILTER 3 & 4 SOLENOID VALVES - REUSE CONDUIT & WIRE
- 11 SEE SWITCH-OVER SEQUENCE IN THE SPECIFICATIONS
- 12 REMOVE CONDUCTORS & FLEX CONDUIT FOR 75 HP TRANSMISSION PUMPS
- 13 REMOVE TRANSMISSION PUMP SOLENOID VALVES, FLEX CONDUIT AND WIRE (2 SOLENOIDS PER PUMP)
- 14 REMOVE TRANSMISSION PUMP, PRESSURE SWITCHES, CONDUIT AND WIRE
- 15 REMOVE SERVICE CONDUCTORS FROM POWER XFMR TO SWITCHBOARD PUGET POWER TO REMOVE XFMR
- 16 EXISTING SODA ASH & ALUM TANKS TO BE REMOVED AND REPLACED ASSOCIATED MIXER & METERING PUMPS TO BE REMOVED AND REINSTALLED ON NEW TANKS.
- 17 REMOVE 1/2HP PUMP AND ASSOCIATED CONDUCTORS & FLEX CONDUIT
- 18 DISCONNECT RAW WATER PUMP AND REMOVE CONDUCTORS
- 19 EXISTING SUMP PUMP IS NOT OPERATIONAL - TO REMAIN AS IS
- 20 EXISTING CONDUIT & WIRE TO TELEMETRY PANEL TO BE REMOVED
- 21 SAMPLE PUMP TO BE REMOVED AND TURNED OVER TO OWNER
- 22 REMOVE EXISTING METER, BASE, AND ASSOCIATED CONDUIT & WIRE TO C.T. ENCLOSURE



EXPIRES 4/17/94      EXPIRES 4/17/93

NO.	REVISIONS	BY	DATE

**Wilson Engineering**  
 CONSULTING ENGINEERS & SURVEYORS

805 DUPONT STREET #7  
 BELLINGHAM, WA 98225  
 (206) 733-6100  
 FAX: (206) 647-9061

**E**  
**CASNE**  
**ENGINEERING,**  
**INC.**  
 P.O. BOX 7207  
 BELLEVUE, WA 98008  
 (206) 404-3555


DESIGNED BY:  
 DMB/VMF  
 DRAWN BY:  
 TEO  
 CHECKED BY:  
 KLA

**WHATCOM COUNTY**  
**WATER TREATMENT PLANT**  
**EXIST. POWER & CONTROL DEMO. PLAN**


DATE	SHEET
July 1992	E06
SCALE	OF
AS SHOWN	
JOB NUMBER	16
92021E06	

**FLAG NOTES:**

- 1 RECONNECT ALL EXISTING EQUIPMENT REUSE EXISTING CONDUIT AND WIRE WHEN POSSIBLE
- 2 PROVIDE SIX NEW SOLENOID VALVES AND TWO LEVEL SWITCHES FOR FILTERS
- 3 PROVIDE SUMP FLOOD SWITCH
- 4 PROVIDE RESERVOIR LEVEL TRANSMITTER
- 5 PROVIDE CONDUCTORS TO NEW RAW WATER PUMPS AND NEW TRANSFER PUMPS
- 6 PROVIDE NEW MCP & MCC-2
- 7 RELOCATE EXISTING 30kVA 480-120/208, 3Ø, XFMR MOUNT ABOVE MCC
- 8 RELOCATE FILTER 1 & 2 TURBIDIMETER
- 9 RELOCATE FILTER 3 & 4 TURBIDIMETER
- 10 SEE CONTROL PANEL SCHEMATICS FOR CIRCUIT DESIGNATIONS
- 11 PROVIDE NEW LEVEL SWITCH
- 12 PROVIDE NEW DOOR SWITCH
- 13 PROVIDE NEW ROCKWELL "HSP" HEAD FOR EXISTING FLOW METER
- 14 CAP ALL UNUSED RACEWAYS AT FLOOR STUB-UP
- 15 NEMA 4X, NON-METALIC, MAINTAINED CONTACT RED MUSCHROOM HEAD PUSHBUTTON TO SEND CLOSED CONTACT TO TELEMETRY WHEN PUSHED
- 16 EXISTING MOTORS TO BE DISCONNECTED FOR REMOVAL OF EXISTING TANKS. RECONNECT AFTER INSTALLATION OF NEW TANK



**WATER TREATMENT PLANT  
NEW POWER & CONTROL PLAN**  
SCALE: 1/4"=1'-0"



NO.	REVISIONS	BY	DATE

**Wilson Engineering**  
CONSULTING ENGINEERS & SURVEYORS

805 DUPONT STREET #7  
BELLINGHAM, WA 98225  
(206) 733-6100  
FAX: (206) 647-9861

**E**  
CASNE  
ENGINEERING,  
INC.  
P.O. BOX 7207  
BELLINGHAM, WA 98206  
(206) 464-3556

DESIGNED BY:  
DMB/VMF  
DRAWN BY:  
TEO  
CHECKED BY:  
KLA

**WHATCOM COUNTY  
WATER TREATMENT PLANT  
NEW POWER & CONTROL PLAN**

DATE	SHEET
July 1992	E07
SCALE AS SHOWN	OF
JOB NUMBER 92021A	16

92021E07





**GENERAL NOTES:**


- 1 PROVIDE LAB AREA LIGHTS & RECEPTACLE
- 2 PROVIDE C12 ROOM RECEPTACLES
- 3 HARD WIRE EXISTING LIGHT IN OFFICE TO EXISTING SWITCH
- 4 PROVIDE TERMINAL BOX FOR EXISTING CIRCUITS TO 120/208V LOADS. LAND ALL EXISTING CIRCUITS ON TERMINALS IN BOX. EXTEND EXISTING 2" C AND PULL NEW CONDUCTORS FROM MCC/PNL-B TO TERMINAL BOX. CIRCUITS AS SHOWN ON DRAWING AND PANEL SCHEDULE B
- 5 EXTEND ALL OTHER HOME RUN CONDUITS (NOT INCLUDED IN NOTE #4) TO NEW MCC - REUSE EXISTING CONDUCTORS IF POSSIBLE
- 6 REWIRE EXISTING 277V BAY LIGHTS - SEE MCC LAYOUT & ONE-LINE FOR DETAILS
- 7 SEE FIXTURE SCHEDULE SHEET E4
- 8 PROVIDE NON-CONDUCTIVE SAFETY MAT IN FRONT OF ENTIRE CONTROL PANEL AND MCC.

**PANEL SCHEDULE**

NO. B		LOCATION: WTP BUILDING MCC2		120/208 VOLTS		3 PHASE		4 WIRE	
SERVING -		100 AMP with MAIN CB 80/3							
CKT NO.	LOAD DESCRIPTION	KVA	TRIP AMPS	TRIP AMPS	KVA	TRIP AMPS	TRIP AMPS	LOAD DESCRIPTION	CKT NO.
1	WALL LIGHTS	0.6	20	20	-	-	-	SPARE	2
3	REC LAB AREA/C12 ROOM	0.6	20	20	0.4	20	20	RESTROOM	4
5	FAN CHLORINE ROOM	0.3	20	20	0.8	20	20	OFFICE/SUMP LIGHTS & REC	6
7	HVAC CONTROL	0.2	20	20	0.2	20	20	CLEAR WELL LIGHTS	8
9	MCP	0.5	20	20	-	20	20	SPARE	10
11	TELEMETRY CONTROL POWER	0.3	20	20	1.4	20	20	SODA ASH METER PUMP & MIXER	12 *
13	MCP	0.5	20	20	0.7	20	20	ALUM METER PUMP	14 *
15	MCP	0.5	20	20	1.0	20	20	MCP SPARE	16 *
17	TURBIDITY ANALYSERS	0.2	20	20	0.6	20	20	PANEL C FEED	18
19	208V RECEPTACLES	1.4	20	20	1.5	20	20	HOT WATER TANK	20
21									22
23	SPARE								24
25									26
27									28
29									30
31									32
33									34
35	SPARE								36
37									38
39									40
41									42
DESCRIPTION				CONNECTED LOAD	DEMAND FACTOR	DEMAND			
LARGEST MOTOR				0.7	1.25	0.9			
OTHER MOTORS				1.9	1.00	1.9			
LIGHTS				1.3	1.25	1.7			
MISC.				6.8	1.00	6.8			
* VIA STARTERS IN MCP				TOTAL	10.7	KVA	29	KVA	31
					AMPS		AMPS		



**LIGHTING, RECEPTACLE AND HVAC POWER PLAN**  
SCALE: 1/4"=1'-0"



NO.	REVISIONS	BY	DATE

**Wilson Engineering**  
CONSULTING ENGINEERS & SURVEYORS

885 DUPONT STREET #7  
BELLINGHAM, WA 98225  
(206) 733-6100  
FAX: (206) 647-9061


**E** CASNE ENGINEERING, INC.  
P.O. BOX 7207  
BELLINGHAM, WA 98208  
(206) 464-3556

DESIGNED BY: DMB/VMF  
DRAWN BY: TEO  
CHECKED BY: KLA


**WHATCOM COUNTY**  
WATER TREATMENT PLAN  
LIGHTING, RECPT., & HVAC POWER PLAN  
PANEL B SCHEDULE

DATE	SHEET
July 1992	E08
SCALE	OF
AS SHOWN	16
JOB NUMBER	92021A

92021E08



**PUMP BUILDING  
CONDUIT & EQUIP. PLAN**  
SCALE: 1/4"=1'-0"




**PUMP BUILDING  
EAST WALL ELEVATION**  
E9


**GENERAL NOTES:**  
1. CONDUITS SHOWN SOLID SHALL BE ROUTED ABOVE CEILING OR WITHIN WALLS WHEN EVER POSSIBLE.

**FLAG NOTES:**  
1 PROVIDE RESTROOM RECEPTACLES WITH LOCKING COVER PASS & SEYMOUR LEGRAND #WP-26L OR EQUAL.  
2 PROVIDE CONDUCTORS AND JUNCTION BOX FOR FUTURE LIGHTS  
3 PROVIDE NON-CONDUCTIVE MAT ENTIRE LENGTH OF MOTOR CONTROL CENTER


PANEL SCHEDULE						
LOCATION: WTP PUMP BLDG.						
120/208 VOLTS 1 PHASE 3 WIRE						
100 AMP WITH 50/2						
NO	L	LOAD DESCRIPTION	KVA	TRIP AMPS	TRIP AMPS	CKT NO.
1	REC	GEN ROOM	0.6	20	20	1
2	REC	PUMP ROOM	0.8	20	20	2
3	REC	RESTROOM	0.4	20	20	3
4	REC	LOUVER MOTORS	1.0	20	20	4
5	REC	LOUVER MOTORS	1.0	20	20	5
6	REC	UNIT HEATER CONTROL/FAN	0.2	20	20	6
7	REC	WTP RES LV IND PNL	0.1	20	20	7
8	REC	SPACE	-	20	20	8
9	REC	SPACE	-	20	20	9
10	REC	SPACE	-	20	20	10
11	REC	SPACE	-	20	20	11
12	REC	SPACE	-	20	20	12
13	REC	SPACE	-	20	20	13
14	REC	SPACE	-	20	20	14
15	REC	SPACE	-	20	20	15
16	REC	SPACE	-	20	20	16
17	REC	SPACE	-	20	20	17
18	REC	SPACE	-	20	20	18
19	REC	SPACE	-	20	20	19
TOTAL			6.6	55	55	
LARGEST MOTOR - (LOUVER)			1.0	20	20	
OTHER MOTORS			1.2	1.00	1.3	
LIGHTS			2.5	1.25	3.2	
MISC			1.9	1.00	1.9	
TOTAL			6.6	55	7.6	
			KVA	AMPS	KVA	AMPS




**PUMP BUILDING  
120V RECEPT. & LIGHTING PLAN**  
SCALE: 1/4"=1'-0"




**OUTDOOR LIGHT CONTROL DIAGRAM**  
N.T.S.



**WTP RESERVOIR LEVEL INDICATION PNL**  
N.T.S.



**OUTDOOR LIGHTING CONTROL PNL**  
N.T.S.



NO.	REVISIONS	BY	DATE

**Wilson Engineering**  
CONSULTING ENGINEERS & SURVEYORS

805 DUPONT STREET #7  
BELLINGHAM, WA 98225  
(206) 733-6100  
FAX: (206) 647-9061

**CASNE ENGINEERING, INC.**  
DESIGNED BY: DMB/VMF  
DRAWN BY: TMC/SKM  
CHECKED BY: KLA

**WHATCOM COUNTY  
WATER TREATMENT PLANT  
PUMP BUILDING POWER & LTG. PLANS**





DATE: July 1992  
SCALE: AS SHOWN  
JOB NUMBER: 92021A  
SHEET: E09 OF 16

ANNUNCIATOR WINDOW ENGRAVING SCHEDULE			
COL	ROW	ENGRAVING (1st LINE / 2nd LINE / 3rd LINE)	INST. No.
1	1	RAW WATER / PUMP 1 / FAIL	YAL-111
1	2	RAW WATER / PUMP 2 / FAIL	YAL-121
1	3	RAW WATER / LOW FLOW / SHUTDOWN	FALL-105
1	4	RAW WATER / HIGH / TURBIDITY	AAHL-106
1	5	RAW WATER PUMP / SUMP / HIGH LEVEL	LAHL-107
1	6	FLOC. TANK / HIGH / LEVEL	LAHL-201
2	1	FILTER 1 / LOW / LEVEL	LALL-313
2	2	FILTER 2 / LOW / LEVEL	LALL-323
2	3	FILTER 3 / LOW / LEVEL	LALL-333
2	4	FILTER 4 / LOW / LEVEL	LALL-343
2	5	FILTER 1 & 2 / TOO FREQUENT / BACKWASH	UA-301
2	6	FILTER 3 & 4 / TOO FREQUENT / BACKWASH	UA-302
2	7	FILTER 1 & 2 / HIGH EFFLUENT / TURBIDITY	AAHL-301
2	8	FILTER 3 & 4 / HIGH EFFLUENT / TURBIDITY	AAHL-302
3	1	CLEARWELL TRANSFER / PUMP 1 / FAIL	YAL-411
3	2	CLEARWELL TRANSFER / PUMP 2 / FAIL	YAL-421
3	3	TRANSFER / CLEARWELL / HIGH LEVEL	LAHL-401
3	4	TRANSFER / CLEARWELL / LOW LEVEL	LALL-401
3	5	WTP RESERVOIR / OVERFLOW	LAHAL-501
3	6	WTP RESERVOIR / HIGH / LEVEL	LAHL-501
3	7	WTP RESERVOIR / LOW / LEVEL	LALL-501
3	8	WTP RES LOW / LVL PUMP / SHUTDOWN	LALL-501
4	1	DIVISION 7 / PUMP 51 / FAIL	YAL-511
4	2	DIVISION 7 / PUMP 52 / FAIL	YAL-521
4	3	DIVISION 22 / PUMP 53 / FAIL	YAL-551
4	4	DIVISION 22 / PUMP 54 / FAIL	YAL-541
5	1	FINISHED WATER / HIGH / pH	AAHL-502
5	2	FINISHED WATER / LOW / pH	AAHL-502
5	3	FINISHED WATER / HIGH / CHLORINE RESIDUAL	AAHL-503
5	4	FINISHED WATER / LOW / CHLORINE RESIDUAL	AAHL-503
5	5	FINISHED WATER / HIGH / TURBIDITY	AAHL-505
6	1	CHLORINE / LEAK / DETECTION	AAL-635
6	2	UTILITY / POWER / FAIL	EAL-651
6	3	STAND-BY / GENERATOR / FAIL	YAL-652
6	4	GENERATOR / NOT IN / AUTO	YAL-653
6	5	GEN COMMON ALARM	YAL-652
6	8	ACKNOWLEDGE, RESET & TEST PUSHBUTTONS	-

NOTE: ALL REMAINING WINDOW SHALL BE PROVIDED WITH LIGHT BOXES AND BLANK WINDOWS

**NAMEPLATE ENGRAVING SCHEDULE**


No.	ENGRAVING (1st LINE / 2nd LINE / 3rd LINE)
1	RAW WATER / GALLONS x 1000 FOR BOTH / FI/FQI-101
2	RAW WATER LEAD / PUMP SELECT / HS-106
3	RAW WATER PUMP 1 / P11 / HS-111
4	RAW WATER PUMP 2 / P12 / HS-121
5	FILTER 1 & 2 / BACKWASH SELECT / HS-301 (PUSH TO B/W)
6	FILTER 1 / EFFLUENT VALVE / HS-311A
7	FILTER 1 / BACKWASH VALVE / HS-311B
8	FILTER 1 / SURFACE WASH VALVE / HS-311C
9	FILTER 2 / EFFLUENT VALVE / HS-321A
10	FILTER 2 / BACKWASH VALVE / HS-321B
11	FILTER 2 / SURFACE WASH VALVE / HS-321C
12	TRANSFER CLEARWELL / LEVEL / LI-401
13	FILTER 3 & 4 / BACKWASH SELECT / HS-302 (PUSH TO B/W)
14	FILTER 3 / EFFLUENT VALVE / HS-331A
15	FILTER 3 / BACKWASH VALVE / HS-331B
16	FILTER 3 / SURFACE WASH VALVE / HS-331C
17	FILTER 4 / EFFLUENT VALVE / HS-341A
18	FILTER 4 / BACKWASH VALVE / HS-341B
19	FILTER 4 / SURFACE WASH VALVE / HS-341C
20	WTP RESERVOIR / LEVEL / LI-501
21	CLRWELL XFER LEAD / PUMP SELECT / HS-402
22	CLRWELL XFER PUMP 1 / P41 / HS-411
23	CLRWELL XFER PUMP 2 / P42 / HS-421
24	DIVISION 7 RES / LEVEL / LI-707
25	DIV 7 PUMP 1 / P51 / HS-511
26	DIV 7 PUMP 2 / P52 / HS-521
27	DIVISION 22 RES / LEVEL / LI-722
28	DIV 22 PUMP 1 / P53 / HS-531
29	DIV 22 PUMP 2 / P54 / HS-541
30	FINISHED WATER / pH / AI-502
31	SODA ASH TANK / MIXER / HS-622
32	SODA ASH / PUMP / HS-621
33	ALUM / PUMP / HS-611
34	FINISHED WATER / CHLORINE RES. / AI-503
35	PRE-CHLORINE / VALVE / HS-633
36	FILTER 1 & 2 CL / VALVE / HS-636
37	FILTER 3 & 4 CL / VALVE / HS-637
38	STAND-BY / GENERATOR / YIL-652
39	BACKWASH / FLOW / FLOWTOTAL / FI/FQI-641
40	OPERATOR / IN / TROUBLE



ANNUNCIATOR, SEE ANNUNCIATOR ENGRAVING SCHEDULE

11	21	31	41	51	61
12	22	32	42	52	62
13	23	33	43	53	63
14	24	34	44	54	64
15	25	35	45	55	65
16	26	36	46	56	66
17	27	37	47	57	67
18	28	38	48	58	68

**WATER TREATMENT PLANT CONTROL PANEL ELEVATION**  
SCALE: 1/4"=1"



NO.	REVISIONS	BY	DATE

**Wilson Engineering**  
CONSULTING ENGINEERS & SURVEYORS




805 DUPONT STREET #7  
BELLINGHAM, WA 98225  
(206) 733-6100  
FAX: (206) 647-9061

**CASNE ENGINEERING, INC.**  
DESIGNED BY: DMB/MAC  
DRAWN BY: TEO  
CHECKED BY: KLA

**WHATCOM COUNTY WATER TREATMENT PLANT CONTROL PANEL ELEVATION AND DETAILS**

DATE	SHEET
July 1992	E10
SCALE AS SHOWN	OF
JOB NUMBER 92021A	16

92021E10



NO.	REVISIONS	BY	DATE

**Wilson Engineering**  
CONSULTING ENGINEERS & SURVEYORS

805 DUPONT STREET #7  
BELLINGHAM, WA 98225  
(206) 733-6100  
FAX: (206) 647-9061

**CASNE ENGINEERING, INC.**  
P.O. BOX 7207  
BELLEVUE, WA 98008  
(206) 464-3556

DESIGNED BY: DMB/VMF  
DRAWN BY: TEO  
CHECKED BY: KLA

**WHATCOM COUNTY WATER TREATMENT PLANT MCP SCHEMATIC DIAGRAM**




DATE: July 1992  
SCALE: None  
JOB NUMBER: 92021A

92021E11  
SHEET: E11  
OF: 16

DESIGNED BY: ROBERT J. CASNE  
DRAWN BY: DAVID M. THARP-BLOOM  
CHECKED BY: ROBERT J. CASNE

EXPIRES 4/17/94 EXPIRES 4/17/93

SEE DWG. E15 FOR FLAG NOTES



NO.	REVISIONS	BY	DATE


**Wilson Engineering**  
CONSULTING ENGINEERS & SURVEYORS

805 DUPONT STREET #7  
BELLINGHAM, WA 98225  
(206) 733-6100  
FAX: (206) 647-9061

DESIGNED BY:  
DMB/KLA  
DRAWN BY:  
KO  
CHECKED BY:  
KLA





WHATCOM COUNTY  
WATER TREATMENT PLANT  
MCP SCHEMATIC DIAGRAM

DATE	SHEET
July 1992	E12
SCALE	NONE
JOB NUMBER	92021A
	OF 16



SEE DWG. E15 FOR FLAG NOTES. 92021E12





SEE DWG. E15 FOR FLAG NOTES 92021E13

NO.	REVISIONS	BY	DATE

**Wilson Engineering**  
CONSULTING ENGINEERS & SURVEYORS

805 DUPONT STREET #7  
BELLINGHAM, WA 98225  
(206) 733-6100  
FAX: (206) 647-9061

**CASNE ENGINEERING, INC.**  
P.O. BOX 7207  
BELLINGHAM, WA 98208  
(206) 464-3555

DESIGNED BY: DMB/YMF  
DRAWN BY: KO  
CHECKED BY: KLA



**WHATCOM COUNTY WATER TREATMENT PLANT MCP SCHEMATIC DIAGRAM**

DATE	JULY 1992	SHEET	E13
SCALE	NONE	OF	
JOB NUMBER	92021A		16





TRANSMISSION PUMPS

FIELD OR MCC ← MCP




TRANSMISSION PUMPS

FIELD OR MCC ← MCP





CHEMICAL FEED (CONT.)

FIELD ← MCP



STANDBY GENERATOR



EDRPS 4/17/94 EDRPS 4/17/93

SEE DWG. E15 FOR FLAG NOTES 92021E14

NO.	REVISIONS	BY	DATE

**Wilson Engineering**  
CONSULTING ENGINEERS & SURVEYORS




805 DUPONT STREET #7  
BELLINGHAM, WA 98225  
(206) 733-6100  
FAX: (206) 647-9061

**E**  
CASNE  
ENGINEERING,  
INC.  
P.O. BOX 7207  
BELLINGHAM, WA 98008  
(206) 464-3555

DESIGNED BY:  
DMB/VMF  
DRAWN BY:  
TEO  
CHECKED BY:  
KLA


WHATCOM COUNTY  
WATER TREATMENT PLANT  
MCP SCHEMATIC DIAGRAM

DATE	SHEET
July 1992	E14
SCALE	None
JOB NUMBER	92021A
	16



**FLAG NOTES:**

- 1 CLASS II TRANSFORMER AND GFCI PROTECTION FOR ANY NON-LISTED/LABELED DEVICES. USE AND SIZE AS REQUIRED TO MAINTAIN UL-508 ACCEPTANCE.
- 2 WIRING TO WTP TELEMETRY REMOTE SEE DWG. E16
- 3 MACHINE TOOL TYPE RELAY
- 4 COMMON CONTROL DIAGRAM FOR FILTER 1 & 2 AND 3 & 4 NUMBERS IN ( ) ARE DESIGNATION FOR FILTER 3 & 4.
- 5 SCALE RECORDER FOR 0-1500 GPM PROVIDE CHART PAPER SCALED 0-1500 OR EQUIVALENT.
- 6 FLOW METER HSP & TRANSMITTER PER 16921-2.03.5
- 7 LEVEL SWITCH PER 16921-2.03.1
- 8 LEVEL SWITCH PER 16921-2.03.2 WIDE DIFFERENTIAL FOR LOW LEVEL CUTOFF OF PUMPS.



NO.	REVISIONS	BY	DATE

**Wilson Engineering**  
CONSULTING ENGINEERS & SURVEYORS

805 DUPONT STREET #7  
BELLINGHAM, WA 98225  
(206) 733-6100  
FAX: (206) 647-9061



**CASNE ENGINEERING, INC.**  
P.O. BOX 7207  
BELLINGHAM, WA 98008  
(206) 464-3555

DESIGNED BY: DMB  
DRAWN BY: TEO  
CHECKED BY: RJC


**WHATCOM COUNTY WATER TREATMENT PLANT MCP SCHEMATIC DIAGRAM**

DATE	SHEET
July 1992	E15
SCALE	OF
NONE	16
JOB NUMBER	
92021A	

92021E15



- CONSTRUCTION NOTES:**
- 1 ADD INTERFACE RELAYS IN WATER TREATMENT PLANT TELEMETRY PANEL TO EXISTING OUTPUTS
  - 2 REMOVE EXISTING INDICATORS AND WIRING AS REQUIRED FOR REMOTE INDICATION PROVIDE COVER PLATES FOR REMOVED INDICATOR LOCATIONS
  - 3 EXISTING POINTS TO BE REUSED.
  - 4 EXISTING POINTS RENAMED TO ACCOMMODATE CHANGES
  - 5 NEW POINT REQUIRED THIS PROJECT.
  - 6 PRE-WIRED & PRE-PROGRAMMED PUMP CONTROL, AND NEW HAND-OFF-AUTO SWITCH IN LOCATION PROVIDED ON HEADQUARTERS PANEL
  - 7 NEW POINT INTO PLC FOR DATA LOGGING AND REPORTING PURPOSES ONLY.
  - 8 EXISTING INTRUSION POINT RE-PROGRAM TO OPERATE "FAIL SAFE".
  - 9 ADD PULSE EXTENDERS FOR NEW TELEMETRY FLOW POINTS.



TELEMETRY MODIFICATIONS

DATA LOGGER AND PRINTER

ROBERT J. CASSE  
STATE OF WASHINGTON  
PROFESSIONAL ENGINEER

PHILIP M. THARR-BLOCK  
STATE OF WASHINGTON  
PROFESSIONAL ENGINEER

EXPRES 4/17/94 EXPRES 4/17/93

NO.	REVISIONS	BY	DATE

**Wilson Engineering**  
CONSULTING ENGINEERS & SURVEYORS

805 DUPONT STREET #7  
BELLINGHAM, WA 98225  
(206) 733-6100  
FAX: (206) 647-9061

**CASNE ENGINEERING, INC.**  
P.O. BOX 7207  
BELLINGHAM, WA 98008  
(206) 464-3555

DESIGNED BY: DMB  
DRAWN BY: TEO  
CHECKED BY: KLA

**WHATCOM COUNTY  
WATER TREATMENT PLANT  
TELEMETRY BLOCK DIAGRAM**

DATE: July 1992  
SCALE: NONE  
JOB NUMBER: 92021A

92021E16  
SHEET: E16  
OF: 16

PIPING SYMBOLS

INSTRUMENTATION SYMBOLS

ABBREVIATIONS

MECHANICAL EQUIPMENT SYMBOLS

VALVE & ACTUATOR SYMBOLS

PRIMARY ELEMENT SYMBOLS

FUNCTION IDENTIFICATION

PIPING DESIGNATIONS

INSTRUMENT ABBREVIATIONS

	CENTRIFUGAL PUMP		GRINDER
	SUBMERSIBLE SUMP PUMP		FAN
	VERTICAL PUMP		
	GEAR PUMP		
	ROTARY LOBE PUMP		
	PROGRESSIVE CAVITY PUMP		
	METERING PUMP		
	FAN		
	COMPRESSOR		
	ROTARY LOBE BLOWER		
	LIQUID RING BLOWER OR COMPRESSOR		
	SILENCER		
	INTAKE SCREEN		
	MIXER		
	VARIABLE SPEED DRIVE		
	GENERATOR		
	SIGHT GLASS		
	TANK		

PIPE LINE DEVICE SYMBOLS

	SLUICE GATE (NORMALLY OPEN)
	SLUICE GATE (NORMALLY CLOSED)
	INJECTOR
	FILTER OR SEPARATOR
	CAP OR PLUG
	BLIND FLANGE
	STRAINER
	REDUCER OR INCREASER
	BACK FLOW PREVENTER
	PIPED TO DRAIN
	STATIC MIXER

	GATE VALVE
	GLOBE VALVE
	PLUG VALVE
	BALL VALVE
	BUTTERFLY VALVE
	CHECK VALVE
	BALL CHECK VALVE
	PINCH VALVE
	DIAPHRAGM VALVE
	NEEDLE VALVE
	RELIEF VALVE
	FLOAT VALVE

F.O. - FAIL OPEN  
F.C. - FAIL CLOSED


	PRESSURE REDUCING VALVE
	BACK PRESSURE SUSTAINING VALVE
	VALVE WITH HAND OPERATOR
	SOLENOID OPERATED VALVE
	ELECTRICAL MOTOR OPERATED VALVE
	PISTON OPERATED VALVE
	DIAPHRAGM OPERATED VALVE
	BACK FLOW PREVENTER

	ORIFICE PLATE
	VENTURI OR FLOW TUBE
	AVERAGING PILOT TUBE
	PROPELLER OR TURBINE METER
	MAGNETIC FLOW ELEMENT
	FLUME
	WEIR
	VARIABLE AREA FLOW METER (ROTAMETER)
	RUPTURE DISC
	FLOW STRAIGHTENING VANES
	ANNULAR CHEMICAL SEAL
	DIAPHRAGM CHEMICAL SEAL
	TEMPERATURE WELL
	MAGNETIC FLOW ELEMENT


PROCESS & SIGNAL LINE SYMBOLS

LINE	DESCRIPTION
	EQUIPMENT BOUNDARY
	MAIN PROCESS FLOW (WITH TYPICAL DIRECTION OF FLOW SHOWN)
	SECONDARY PROCESS FLOW
	INSTRUMENT SUPPLY, PROCESS TAPS, NON PROCESS FLOW
	PNEUMATIC SIGNAL (ANALOG)
	ELECTRIC SIGNAL (ANALOG)
	PNEUMATIC SIGNAL (DISCRETE)
	ELECTRIC SIGNAL (DISCRETE)
	CAPILLARY TUBE OR FILLED SYSTEM
	ELECTROMAGNETIC OR SONIC SIGNAL (GUIDED)
	ELECTROMAGNETIC OR SONIC SIGNAL (UNGUIDED)
	SOFTWARE OR DATA LINK
	MECHANICAL LINK
	HYDRAULIC
	ELECTRIC POWER SUPPLY 120VAC, 60HZ U.O.N.

INSTRUMENT LOOP IDENTIFICATION



INSTRUMENT TAG NUMBERS



INSTRUMENT & FUNCTION SYMBOLS

	DISCRETE INSTRUMENT
	MULTIFUNCTION INSTRUMENT WITH SHARED HARDWARE (USED FOR "DISTRIBUTED CONTROL SYSTEMS")
	COMPUTER FUNCTION
	INTERLOCKING OR SEQUENTIAL CONTROL FUNCTION
	PROGRAMMABLE LOGIC CONTROL


NOTE: ANY OF THE ABOVE SYMBOLS MAY BE SHOWN WITH HORIZONTAL BAR(S) TO INDICATE PANEL MOUNTING &/OR OPERATOR ACCESSIBLE

	FACE MOUNTED ON MAIN PANEL OPERATOR ACCESSIBLE
	MOUNTED ON/IN MAIN PANEL OPERATOR INACCESSIBLE
	FACE MOUNTED ON FIELD PANEL OPERATOR ACCESSIBLE
	MOUNTED ON/IN FIELD PANEL OPERATOR INACCESSIBLE
	ASTERISK DENOTES EXISTING INSTRUMENTS


ALS - ALUM SOLUTION	ALT M.V. - ALTITUDE VALVE
BW - SETTLED BACK WASH WATER	CL RES - RESIDUAL CHLORINE
BWW - BACKWASH WATER	F.C. - FAIL CLOSED
C2 - CHLORINE GAS	F.O. - FAIL OPEN
CS - CHLORINE SOLUTION	HDA - HAND-OFF-AUTO
CW - CHLORINATED WATER	I/O - ON/OFF
D - DRAIN	HOR - HAND-OFF-REMOTE
FE - FILTER EFFLUENT	MUX - TELEMETRY MULTIPLEXING
FI - FILTER INFLUENT	OAC - OPEN-AUTO-CLOSE
FTW - FILTER TO WASTE	OOR - ON-OFF-REMOTE
FW - FINISHED WATER	PLC - PROGRAMMABLE LOGIC CONTROLLER
OF - OVERFLOW	TURB - TURBIDITY
NG - NATURAL GAS	
PW - POTABLE WATER	
RW - RAW WATER	
SAS - SODA ASH SOLUTION	
SW - SURFACE WASH	

EQUIPMENT SPECIFICATIONS

Q - FLOW RATE
TDA - TOTAL DYNAMIC HEAD
HP - HORSE POWER



NOTES:



EXPIRES 4/17/94 EXPIRES 4/17/93

NO.	REVISIONS	BY	DATE

**Wilson Engineering**  
CONSULTING ENGINEERS & SURVEYORS

805 DUPONT STREET #7  
BELLINGHAM, WA 98225  
(206) 733-6100  
FAX: (206) 647-9061

**CASNE ENGINEERING, INC.**  
DESIGNED BY: DMB/MAC  
DRAWN BY: TEO  
CHECKED BY: KLA

WHATCOM COUNTY  
WATER TREATMENT PLANT  
SYMBOLS & ABBREVIATION

DATE	JUNE 1992	SHEET	P1
SCALE	NONE	OF	
JOB NUMBER	92021A		5

92021P1

HEADQUARTERS DATA LOGGER

TELEMETRY HEADQUARTERS PANEL



TELEMETRY HEADQUARTERS PLC

WTP TELEMETRY PANEL

WATER TREATMENT PLANT CONTROL PANEL

WATER TREATMENT PLANT PLC

- INTERLOCK/LOGIC NOTES:**
- IN AUTO, LC-201 RUNS PUMP P11 VIA YC-106. IF RUNNING SIGNAL NOT RECEIVED WITHIN 5 SEC., FAIL PUMP & START LAG.
  - P-11 CAN NOT RUN AT THE SAME TIME AS P-12.
  - IN AUTO, LC-201 RUNS PUMP P12 VIA YC-106. IF RUNNING SIGNAL NOT RECEIVED WITHIN 5 SEC., FAIL PUMP & START LAG.
  - P-21 CAN NOT RUN AS THE SAME TIME AS P-11.
  - IF FLOW IS NOT VERIFIED WITHIN 15 SECONDS FROM PUMP CALL, LOW FLOW ALARM IS INITIATED AND LAG PUMP IS CALLED TO START.
  - LEAD PUMP SELECTED VIA HS-106 OR ALTERNATOR.
  - IN AUTO, ALUM PUMP RUNS WHEN EITHER RAW WATER PUMP RUNS.
  - IN AUTO, SODA ASH PUMP RUNS WHEN EITHER RAW WATER PUMP RUNS.
  - RAW WATER PUMP IS "CALLED" WHEN LEVEL DROP BELOW LS-201B AND STOPS WHEN LEVEL RISES ABOVE LS-201A.
  - IN AUTO, YV-633 OPENS WHEN EITHER RAW WATER PUMP RUNS.



NO.	REVISIONS	BY	DATE

**Wilson Engineering**  
CONSULTING ENGINEERS & SURVEYORS

805 DUPONT STREET #7  
BELLINGHAM, WA 98225  
(206) 733-6100  
FAX: (206) 647-9061



DESIGNED BY:  
DMB/MAC


DRAWN BY:  
TEO

CHECKED BY:  
KLA

WHATCOM COUNTY  
WATER TREATMENT PLANT  
RAW WATER PUMPING & FLOCCUATION

DATE	SHEET
July 1992	P2
SCALE NONE	OF
JOB NUMBER 92021A	5

92021P2




**INTERLOCK/LOGIC NOTES:**

- HS-301 SELECTS FILTER BAY 1 & 2 OPERATION
- O=OFFLINE, ALL VALVES CLOSED
- T=HIGH FILTER TURBIDITY FROM AIT-301 INITIATES BACKWASH
- H=FILTER HEADLOSS FROM PSL311/321 INITIATES BACKWASH
- M=MANUAL INITIATION OF BACKWASH FILTER EFFLUENT VALVE CLOSURES UPON REACHING LEVEL CONTROL AS SENSED BY LC-401 (DWG P4)
- HS-302 SELECTS FILTER BY 3 & 4 OPERATION IN THE SAME MANNER AS YC-301
- BOTH FILTER BAYS CANNOT BACKWASH AT THE SAME TIME. 30 MIN DELAY BETWEEN BACKWASHES REQUIRED
- BACKWASH SEQUENCE CONTROL FOR FILTER BAY 1 SHALL BE AS FOLLOWS (ALL VALVE SELECTOR SWITCHES IN "AUTO")
  1. CLOSE YV-311A (EFFLUENT) TIME=0
  2. OPEN YV-311B (SURFACEWASH) TIME+0.5 MIN
  3. OPEN YV-311C (BACKWASH) TIME+2.5 MIN
  4. CLOSE YV-311B TIME+4.5 MIN
  5. CLOSE YV-311C TIME+10.0 MIN
  6. OPEN YV-311A TIME+20.0 MIN
- IF LEVEL DROPS BELOW LSL-313, EFFLUENT VALVE IS CLOSED & LOW FILTER LEVEL ALARM IS INITIATED. FILTER CANNOT RESTART UNTIL RESET (TYPICAL YC-311,321,331,341)
- BACKWASH SEQUENCE CONTROL FOR FILTER BAY 2 SHALL BE AS FOLLOWS (ALL VALVE SELECTOR SWITCHES IN "AUTO")
  1. CLOSE YV-321A (EFFLUENT) TIME=0
  2. OPEN YV-321B (SURFACEWASH) TIME+8.0 MIN
  3. OPEN YV-321C (BACKWASH) TIME+11.5 MIN
  4. CLOSE YV-321B TIME+12.0 MIN
  5. CLOSE YV-321C TIME+19.0 MIN
  6. OPEN YV-321A TIME+20.0 MIN
- BACKWASH SEQUENCE FOR FILTER BAY 3 SAME AS YC-311
- BACKWASH SEQUENCE FOR FILTER BAY 4 SAME AS YC-321
- IN AUTO, YV 636/7 OPENS WHEN FILTER IS ON-LINE

**FLAG NOTES:**

- 1 SET LEVEL TO MATCH LSL-333/343

**FILTER SYSTEM**  
 Q: 5.0 GPM/SQ FT.  
 SURFACE AREA: 73.3 SQ FT.  
 WIDTH (EACH FILTER): 8.0 FT.  
 LENGTH (EACH FILTER): 9' 2" FT.



EXPIRES 4/17/94 EXPIRES 4/17/93

NO.	REVISIONS	BY	DATE

**Wilson Engineering**  
 CONSULTING ENGINEERS & SURVEYORS

805 DUPONT STREET 17  
 BELLINGHAM, WA 98225  
 (206) 733-6100  
 FAX: (206) 647-9061


**CASNE ENGINEERING, INC.**  
 P.O. BOX 7307  
 BELLINGHAM, WA 98208  
 (206) 464-3555

DESIGNED BY:  
 DMB/MAC  
 DRAWN BY:  
 TEO  
 CHECKED BY:  
 KLA


**WHATCOM COUNTY WATER TREATMENT PLANT FILTRATION P & ID**

DATE	July 1992	SHEET	P3
SCALE	NONE	OF	
JOB NUMBER	92021A		5





- INTERLOCK/LOGIC NOTES:**
- LC 401 FILTERS BROUGHT ON-LINE AT 7.38' AND OFF-LINE AT 7.95' VIA YC-301 & YC-302 (DWG P3)
  - LC 402 LEAD PUMP SELECTED VIA HS-402 OR ALTERNATOR. IF PUMP IS NOT RUNNING WITHIN 5 SECONDS, FAIL PUMP & START LAG
  - LC 411 IN AUTO, LC-501 RUNS PUMP P41 VIA YC-402. IF PUMP IS NOT RUNNING WITHIN 5 SECONDS FAIL PUMP & START LAG
  - LC 412 IF CLEAR WELL DROPS BELOW 2.5' VIA LSL-401, PUMP P41 IS SHUT DOWN LEVEL MUST RISE ABOVE 5.0' VIA LS-401B BEFORE PUMP MAY RE-START.
  - LC 413 BOTH PUMPS CAN NOT OPERATE AT THE SAME TIME
  - LC 421 IN AUTO LC-501 RUNS PUMP P41 VIA YC-402. IF PUMP IS NOT RUNNING WITHIN 5 SECONDS, FAIL PUMP & START LAG
  - LC 422 IF CLEARWELL DROPS BELOW 2.5' VIA LSL-401, PUMP P42 IS SHUT DOWN LEVEL MUST RISE ABOVE 5.0' VIA LS-401B BEFORE PUMP MAY RESTART.
  - LC 423 LEAD CLEARWELL TRANSFER PUMP STARTS AT 19.0', STOPS AT 23.5'
  - LC 431 IN AUTO, YV-634 IS OPEN WHEN ANY FILTER EFFLUENT VALVE IS OPEN.




**CHLORINE CYLINDERS**  
 CAPACITY: 150 LBS EACH  
 AUTOMATIC SWITCHOVER VALVES  
 SIZE: -  
 POWER: 115 VAC

**WATER TREATMENT PLANT RESERVOIR**  
 DIAMETER: 40.0'  
 HEIGHT: 25.0'  
 CAPACITY: 220,890 GALLONS  
 MATERIAL: STEEL

**RES. LEVEL INDICATOR PNL**

- OVERFLOW ALARM 328.62 (11.45')
- HIGH LEVEL ALARM 325.67 (8.45')
- TRANSFER PUMP OFF 358.50 (23.5')
- TRANSFER PUMP ON 354.00 (19.0')
- OUTLET DIFFUSER 25" HOLES LOW LEVEL ALARM 342.00 (6.0')
- TRANSMISSION PUMP SHUT DOWN & ALARM 341.00 (5.0')
- EL 336.00'



NO.	REVISIONS	BY	DATE

**Wilson Engineering**  
 CONSULTING ENGINEERS & SURVEYORS


805 DUPONT STREET #7  
 BELLINGHAM, WA 98225  
 (206) 733-6100  
 FAX: (206) 647-9061

**CASNE ENGINEERING, INC.**  
 DESIGNED BY: DMB/MAC  
 DRAWN BY: TEO  
 CHECKED BY: KLA

**WHATCOM COUNTY WATER TREATMENT PLANT CHLORINATION**

DATE	SHEET
July 1992	P4
SCALE NONE	OF
JOB NUMBER 92021A	5

92021P4



NO.	REVISIONS	BY	DATE

**Wilson Engineering**  
CONSULTING ENGINEERS & SURVEYORS


805 DUPONT STREET #7  
BELLINGHAM, WA 98225  
(206) 733-6100  
FAX: (206) 647-9061

**CASNE ENGINEERING, INC.**  
P.O. BOX 7207  
BELLEVUE, WA 98008  
(206) 464-3550

DESIGNED BY:  
**DMB/MAC**  
DRAWN BY:  
**TEO**  
CHECKED BY:  
**KLA**

**WHATCOM COUNTY**  
WATER TREATMENT PLANT  
FINISHED WATER PUMPING & DIST. P & ID


DATE: July 1992  
SCALE: NONE  
JOB NUMBER: 92021A  
SHEET: P5 OF 5




EPWES 4/17/94 EPWES 4/17/93

92021P5






DETAIL A  
EXISTING FOUNDATION DRAINS  
NO SCALE




TYPICAL TRENCH SECTION  
FOR CLAY PIPE



TYPICAL TRENCH SECTION FOR  
CAST IRON-DUCTILE IRON PIPE

ADDITIONAL TOPOGRAPHY  
DATED JAN. 8, 1971

TOPOGRAPHY THIS SIDE  
WAS TRACED FROM WATER  
TREATMENT PLANT TOPOG  
DATED 12-70



NOTE - MIN 24\"/>

SUDDEN VALLEY GRD SYSTEM  
SUDDEN VALLEY DATUM PLANE

DATE OF PRINT  
NOV 27 1974

DESIGNED	RSH	MLP	3-27-72
DRAWN	DEE	RVH	1-18-72
CHECKED	DEE		
SYMBOL	REVISION	BY	APPROVED DATE


CONSULTING ENGINEERS  
PLANNING CONSULTANTS  
GOLF COURSE ARCHITECTS  
GOLF COURSE ENGINEERING  
SOIL MECHANICAL ENGINEERS  
ARCHITECTS & LANDSCAPE ARCHITECTS

HORTON DENNIS & ASSOCIATES, INC.  
DAVID JENSEN ASSOCIATES  
THEODORE S. ROBINSON  
D. A. HOGAN & ASSOCIATES  
DAMES & MOORE  
WILES TAYLOR & CO.


**Sudden Valley**

THE SANWICK CORPORATION


JOB NO.  
2277.6




PUMP VAULT SUMP PLAN (NO SCALE)



PLAN VIEW



TYPICAL TRENCH SECTION (NO SCALE)



DETAIL Y (NO SCALE)

JAN. 6, 1972 INSPECTION NOTES:

1. B BLOCK CUTS FOR EFFLUENT PUMPS VARY FROM 7 3/4" TO 7 7/8" DIA'S
2. PUMP DRAIN INTAKES LOCATED PER KEYSTONE DIAL EXHIBIT NOT THE ONE WHICH IS DIMENSIONED ON PLAN ABOVE. RIGHT ANGLE JOG IN IN-SLAB DRAIN PIPING WAS NOT INTENDED. ALSO, PROTRUDING NIPPLES WERE PLANNED INSTEAD OF SMALL FLOOR DRAINS
3. VIEW PORT IS 4'-0" INSTEAD OF 3'-4" AND THEREFORE EXTENDS INTO CLEARWELL 8 1/2" INSTEAD OF BEING FLUSH
4. VERIFIED THAT ALL CONDUIT FOR KEYSTONE EQUIP. WAS IN PLACE. ONE EXCEPTION, THE CONDUIT LOCATED NEXT TO THE VIEW PORT APPEARS TO BE AN EXTRA 2" CONDUIT WAS USED WHERE 3" IS CALLED FOR ON KEYSTONE DWGS.
5. SUMP PUMP DRAIN PIPE WAS INSTALLED "IN-SLAB" INSTEAD OF "BELOW" AS SHOWN ON THESE DWGS.
6. FORMS NOTED TO BE OUT OF LINE: (1) CLEARWELL LIGHT (2) NORTHERLY 2" SURGE RELIEF PIPE (3) SIDE CLEARANCE OF CONDUIT IN CRE. OVER.
7. FLOOR DRAIN NEAR TRENCH IN CENTER OF BLDG. BELOW GRADE.
8. HATCH COVER WAS 1" BELOW GRADE AND EASTERN EDGE SHOULD BE RECESSED IN WALL
9. CONDUIT CROSS-OVER IS CONSIDERABLY NARROWER THAN INTENDED BUT APPEARS TO BE SATISFACTORY.
10. ENTRANCE OF FLOOR & PUMP DRAIN PIPING INTO TRENCH WAS NOT INSPECTED. PIPE WAS BEHIND TRENCH FORMS & HAD BEEN POURED IN PLACE IN TRENCH WALL. CONSTRUCTION FOREMAN INDICATES PIPES ENTERED TRENCH 8" FROM SLAB SURFACE

ITEMS 6 & 7. WERE CORRECTED 1-7-72.








NOTES:

- FOR LOCATION OF ELECTRICAL CONDUIT IN SLAB, SEE SHT 3, KEYSTONE ENGINEERING DRAWINGS.
- J.R. SMITH OR EQUIV. FLOOR DRAIN (5 PLACES) FOR LOCATION OF DRAINS AND UNDER SLAB PIPING, SEE SHT. 4, KEYSTONE ENGINEERING DRAWINGS
- USE THIS DIMENSION TO SET WALL SPOOL IN PUMP VAULT WALL

DATE OF PRINT NOV 27 1974

INSPECTION REPORT, IN-SLAB PIPING (PRIOR TO CONCRETE POUR) 1-6-72 R.M. [Signature]

DESIGNED: R.I.A.	CHGD. PUMP VAULT PIPING & GENERAL UPDATE	SAW RVM	1-7-72	CONSULTING ENGINEERS PLANNING CONSULTANTS GOLF COURSE ARCHITECT SOIL MECHANICS ENGINEERS ARCHITECTS & LANDSCAPE ARCHITECTS	MORTON DENNIS & ASSOCIATES INC DAVID JENSEN ASSOCIATES THEODORE W. ROBINSON D. A. HOGAN & ASSOCIATES DAMES & MOORE MILLS YANICK & CO	Sudden Valley	the undevelopment of the THE SANWICK CORPORATION SUITE 1200 DENNY BUILDING SEATTLE WASHINGTON 98101	DATE: 12-24-70	WATER TREATMENT PLANT EXTERNAL PIPING DETAILS	JOB NO. 2277.6
DRAWN: T.M.A.	CHGD. CLEARWELL OVERFLOW & PUMP VAULT PIPING	SAW RIA	12-1-71					SCALE AS SHOWN		SHEET NO. 3
CHECKED: R.I.A.	CHANGED RAW WATER INTAKE LINE TO AVOID ROCK	RIA	10-22-71					F. B. NO.		3 of 7




NOTE: FULL COMPACTION MUST BE ATTAINED BETWEEN 4" & 12" PIPES

○ - MEASURED DIMENSIONS SEE INSPECTION NOTES ON SHT 1

DATE OF PRINT NOV 27 1974

INSPECTION REPORT, IN-SLAB PIPING (PRIOR TO CONCRETE POUR) 1-6-72

DESIGNED: RIA	CHGD. CLEARWELL OVERFLOW	ESH	RUM	1-31-72	CONSULTING ENGINEERS PLANNING CONSULTANTS GOLF COURSE ARCHITECT GOLF COURSE ENGINEERING SOIL MECHANICS ENGINEERS ARCHITECTS & LANDSCAPE ARCHITECTS MILES TANICK & CO	HORTON DENNIS & ASSOCIATES INC DAVID JENSEN ASSOCIATES THEODORE G. ROBINSON D. A. HOGAN & ASSOCIATES JAMES B. WOODRE	<b>Sudden Valley</b> the undevelopment of the <b>THE SANWICK CORPORATION</b> SUITE 100 DENNY BUILDING SEATTLE WASHINGTON 98101	DATE: 12-70	<b>WATER TREATMENT PLANT</b> <b>EXTERNAL PIPING DETAILS</b>	JOB NO. 2277.0
DRAWN: SAW	CHGD. PUMP VAULT PIPING & GENERAL UPDATE	SAW	RUM	1-7-72				SCALE: 1/4" = 1'-0"		SHEET NO. 4 OF 7
CHECKED: RIA	CHGD. CLEARWELL OVERFLOW & PUMP VAULT PIPING	RIA	RIA	12-1-71				APPROVED: P. B. MO		
	CHANGED RAW WATER INTAKE LINE TO AVOID ROCK	RIA	RIA	10-22-71						




- IDENTIFICATION LIST**
- 1 FILTER
  - 2 REACTOR
  - 3 BACKLASH CONTROL VALVE
  - 4 EFFLUENT CONTROL VALVE
  - 5 MANUAL SHUT-OFF VALVE
  - 6 SURFACE WASHERS
  - 7 SUMMER PUMP
  - 8 RAW WATER PUMP
  - 9 RATE OF FLOW CONTROL VALVE
  - 10 FLOW METER
  - 11 EFFLUENT PUMP
  - 12 PUMP CONTROL VALVE
  - 13 RELIEF VALVE
  - 14 BY-PASS VALVE
  - 15 ALUM TANK FEED MIXER
  - 16 CAUSTIC
  - 17 PE TANK FEED
  - 18 SERVICE PANEL ROOM
  - 19 MOTOR CONTROL CENTER
  - 20 FILTER CONTROL CENTER
  - 21 TURBIN METER
  - 22 SUCTION TRAP
  - 23 SAMPLE PUMP
  - 24 CLEARWELL VALVE CONTROL
  - 25 VACUUM RELIEF
  - 26 CLEARWELL VALVE
  - 27 SURGE CONTROL
  - 28 CHLORINATION ROOM
  - 29 CHLORINE


REV. NO. 1 - ADD CHLORINATOR

**KEYSTONE ENGINEERING**

11/16/70  
 18'-0"  
 10'-0"  
 10'-0"




**DETAIL B**  
EFFLUENT PUMP PADS




**PAD DETAIL**  
TYPICAL 4 PLACES

**DETAIL C**  
SCALE: 1"=1'-0"  
2 REQ'D  
NOTE: ANCHOR BOLTS TO BE CAST IN SLAB.




**LOSS OF HEAD SWITCH PIPING ASSY**  
NOTE: ALL PIPE & FITTINGS TO BE 1/2" BRASS



NOTE: PIPING FOR BOTH VALVES TO BE IDENTICAL

- CODE:
- 1 X47A EJECTOR
  - 2 CK2 COCK
  - 3 C53S SOLENOID
  - 4 100KR HYTROL
  - 5 BELL REDUCER 3/8" x 1/2"
  - 6 CFM2 MODULATING FLOAT CONTROL

**FILTER RATE CONTROL VALVE ASSY**




**SECTION D-D** SHT #1


REVISED  
1-31-70

REV #1	CHG'D PAD DIM.	1-29-70
<b>KEYSTONE ENGINEERING AND PRODUCTS CO., INC.</b>		
DATE	2/4/70	MISC. DETAILS
PROJECT	10MGD WATER TREATMENT PLANT	
BY		SUDDEN






SECTION A-A




SECTION B-B







SECTION C-C

REVISED  
 BY: J. M. S. L. S.  
 DATE: 12/1/72




<b>KEYSTONE ENGINEERING AND PRODUCTS CO., INC.</b>		
DATE: 1/23/70	SECTIONAL DETAILS	72
BY: J. M. S. L. S.	LONG-DURATION TEST	
CHK: B. G.	SUBJECT:	
APP: J. D.		




*Interlock*




- PARTS LIST & IDENT**
- FTC-TIME DELAY RELAY-EAGLE SIGNAL-HD32A622
  - FNR-PUSH BUTTON-FURNAS-BJPI/BJ1
  - FHR-HOLDING RELAY-FURNAS-46FB11
  - R-RED LIGHT-FURNAS-BJLD11
  - FS-FLOW SWITCH-MCDONNELL-FS4-3F
  - ICR-INLET CONTROL RELAY-EAGLE SIGNAL #22AP5C10A120 W/D101749 BASE
  - CFR-CHEMICAL FEED RELAY-FURNAS-46FB40
  - FCR-FILTER CONTROL
  - AR-ALARM RELAY
  - IR-INTERRUPT RELAY
  - HR-HOLDING RELAY
  - MR-MONITOR RELAY
  - BFR-BACKWASH FREQ. RELAY
  - TD1-TD2-TIME DELAY RELAY-EAGLE-HD32A622
  - LHC-LOSS OF HEAD SWITCH-BARKSDALE-DITAB
  - SS1-SS2-SS3-SELECTOR SWITCH-FURNAS-BJSC/BJX
  - SS3, SS4, SS5
  - PB1, 2, 3-PUSH BUTTON-BJPI/BJ211 BJPI/BK
  - AL1, 2-RED LIGHT
  - MT-MONITOR TIMER-EAGLE-HP59A6-10 HR
  - TM-T4-T20 B/WASH TIMER-EAGLE-MPTA620 WMPB-40 GEAR
  - IFS1, IFS2-INLET FLOAT SWITCH-GEMIS 1500
  - CWFS-CLEARWELL FLOAT SWITCH-ALITOCON ELECTRO M5
  - SP-SAMPLE PUMP
  - RECORDER-RUSTRAX 88/141C



**KEYSTONE ENGINEERING AND PRODUCTS CO., INC.**  
CONTROL LINE & WIRING DIAGRAM  
MCD-WATER TREATMENT PLANT  
SUDEN VALLEY, INC.



- ② TO CLEARWELL FLOAT SWITCH CWFS1 [REPLACE CWFS1 LEVEL SWITCH WITH 3CE1 AT LINE 9 ON KEYSTONE ENG. DRAWING]
- ③
- ④ CONTACTS TO BE WIRING TO DATE LOCK IN THE P&ID FOR CLARIFICATION ON WIRING PARALLEL ACTION MAY BE
- ⑤ TO FCB2 IN EXISTING CONTROL PANEL TO CONTROL SV-3 [K.E. DRW. LINE #11, 12]
- ⑥ DRY CONTACTS FOR SAMPLE PUMP - POWERED VIA EXISTING POWER SUPPLY
- ⑦
- ⑧ FILTER #3 LOW LEVEL SWITCH LL103 N.O.
- ⑨ SV8 EFFLUENT SOLENOID VALVE - FILTER #3
- ⑩ SV9 EFFLUENT SOLENOID VALVE - FILTER #4
- ⑪ FILTER #4 LOW LEVEL SWITCH LL104 N.O.
- ⑫ HEADLOSS SWITCH HL103 - FILTER #3
- ⑬ HEADLOSS SWITCH HL104 - FILTER #4
- ⑭ TO NO. 1 R. CONTACTS IN EXISTING CONTROL PANEL [K.E. DRW. LINE #5] - DRY CONTACTS REQUIRED -
- ⑮ EFF. TURB. LATCHING RELAY (1, 15, 16, 26)
- ⑯ HIGH EFF. TURB.
- ⑰ RAW WATER TURB. LATCHING RELAY (10, 20, 26)
- ⑱ HIGH RAW WATER TURB.
- ⑲ DRY CONTACTS TO REMOTE EFFLUENT TURBIDITY ALARM CIRCUIT
- ⑳
- ㉑ DRY CONTACTS TO REMOTE RAW WATER TURBIDITY ALARM CIRCUIT
- ㉒



- ① NO DRY CONTACTS FROM IR RELAY IN EXISTING CONTROL PANEL [K.E. DRW. LINE #7]
- ②
- ③ CONTACTS TO BE PLACED IN SERIES BEFORE ICR RELAY IN EXISTING CONTROL PANEL [K.E. DRW. LINE #1]
- ④
- ⑤ BACKWASH FREQ. TIMER (10 HR.)
- ⑥ BACKWASH FREQ. LATCHING RELAY
- ⑦ TOO FREQ. BACKWASH
- ⑧
- ⑨ SIGNAL TO RECORDER FROM LOW WATER TURBIDITY HIGH PRESS. - FILTER #2 -
- ⑩ SIGNAL TO RECORDER FROM EFFLUENT TURBIDITY - FILTER #2 -
- ⑪
- ⑫ HORN ON CONTROL PANEL (EMERGENCY FEED)
- ⑬
- ⑭ TO HORN ON CONTROL PANEL
- ⑮
- ⑯ TO RECALL WASH IN EXISTING CONTROL PANEL [K.E. DRW. LINE #9]
- ⑰
- ⑱ CONTACTS TO BE USED IN EXISTING CONTROL PANEL [K.E. DRW. LINE #16]
- ⑳

NOTE: REFER TO KEYSTONE ENGINEERING DRAWING D-15720-8-5 SHOWING REQUIRED INTERFACE REVISIONS

NOTE 2: TURBIDITY ALARM CONTACTS LOCATED ON ACTION PANEL 1000'S


NO.	REVISIONS	CHK.	DATE	APP.	DATE

REVISE TURBIDITY LOOP TO INCORPORATE HIGH WATER DO 4.9.98




WATCOM COUNTY WATER DISTRICT No. 10					
WATER TREATMENT EXPANSION ELECTRICAL CONTROL SCHEM.					
OWN. BY:	DEP	DATE:	4-93	APP. BY:	DATE:
JOB NO:	4175	DWG NO:	D-15720-8-5	SCALE:	
ISSUE:		DATE:		REV:	





ITEM LIST	
KEY NO.	DESCRIPTION
1	6" x 6" x 6" TEE FLxFLxFL
2	6" SPOOL FLxPE
3	6" FLANGED COUPLING ADAPTER
4	6" 90° ELBOW FLxFL
5	6" BACKWASH CONTROL VALVE
6	8" x 6" x 8" TEE FLxFLxFL
7	8" BFV
8	8" x 6" 90° ELBOW FLxFL
9	8" 45° ELBOW FLxFL
10	8" FLANGED COUPLING ADAPTER
11	8" SPOOL FLxPE
12	8" x 12" 90° ELBOW FLxFL
13	12" FLANGED COUPLING ADAPTER
14	12" SPOOL FLxPE
15	6" FILTER CONTROL VALVE
16	8" INSULATING FLANGE
17	8" BFV




Designed	RD	Approved	<i>[Signature]</i>
Drawn	MN	Scale	3/8" = 1' 0"
Date		Date	FEB. 1985
Checked	GRN	Project No.	W350102

**POOL ENGINEERING, INC.**  
 Consulting Engineers & Surveyors  
 2950 Northrup Way  
 Duluth, Minnesota 55814  
 (218) 822-6444  
 4225 Touhy Ave. #100  
 Kenilworth, Illinois 60149  
 (815) 225-1828


**WATER DISTRICT 10**  
**WATER TREATMENT PLANT**

**PLAN**


1  
2



SECTION A  
SCALE: 3/8" = 1'-0"



FILTER RATE CONTROL VALVE ASSEMBLY  
NOT TO SCALE



SECTION B  
SCALE: 3/8" = 1'-0"



Designed	RD	Approved	[Signature]
Drawn	MN	Scale	AS SHOWN
Date		Date	FEB. 1985
Checked	GRN	Project No.	W350102

**POOL ENGINEERING, INC.**  
Consulting Engineers & Surveyors  
2950 Northrup Way  
Bellevue, Washington 98004  
(206) 822-6464  
1225 Tongass Avenue  
Ketchikan, Alaska 99901  
(907) 225-6626

WATER DISTRICT 10  
WATER TREATMENT PLANT

SECTIONS AND